ἔκδοσις

Typesetting `TEI` `xml`-Compliant Critical Editions

Robert Alessi

mailto:alessi@robertalessi.net

2021/11/21 – v1.4

Contents

List of listings

Abstract

ekdosis is a LuaLaTeX package designed for multilingual critical editions. It can be used to typeset texts and different layers of critical notes in any direction accepted by LuaTeX. Texts can be arranged in running paragraphs or on facing pages, in any number of columns which in turn can be synchronized or not. In addition to printed texts, ekdosis can convert .tex source files so as to produce TEI xml-compliant critical editions. Database-driven encoding under LaTeX then allows extraction of texts entered segment by segment according to various criteria: main edited text, variant readings, translations or annotated borrowings between texts. It is published under the terms of the GNU General Public License (GPL) version 3.

License and Disclaimer

License Applicable to this Document

This release of ekdosis consists of the following source files:
– `ekdosis.ins`
– `ekdosis.dtx`
– `ekdosis.el`
– `Makefile`

1   Introduction

THE READER will find here, by way of introduction, a summarized version of the first part of an article published in the *Journal of Data Mining and Digital Humanities* as a contribution to a Digital Humanities workshop held at Stanford University (April 15, 2019).[1]

The name of this package, ekdosis, derives from a Greek action noun—ἔκδοσις—the meaning of which is: "publishing a book", and also in concrete sense: "a publication, treatise". For us moderns, this term refers to a long tradition of scholarly work consisting in establishing from manuscript evidence the texts of Greek and Latin classics that were handled down through the Middle Ages to the time of the first printed editions. Of course, this definition is extendible to other languages as well. The basic premise is that critical editions exhibit reconstructed texts from manuscript evidence either under the title of the edited text (direct tradition) or from explicit citations or parallel passages or translations in other languages (indirect tradition).

Whether in print or digital, critical editions come with an apparatus criticus in which is mentioned all the evidence that was used to build the edited text. Arguably, it is precisely on this common point that the two kind of editions part ways for reading a traditional, well written apparatus criticus is only meant for experienced readers. Getting oneself familiarized with its many conventional rules is not unrelated to learning a language, equipped with technical terms, grammar rules and style embellishments, which came into existence out of over three centuries of scholarly attainments. Nevertheless, whereas this language is immediately accessible to human mind's ability to use language and interpret conventional symbols, it is quite inaccessible to a computer unless every item of information has been encoded in the rather dumb format that is suited to machines.

---

1. Robert Alessi, "ekdosis: Using LuaLᴬTEX for Producing `TEI xml`-Compliant Critical Editions and Highlighting Parallel Writings," *Journal of Data Mining and Digital Humanities: Collecting, Preserving, and Disseminating Endangered Cultural Heritage for New Understandings through Multilingual Approaches* (Nov. 2020), jdmdh: 6536.

On the other hand, editions in print have their own limitations. For example, every detail that editors of classical texts decide to discard to save space, regardless to its relevance to the purpose of the edition, is lost permanently as in the case of dialectal coloring of ancient books. Furthermore, passages collected as indirect tradition are only available as references in the *apparatus testium* and cannot be referred to the original text. As a result, the reader is refrained from bestowing attention upon major parallel passages to understand better difficult passages.

To conclude on these issues, print publications and digital editions are often contrasted as they belonged to two different worlds.[2] It is commonly said that the content of editions in print is the result of the binding of the book itself as an object, whereas digital editions, in which format and presentation are by definition separated from content, are free from limitations coming from such bindings. To sum up from the foregoing considerations, this statement is likely to be qualified: as already seen above, the apparatus criticus must be looked at as a brilliant production of mind refined by centuries of scholarly tradition—and surely tradition must go on—arguably not as compact paragraphs that require special and painful training to be 'decoded'. On the other hand, what editions in print do not provide are what Donald J. Mastronarde and Richard J. Tarrant have called "actionable texts for use in digital research",[3] namely database-driven texts allowing the reader to select annotations and display or arrange translations, parallel passages or borrowings in a variety of ways.

ekdosis can be seen as an attempt at combining the two approaches.

1.1 Requirements

Please refer to .

1.2 Features

A list of the main features of ekdosis follows:—

(a) *Multilingual critical editions*: ekdosis can be used to typeset any number of texts in any direction accepted by LuaTEX. Running paragraphs of text can be arranged in any number of columns, either on single or facing pages, which in turn can be synchronized or not. ekdosis is also suitable for complex layouts as in the case of Arabic poetry or images where three-way alignment is required, or diagrams, *&c*.

(b) *Apparatus criticus*: Edited texts can receive multiple layers of apparatus, e.g. apparatus criticus (to record variant readings), apparatus fontium (to collect references to texts quoted or cited in the edited text), apparatus testium (to collect testimonia or parallel passages), or any kind of short notes to be printed on the same page as the edited text, *&c*.

(c) `TEI xml` output: ekdosis can be instructed to output both PDF and `TEI xml` files at the same time.

(d) *Database-driven encoding* under LATEX of texts entered segment by segment allows for alignment of parallel texts from multilingual corpora.

Before going into detail, the following simple example will give the reader a general idea of the method of encoding with ekdosis authoritative texts composed of lemmata, in a way that is very close to `TEI xml` encoding:—

---

2. For a good illustration of this point, see Digital Latin Library, "Textual Criticism," https://digitallatin.org/library-digital-latin-texts/textual-criticism, accessed May 24, 2020, "Content, not Display."

3. Donald J. Mastronarde and Richard J. Tarrant, "Review: Guidelines for Encoding Critical Editions for the Library of Digital Latin Texts," Society for Classical Studies (Dec. 4, 2017), https://classicalstudies.org/scs-blog/donald-j-mastronarde/review-guidelines-encoding-critical-editions-library-digital-latin.

Listing 1: The "Peter/John" basic example

```
1  \begin{ekdosis}
2    I
3    \app{
4      \lem{saw}
5      \rdg{met}
6    }
7    my friend \app{\lem{Peter}\rdg{John}} at the station yesterday.
8  \end{ekdosis}
```

PDF output:—

1   I saw my friend Peter at the station yesterday.

_____

1 saw] met   Peter] John

`TEI xml` output:—

```
<p>I
<app>
  <lem>saw</lem>
  <rdg>met</rdg>
</app>my friend
<app>
  <lem>Peter</lem>
  <rdg>John</rdg>
</app>at the station yesterday.</p>
```

As can be seen from listing 1, the edition text is inserted in the `ekdosis` environment (l. 1 to 8). Then two `\app{`⟨*apparatus entry*⟩`}` commands (ll. 3 and 7) contain the lemma (`\lem{`⟨*lemma*⟩`}`), namely the reading that is accepted by the editor, and at least one variant reading (`\rdg{`⟨*reading*⟩`}`, ll. 5 and 7). As the listing shows, the editor is free to lay out the code in a legible manner to the eye: the first lemma above spans several lines whereas the second one is written in sequence without spaces.

In the PDF output, the edition text is printed in the upper part of the page, above the line, and naturally shows the accepted readings. The margins are used for numeration. In the apparatus criticus, below the line, reference to the text is made by specifying the number of the line and if several entries refer to the same line, numbers are not repeated. Instead, entries are separated from one another by a broad horizontal space. Finally, a square bracket is used inside entries to distinguish the lemma from the variant readings.

Furthermore, as said above, if a `TEI xml` output be required, `ekdosis` compiles an additional `.xml` file an excerpt of which is provided above.

2 The Basics of ekdosis

2.1 Loading the Package—General Options

ekdosis is loaded in the preamble like so:—

```
\usepackage{ekdosis}
```

ekdosis may be loaded with five optional 'named arguments' either of which is set using the syntax ⟨*key*⟩=⟨*value*⟩. The description of the optional arguments follows.

⚠ The reader is invited to refer to the relevant sections of this documentation for more information on how to use these options.

layout   `layout=float|footins|keyfloat|fitapp`   ⟨ Default: float ⟩

   (a) `layout=float` By default, layers of critical notes are inserted as floating environments to be printed at the bottom of the pages.

   (b) `layout=footins` This can be set to insert critical notes in the default footnote block which can be considered to be a special kind of float that is printed at the bottom of the pages. In this case, the apparatus criticus will be inserted between regular numbered footnotes, but will carry no footnote mark of its own.

New feature v1.3   (c) `layout=keyfloat` does approximately the same as the default option `layout=float` but uses the keyfloat package[4] to generate the floating environments to be used as containers for critical footnotes. This way, the keys and values provided by this package[5] may be used to achieve such effects as append additional, informative text below the apparatus, draw a line around the apparatus block or change its width.[6]

New feature v1.3   (d) `layout=fitapp` As described below in sect. 11.1 on page 60, "The Oscillating Problem", ekdosis may oscillate indefinitely between different sets of page decisions when one or more apparatus entries attached to the last lines of the edition text on a given page do not fit in the apparatus block. The reader will find in this section of the documentation a detailed account of several ways to circumvent this issue. Alternatively, or rather conjointly with those ways, `layout=fitapp` can be used to instruct ekdosis to scale down the characters of the apparatus block so that the contentious entries can fit. This mechanism uses the "fitting" library provided by the tcolorbox package.[7] When this option is set, the apparatus criticus grows normally until a predefined height is reached. This height is set to `0.5\textheight` by default.[8] From this point on, the apparatus block ceases to grow; rather, the size of the characters is reduced to allow for additional entries. As a consequence of this rationale, the total number of entries on a given page must not be too high. It is therefore advisable to use `layout=fitapp` conjointly with `maxentries` as described below on page 36 and in sect. 11.1 on page 60.

⚠ If used appropriately, this mechanism gives excellent typographical results, notably with complex edition texts of which the entries in the associated apparatus can be quite abundant in number. It may even put an end to the "oscillating problem" in most of the cases. However, as suitable it may be for high quality typeset texts and final, camera-ready copies, its benefit comes at the expense of slowing down the compilation process. Yet looser algorithms can be selected when speed must prevail over quality for intermediate or draft copies.[9]

divs   `divs=ekdosis|latex`   ⟨ Default: ekdosis ⟩

In many occasions, LATEX standard textual divisions do not meet the specific requirements of classical and literary texts, the divisions of which may depend on many different received traditions. ekdosis provides a flexible mechanism in which format and presentation have been carefully separated from content. It is designed to build un-numbered TEI divisions

---

4. Brian Dunn, *The Keyfloat package: Provides a key/value interface for generating floats* (version 2.06) (June 29, 2021), https://ctan.org/pkg/keyfloat.

5. See ibid., sect. 2.3, pp. 13–16.

6. See below, on page 32 for more information.

7. Thomas F. Sturm, *The Tcolorbox package: Coloured boxes, for LaTeX examples and theorems, etc* (version 4.51) (June 14, 2021), https://ctan.org/pkg/tcolorbox, sect. 22, pp. 438–49.

8. Of course, this height can be modified. See below on page 32 for details.

9. See below on page 32 for more information.

allowed to nest recursively.[10] However, if `divs` be set to `latex`, LaTeX standard textual divisions can be used and will be translated into `TEI` numbered `<div>` elements.

⚠ It must be noted that the two styles are mutually exclusive.

`poetry`
New feature v1.2

`poetry═verse`   `Default: not set`

`poetry=verse` instructs **ekdosis** to load and use the facilites supplied by the **verse** package for the typesetting of lines of poetry.[11] The `ekdverse` environment must then be used instead of the `verse` environment that is provided by the **verse** package as described below in sect. 7.2 on page 41.

`parnotes`

`parnotes═true|false|roman`   `Default: not set`

This named argument does not need a value as it defaults to `true` if used. Apparatus criticus typeset by **ekdosis** may contain notes and footnotes. The latter can be laid out as paragraphed notes below the block of critical notes by means of the **parnotes** package. Additionally, `parnotes=roman` prints these footnotes numbered with Roman numerals.

`teiexport`

`teiexport═true|false|tidy`   `Default: not set`

This named argument does not need a value as it defaults to `true` if used. If `teiexport` be set to `true`, ekdosis is instructed to output both PDF and `TEI xml` files at the same time. By default, the `TEI` file will receive the same basename as the `.tex` source file, suffixed with `-tei.xml`. The raw `.xml` file that is produced by **ekdosis** can be further processed by the **tidy** console application.[12] To make this happen, **tidy** must be installed and the `.tex` source file must be compiled with the `--shell-escape` facility so that spawning programs from LaTeX can be allowed.[13]

As an example, the following line loads **ekdosis** and instructs it to output a `TEI xml` file (in addition to the PDF one) and to use **parnotes** to format with Roman numerals the footnotes that are inserted in the apparatus criticus:—

```
\usepackage[teiexport, parnotes=roman]{ekdosis}
```

2.2 Setup

`\ekdsetup`
New feature v1.3

Starting from v1.3, `\ekdsetup` can be used to specify options that affect the general behavior of **ekdosis**. `\ekdsetup` is a preamble-only command. It accepts the following `key=value` options the number of which is expected to increase as **ekdosis** grows:

`showpagebreaks`

`showpagebreaks═true|false`   `Initially: false; Default: true`

This named argument, which defaults to `true` if used without value, has specific marks printed in the margins so as to spot with a rapid cast of the eye the locations of conditional page breaks generated by the `\ekdpb` command described below on page 60. By default, page breaks generated by `\ekdpb` are identified by the string `spb`—for "soft" page break—whereas those generated by `\ekdpb*` are identified by `hpb`—for "hard" page break. Furthermore, when `\ekdpb` triggers no page break, the marker is printed between square brackets, like so: `[spb]`. In this way, inoperative `\ekdpb` can be easily spotted and removed.

`spbmk`

`spbmk═`⟨*string*⟩   `Default: spb`

`spbmk` is used to change the string associated to "soft" page breaks.

`hpbmk`

`hpbmk═`⟨*string*⟩   `Default: hpb`

`hpbmk` is used to change the string associated to "hard" page breaks.

---

10. See below, sect. 10 on page 54.

11. `verse` does not need to be set if the **memoir** class be used. See sect. 7.2 on page 41 for more detail.

12. See http://www.html-tidy.org.

13. See https://texfaq.org/FAQ-spawnprog for more information on how to do this.

As an example, what follows has "soft" page breaks printed in blue and "hard" page breaks printed in red:—

```
\ekdsetup{
  showpagebreaks,
  spbmk = \textcolor{blue}{spb},
  hpbmk = \textcolor{red}{hpb}
}
```

2.3   Using a Configuration File

Complex editions may use a large number of witnesses, sources and scholars. It may also be required to define a multiple-layer apparatus criticus, several text environments to be aligned and quite a number of new commands. ekdosis provides a convenient way to avoid overloading the document preamble: all the settings related to the critical edition can be gathered in a separate configuration file named `\jobname-ekd.cfg`. If such a file can be found, its contents are automatically read and used by ekdosis.

2.4   Witnesses, Hands, Sources, Scholars & Shorthands

Terminology   Strictly speaking, the term "witness" should apply to any manuscript evidence dating back to the Middle Ages used by the editor to establish the edition text. That said, editors often consult many other types of documents, such as modern editions, articles, notes, correspondence and the like, all of which fall into the category of "sources". Furthermore, unpublished conjectures are also taken into account, not to mention the corrections and emendations that are proposed in many places by the editor of the text. As it is necessary to refer to scholars as individuals, "scholars" naturally emerges as a third category.

Any reference that is to be used in the apparatus criticus must be "declared" in the preamble beforehand, namely: manuscript sigla (either for single manuscripts or manuscript families, primary or later hands, *&c.*), abbreviated last names of sources and scholars. To that effect, ekdosis provides the following preamble-only commands:—

\DeclareWitness   **Witnesses**   `\DeclareWitness{`⟨*unique id*⟩`}{`⟨*rendition*⟩`}{`⟨*description*⟩`}[`⟨*options*⟩`]`
This command requires three mandatory arguments enclosed between curly braces used to specify consecutively:
  (a) The unique identifier of the witness to be used both in the `.tex` source file and as an `xml:id` in the `TEI` `xml` output if any.[14]
  (b) The rendition to be used in the printed apparatus criticus, which also will be found within the `<sourceDesc>` element of the `TEI` header where the description of the witness occurs, within a `<abbr type="siglum">` element.
  (c) A basic description of the manuscript to be found in a typical printed Conspectus Siglorum, namely: the name of the manuscript followed by its call number.
Finally, the optional argument of `\DeclareWitness` accepts a comma-separated list of the following "name=value" arguments the first six of which are used to collect items of information to be found within the `<msIdentifer>` element in the `TEI` header:[15]—

settlement   `settlement=`⟨*name*⟩: The name of a city or administrative unit.
institution   `institution=`⟨*name*⟩: The name of an institution such as a university or library.

---

14. See on page 65 for more information.
15. See https://tei-c.org/release/doc/tei-p5-doc/en/html/MS.html#msid for detailed information on these elements.

repository	**repository**=⟨*name*⟩: The name of the repository within which the witness is stored.
collection	**collection**=⟨*name*⟩: The name of a collection of manuscripts.
idno	**idno**=⟨*call #*⟩: Any form of call number.
msName	**msName**=⟨*name*⟩: The name commonly used for the witness.
origDate	**origDate**=⟨*date*⟩: Any form of date used to identify the date of origin for the witness.
locus	**locus**=⟨*locus*⟩: The sequence of folio references where the edition text is found in the
New feature v1.3	manuscript.

To take here one example, a witness such as the *Marcianus Graecus* 269, referred to as manuscript 'M' in the editions, which contains sixty treatises transmitted under the name of Hippocrates, could be declared as follows:[16]—

```
\DeclareWitness{M}{M}{\emph{Marcianus Gr.} 269}[
        settlement=Venice,
        institution=Marciana Library,
        msName=Marcianus Gr.,
        idno=269,
        origDate=s. X,
        locus=fol. 416\textsuperscript{v}-426\textsuperscript{v}]
```

\DeclareHand   **Hands** \DeclareHand{⟨*unique id*⟩}{⟨*base ms.*⟩}{⟨*rendition*⟩}[⟨*note*⟩]
This command requires three mandatory arguments enclosed between curly braces and one optional argument between square brackets used to specify consecutively:—

   (a) The unique identifier of the hand to be used both in the `.tex` source file and as an `xml:id` in the `TEI xml` output if any.[17]

   (b) The unique identifier of the witness the hand is related to. Of course, this witness must have been declared beforehand.

   (c) The rendition to be used in the printed apparatus criticus, which also will be found within the `<handNote>` element of the `TEI` header where the description of the hand occurs, within a `<abbr type="siglum">` element.

   (d) Some further information about the hand.

To continue the preceding example, here is how additions and corrections found in the *Marcianus Gr.* 269 could be declared after this witness has been declared itself:—

```
\DeclareHand{M1}{M}{M\textsuperscript{1}}[Emendatio scribae ipsius]
\DeclareHand{M2}{M}{M\textsuperscript{2}}[Manus posterior]
```

As can be seen, values such as M, M1 and M2 in the `.tex` source file will be printed as M, M^1 and M^2 respectively. Not only the code gains legibility, but also flexibility for simply changing any declared rendition will update corresponding sigla throughout the entire edition.

As a final example, here is how ekdosis would encode information as declared above for the *Marcianus Gr.* 269 should a `TEI` output be required:—

```
<sourceDesc>
  <listWit>
    <witness xml:id="M">
    <abbr type="siglum">M</abbr>
    <emph>Marcianus Gr.</emph>269
    <msDesc>
```

---

16. The locus specified refers to Hippocrates' *Epidemics*, Book 6.
17. See on page 65 for more information.

```
      <msIdentifier>
        <settlement>Venice</settlement>
        <institution>Marciana Library</institution>
        <idno>269</idno>
        <msName>
          Marcianus Gr.
        </msName>
      </msIdentifier>
      <physDesc>
        <handDesc hands="2">
          <handNote xml:id="M1">
            <abbr type="siglum">M
            <hi rend="sup">1</hi></abbr>
            <p>Emendatio scribae ipius</p>
          </handNote>
          <handNote xml:id="M2">
            <abbr type="siglum">M
            <hi rend="sup">2</hi></abbr>
            <p>Manus posterior</p>
          </handNote>
        </handDesc>
      </physDesc>
      <history>
        <origin>
          <origDate>s. X</origDate>
        </origin>
      </history>
    </msDesc></witness>
  </listWit>
</sourceDesc>
```

Sources \DeclareSource{⟨*unique label*⟩}{⟨*rendition*⟩}

\DeclareSource
New feature v1.1

The *Conspectus Siglorum* that is placed ahead of the edition text is traditionally divided into two parts: a) *Codices*, which provides the list of sigla used in the apparatus, b) *Editiones uel Studia*, which provides references to sources, either published or unpublished, which contain conjectures used in the apparatus criticus. \DeclareSource takes two mandatory arguments used to specify consecutively:—

(a) A unique label used in the .tex source file to refer to the work where the conjecture is found.
(b) The rendition to be used in the printed apparatus criticus.

As ekdosis can include and use TEI xml-compliant lists of references,[18] it is advisable to use Bib(LA)TEX labels in the first argument of \DeclareSource. Otherwise, the unique label used to declare the source would point to no xml:id and the TEI xml would not be valid. Likewise, shorthands fields from the bibliographical database can be recalled from within the second argument of \DeclareSource:—

```
\DeclareSource{Wil}{Wilamowitz}
% or for example:
\DeclareSource{Wil}{\citename{Wil}{shorteditor}}
```

---

18. See below sect. 12.7 on page 71.

Scholars \DeclareScholar{⟨*unique id*⟩}{⟨*rendition*⟩}[⟨*options*⟩]

\DeclareScholar
New feature v1.1

Occasionally, it is necessary to refer to a scholar as a person. For example, corrections and conjectures are commonly inserted as self-references to the editor of the text in the apparatus criticus in print with such words as *scripsi*, *addidi*, *correxi* and the like. Other examples come from unpublished conjectures of other scholars found in private libraries. \DeclareScholar takes two mandatory arguments to specify consecutively:—

(a) The unique identifier of the scholar to be used both in the .tex source file and as an xml:id in the TEI xml output if any.[19]

(b) The rendition to be used in the apparatus criticus in print, which also will be found within the <sourceDesc> element of the TEI header where the description of the persons cited occurs, within an <abbr type="siglum"> element.

Finally, the optional argument of \DeclareScholar accepts the following comma-separated list of key-value arguments:—

rawname **rawname**=⟨*name*⟩

rawname refers to a name that is not to be dissected into name part components such as forename, surname and the like. If rawname be used, then ekdosis will ignore the following three optional arguments: forename, surname and addname.

forename **forename**=⟨*forename*⟩

forename refers to first and middle names or initials.

surname **surname**=⟨*surname*⟩

surname stores the last name.

addname **addname**=⟨*additional name*⟩

addname refers to an additional or alternate name by which the scholar is known viz. a Latinized form of the name, a nickname, an epithet or alias.

note **note**=⟨*note*⟩

note may hold any relevant information about the material used by the editor. For example, a note may specify that this material has been found as marginal notes by the hand of the scholar in some edition in print.

\DeclareShorthand

Shorthands \DeclareShorthand{⟨*unique id*⟩}{⟨*rendition*⟩}{⟨*csv list of identifiers*⟩}

This command provides a convenient way to declare *families* of witnesses. It takes three mandatory arguments used to specify consecutively:—

(a) The unique identifier of the family to be used in the .tex source file.

(b) The rendition to be used in the printed apparatus criticus.

(c) A comma-separated list of previously declared witnesses.

As an example, the manuscripts of Caesar's *Gallic War* are divided into two families: α, which includes mss. A, M, B, R, S, L and N, and β, which includes mss. T, f, U and l. Therefore, provided that all these witnesses have been already declared, here is how the two families α and β could be declared:[20]—

```
\DeclareShorthand{a}{α}{A,M,B,R,S,L,N}
\DeclareShorthand{b}{β}{T,f,U,l}
```

Then, symbols a and b can be used in the .tex source file in place of manuscripts that belong to either family.

That said, \DeclareShorthand is not meant to be restricted to declared witnesses. On the contrary, it also applies to any declared sources and scholars by means of

---

19. See on page 65 for more information.
20. These witnesses are used in the example provided below in listing 6 on page 26.

`\DeclareSource` and `\DeclareScholar`. As an example, assuming that a self-reference to the person responsible for the edition has been set in the preamble, an associated shorthand can be defined like so:—

```
1  \DeclareScholar{ego}{ego}[
2      forename=John,
3      surname=Smith,
4      note=Main editor of the text]
5  \DeclareShorthand{egoscr}{\emph{scripsi}}{ego}
```

Then, the shorthand `egoscr` (l. 5) can be used to print in the apparatus criticus the technical term *scripsi* and use at the same time the pointer `#ego` that is expected in the `TEI xml` output file. Detailed examples of this technique will be provided below in .

2.4.1 Printing Formatted Witnesses — Conspectus Siglorum

Once witnesses, hands, scholars and sources have been declared, ekdosis provides two commands to have them printed as declared from their identifiers.

\getsiglum   `\getsiglum{⟨csv list of witnesses or single witness⟩}` behaves exactly as the `wit` optional argument of `\lem` and `\rdg` described below on pages 14 and 15. From a single identifier or from a comma-separated list of identifiers, it returns their formatted counterparts. To return to the example provided on pages 9–10, `\getsiglum{M}` would return M, while `\getsiglum{M1}` would return M^1.

\SigLine   `\SigLine{⟨unique id⟩}` returns from ⟨unique id⟩ used in the first argument of `\DeclareWitness`[21] a line ready to be inserted in a table set to print a Conspectus Siglorum with the following items of information separated by the symbol `&`: the siglum referring to the witness, the contents of the `description` field, followed if applicable by the sequence of folios that refers to the edition text, and the contents of the `origDate` field. An example of how one could print the Conspectus Siglorum of the manuscripts of Caesar's *Gallic War* from the list provided on the preceding page follows:—

Listing 2: Conspectus Siglorum of Caesar's *Gallic War*

```
\begin{xltabular}[c]{0.75\linewidth}{lXl}
  \caption*{\textbf{Conspectus siglorum}}\\
  \multicolumn{3}{c}{\emph{Familia} \getsiglum{a}}\\
  \SigLine{A}\\
  & \getsiglum{A1} \emph{Emendationes scribae ipsius} & \\
  \SigLine{M}\\
  [...]
  \SigLine{N}\\
  \multicolumn{3}{c}{\emph{Familia} \getsiglum{b}}\\
  \SigLine{T}\\
  [...]
  \SigLine{l}\\
\end{xltabular}
```

Conspectus siglorum

Familia α

A	*Bongarsianus* 81	s. IX–X

---

21. See above on page 8.

	A^1 *Emendationes scribae ipsius*	
M	*Parisinus Lat.* 5056	s. XII
B	*Parisinus Lat.* 5763	s. IX–X
R	*Vaticanus Lat.* 3864	s. X
S	*Laurentianus* R 33	s. X
L	*Londinensis* Br. Mus. 10084	s. XI
N	*Neapolitanus* IV, c. 11	s. XII
	Familia β	
T	*Parisinus Lat.* 5764	s. XI
f	*Vindobonensis* 95	s. XII
U	*Vaticanus Lat.* 3324	s. XI
l	*Laurentianus* Riccard. 541	s. XI–XII

2.5 Editing a Single Text

ekdosis Running paragraphs of one single text to be edited should be inserted in the **ekdosis** environment, like so:[22]—

```
\begin{ekdosis}
  Edition text goes here.
\end{ekdosis}
```

\app **Apparatus Entries** \app[type=⟨*type*⟩]{⟨*apparatus entries*⟩}
This command takes one mandatory argument and accepts one optional argument. Once references to be used as witnesses in the apparatus criticus have been declared in the preamble as described in sect. 2.4 on pages 8–11, the \app command is used for inserting entries in the apparatus criticus, either lemmata, readings or notes, like so:—

```
I saw my friend \app{\lem{Peter}\rdg{John}} yesterday.
or:
I saw my friend
  \app{
    \lem{Peter}
    \rdg{John}
  }
yesterday.
```

\app accepts one further optional argument:—

type **type**=⟨*type*⟩   Default: default
As will be described below in sect. 5.3 on page 35, ekdosis initially sets one layer of notes—the **default** layer—in the apparatus criticus. This layer is fit to receive notes related to variant readings from witnesses and sources used by the editor to establish the edition text. Additional layers can be defined to receive other kinds of notes, such as references to texts quoted or cited in the text of the edition (*apparatus fontium*), references to testimonia, or quotations of the edited text by other authors (*apparatus testium*), explanatory notes, and so forth.[23] Once additional layers have been defined and assigned to new 'types', such as 'testium' and the like, these types can be used as values appended to the **type** 'named option'. For more information about inserting notes in multiple-layer apparatus, see sect. 6 on page 36.

---

22. See above listing 1 on page 5.
23. See below, sect. 6.2 on page 37.

Base text and variants As can be seen in the example above, there are two kinds of individual readings: the *lemma*, which contains the base text accepted by the editor, and the *reading*, which contains deviant readings rejected by the editor.

⚐ What follows refers to the notions of "witness", "source" and "scholar" as defined above on page 8.

\lem **Lemmata**   \lem[⟨*options*⟩]{⟨*lemma text*⟩}
As ⟨*lemma text*⟩ is a word or a phrase judged by the editor to be authentic or authoritative, \lem prints it by default both in the edition text and as the first part of a new entry in the apparatus criticus, preceded by the line number where it occurs or a broad space when the entry refers to the same line as the preceding entry. The optional argument of \lem accepts the following comma-separated list of "name=value" arguments:—

wit **wit**=⟨*csv list of witnesses*⟩
While a single witness may be recorded as in wit=A, comma-separated lists of multiple witnesses must obviously be enclosed in curly braces, like so: wit={A,B,C}. It must be noted that witnesses can be grouped by using spaces as separators, like so: wit={A,B,C,␣D,E,F}.

⚐ In the apparatus criticus in print, it is customary to remind the reader of the manuscript groupings by spaces or commas. ekdosis prints spaces by default, but can be instructed to print any other symbol instead.[24]

⚐ Although any unique identifiers or labels used to "declare" sources and scholars as described above on pages 10–11 can also be used as values of the wit optional argument, it is recommended to use sources and resp to refer to either category respectively as described below.

source **source**=⟨*csv list of sources*⟩
New feature v1.1 A "source" refers to any type of document consulted by the editor to establish the edition text. Most commonly, corrections and emendations from previous editions are cited in the apparatus criticus.[25]

resp **resp**=⟨*csv list of scholars*⟩
New feature v1.1 resp refers to scholars responsible for the emendations, conjectures and corrections that are cited in the apparatus criticus.[26]

alt **alt**=⟨*alternate lemma*⟩
While the mandatory argument of \lem, ⟨*lemma text*⟩, is always used to print the edition text in the upper part of the page, ⟨*alternate lemma*⟩, if specified, supersedes what is printed in the related entry of the apparatus criticus. This mechanism is useful in more than one respect. For instance, it can be used to insert abbreviated lemmata in the apparatus criticus, or to introduce an alternate way of writing entries with Latin technical terms in the apparatus criticus as will be demonstrated below in the example provided by listing 3 on page 16.

sep **sep**=⟨*separator*⟩
sep allows to change the symbol used to separate the lemma text from deviant readings, which is by default the closing square bracket (])

nosep **nosep**=true|false
This named argument does not need a value as it defaults to true if used. nosep removes the separator mentioned above. Obviously, nosep must be used when for some reason no \rdg command follows a \lem command that has just been used, as shown below in listing 5 on page 23, l. 7.

---

24. See below on page 32 for details.
25. For edition texts used as sources, see examples below in sect. 3 on page 20 and sect. 12.7 on page 71.
26. See detailed examples in sect. 3 on page 20.

nolem   `nolem=true|false`
This named argument does not need a value as it defaults to `true` if used. `nolem` completely removes the lemma text from the related entry in the apparatus criticus.

type   `type=⟨value⟩`
This named argument has no effect on the apparatus criticus of the edition in print, but it is used in the `TEI xml` output to classify the variation recorded in the entry according to some convenient typology. Categories such as lexical, morphological, orthographical and the like may apply. Obviously, `type=emendation` should be restricted to lemma texts and `type=conjecture` to variant readings recorded by means of `\rdg` described below.

num   (no-value argument)
New feature v1.3   `num` takes no value. If used, this argument instructs to print any line number that `ekdosis` may have decided not to print in the apparatus criticus before the lemma text.

nonum   (no-value argument)
New feature v1.3   Compared to `num`, `nonum` does the opposite. If used, any number that `ekdosis` may have decided to print before the lemma text is suppressed.

Finally, four named arguments can be used to insert words at the following specific places in the lemma text:

1 pre Peter post prewit A postwit] John B

pre   `pre=⟨words⟩`
`pre` inserts ⟨*words*⟩ *before* the lemma text.

post   `post=⟨words⟩`
`post` inserts ⟨*words*⟩ *after* the lemma text.

prewit   `prewit=⟨words⟩`
`prewit` inserts ⟨*words*⟩ *before* the list of witnesses.

postwit   `postwit=⟨words⟩`
`postwit` inserts ⟨*words*⟩ *after* the list of witnesses.

\rdg   **Readings**   `\rdg[⟨options⟩]{⟨variant reading⟩}`
As ⟨*reading*⟩ is a word or a phrase judged by the editor to be unsatisfactory or corrupted, `\rdg` prints it by default in the last part of the corresponding entry in the apparatus criticus, after the symbol that is used to separate words of the base text (the lemma text) from words rejected by the editor. The optional argument of `\rdg` accepts a comma-separated list of "name=value" arguments that is almost identical to `\app`. Therefore, emphasis will be placed here only on the differences. The reader is invited to refer to the description provided above on pages 14–15 for more detailed information:—

wit   `wit=⟨csv list of witnesses⟩`

source   `source=⟨csv list of sources⟩`

resp   `resp=⟨csv list of scholars⟩`

alt   `alt=⟨alternate reading⟩`

nordg   `nordg=true|false`
This named argument does not need a value as it defaults to `true` if used. `nordg` completely removes the variant reading from the related entry in the apparatus criticus.

type   `type=⟨value⟩`
Obviously, `type=conjecture` should be restricted to variant readings and `type=emendation` to lemma texts recorded by means of `\lem` described above.

pre   `pre=⟨words⟩`

post	**post**=⟨*words*⟩
prewit	**prewit**=⟨*words*⟩
postwit	**postwit**=⟨*words*⟩
subsep	**subsep**=⟨*subseparator*⟩

New feature v1.4   **subsep** inserts a subseparator to be printed *before* the current entry as described below on page 33. This option is supposed to be used when no subseparator is defined, or when one is defined but for some reason a different subseparator is needed for the current entry.

nosubsep   This argument-less option removes the subseparator from the current entry, provided one has been set by means of **\SetSubseparator**, **\SetApparatus** or **\DeclareApparatus**.[27]

\note **Notes**   **\note[**⟨*options*⟩**]{**⟨*text*⟩**}** or **\note*[**⟨*options*⟩**]{**⟨*text*⟩**}**

\note*   It may happen that editorial notes are needed to record short comments of general nature *between* lemmata and readings. **\note** inserts inline comments while **\note*** places comments below the entire apparatus block. Furthermore, if ekdosis be loaded with the **parnotes** option as described above on page 7, **\note*** will use the **parnotes** package to lay out the notes as an additional paragraph below the apparatus criticus. The optional argument of **\note**/**\note*** accepts the following comma-separated list of "name=value" arguments:—

pre   **pre**=⟨*words*⟩

   pre inserts ⟨*words*⟩ immediately before the note.

post   **post**=⟨*words*⟩

   post inserts ⟨*words*⟩ immediately after the note.

sep   This argument-less option is equivalent to **post=\ekdsep**.[28]

subsep   This argument-less option is equivalent to **pre=\ekdsubsep**.[28]

Under no circumstances is it permitted to insert this command **\note** or **\note*** inside the argument of **\lem** or **\rdg**. **\note**/**\note*** must go *between* these commands. As a general rule, within **\app{}** elements, notes are inserted immediately *after* the lemma or the variant reading they are related to. However, as will be described below in sect. 6.2 on page 37, the command **\note**—with no star appended—that is used to insert explanatory notes or references to sources or testimonia is permitted within the mandatory argument of **\lem{}**, although it is subject to a very strict syntax.

Listing 3 provides an illustration of some of the possibilities afforded by the commands just described:—

Listing 3: The "Peter/John" full example

```
1   \begin{ekdosis}
2     I
3     \app{
4       \lem[wit=A]{saw}
5       \rdg[wit=B]{met}}
6     my friend
7     \app{
8       \lem{Peter}
9       \rdg{John}
10    }
11    at the station yesterday. We were both in a
12    \app{
13      \lem[wit=A]{great}
```

---

27. See on pages 33–34 and sect. 5.3.1 on page 35 for details.
28. See below on page 33 for more information and listing 5 on page 23, ll. 23–5 for an illustrative example.

```
14        \rdg[wit=B]{good}}
15    mood.
16    \app{
17      \lem[wit=A, alt={How nice... said}]{\enquote{How nice to find
18          you here!} he said.}
19      \note*{There are no quotation marks in the mss.}
20      \rdg[wit=B, alt=\emph{om.}]{}}
21    I chuckled to myself, recalling the last time we
22    \app{
23      \lem[wit=A,nolem]{met}
24      \rdg[wit=B, alt={\emph{post} met \emph{add.} there}]{met
25        there}
26      \note*{Ms. \getsiglum{B} provides other additions of this kind.}}.
27 \end{ekdosis}
```

1   I saw my friend Peter at the station yesterday. We were both in a great mood. "How
2 nice to find you here!" he said. I chuckled to myself, recalling the last time we met.

---

1 saw A] met B   Peter] John   great A] good B   **1–2** "How nice... said A]ⁱ *om*. B   **2** *post* met *add.* there Bⁱⁱ

ⁱ There are no quotation marks in the mss.   ⁱⁱ Ms. B provides other additions of this kind.

REM. 1 Close examination of lines 17–8 from listing 3 on the previous page shows how `alt` has been used to insert an abridged lemma text in the apparatus criticus in print while keeping safe what is to be found in the `TEI xml` output.

REM. 2 The same technique has been used at line 24 to insert alternate words, including Latin technical terms, in place of the variant reading. Hence the use of `nolem` at line 23 to remove the lemma text from the apparatus criticus in print.

REM. 3 `\note*` has been used to insert short annotations in two places (ll. 19 and 26).

REM. 4 For an example of the use of `nordg`, see below listing 6 on page 26, l. 11.

The corresponding `TEI xml` output produced by `ekdosis` from the LATEX source file follows:—

Listing 4: The "Peter/John" full example: `TEI xml` output

```
<p>I
<app>
  <lem wit="#A">saw</lem>
  <rdg wit="#B">met</rdg>
</app>my friend
<app>
  <lem>Peter</lem>
  <rdg>John</rdg>
</app>at the station yesterday. We were both in a
<app>
  <lem wit="#A">great</lem>
  <rdg wit="#B">good</rdg>
</app>mood.
<app>
  <lem wit="#A">
  <quote>How nice to find you here!</quote> he said.</lem>
  <note>There are no quotation marks in the mss.</note>
  <rdg wit="#B" />
</app>I chuckled to myself, recalling the last time we
<app>
```

```
  <lem wit="#A">met</lem>
  <rdg wit="#B">met there</rdg>
  <note>Ms.
  <ref target="#B">B</ref>provides other additions of
  this kind.</note>
</app>.</p>
```

2.6 Indicating Subvariation in Apparatus Entries

It must be noted that grouping readings so as to keep emphasis on subvariation, regardless of its cause, is entirely optional. Furthermore, the applicability of this technique is limited to the TEI xml output as it helps the machines to understand a grouping otherwise immediately accessible to human mind from the information that is available in well-written apparatus. ekdosis provides two ways of expressing subvariation.

2.6.1 Implicit Grouping

Because apparatus entries may nest recursively, the \app command can be used to group similar readings.

However, for nesting to work, the alt optional argument must be used in every \lem and \rdg command involved in the nesting. This rule applies to both parent and child commands, as demonstrated in the following example:—

```
As I was walking home through Times Square, I saw my friend
\app{
  \lem[wit={A,B}, alt={Peter\---Street}]{Peter at the
    \app{
      \lem[wit=A, alt=station]{station}
      \rdg[wit=B, alt=bookstore]{bookstore}
    }
    on 42nd Street}
  \rdg[wit=C, alt={John on Broadway}]{John on Broadway}
}.
```

PDF output:—

1   As I was walking home through Times Square, I saw my friend Peter at the station on
2 42nd Street.

_____

1 station A] bookstore B **1–2** Peter—Street AB] John on Broadway C

REM. Two \app commands naturally insert two entries in the apparatus criticus. As the subvariation comes first, what ms. C reads is only mentioned in the subsequent entry.

TEI xml output:—

```
<p>As I was walking home through Times Square, I saw my
friend
<app>
  <lem wit="#A #B">Peter at the
  <app>
```

```
    <lem wit="#A">station</lem>
    <rdg wit="#B">bookstore</rdg>
  </app>on 42nd Street</lem>
  <rdg wit="#C">John on Broadway</rdg>
</app>.</p>
```

It must be noted that from a technical standpoint, albeit the nested lemmas are printed *before* their parents in the apparatus criticus, they are seen by ekdosis *after* the latter as the source file is compiled. As a result, notably when the whole nested group of lemmas falls on the same line without being preceded by an apparatus entry on this line, it may be needed to suppress redundant numbers that ekdosis may have decided to print in the appartus criticus. Conversely, it may be needed to print numbers that ekdosis may have decided not to print. To both ends, the `num` and `nonum` optional arguments of the `\lem` command can be used as described above on page 15.

2.6.2 Explicit Grouping

\rdgGrp
New feature v1.1

`\rdgGrp[`⟨*options*⟩`]{`⟨*lemma text | readings*⟩`}`
Explicit grouping of readings can be achieved by means of the `\rdgGrp` command. It takes as mandatory argument the commands used for inserting lemma texts, readings and notes that are described on pages 14–18, viz. `\lem`, `\rdg` and `\note`. `\rdgGrp` accepts one further optional argument:—

type
`type=`⟨*value*⟩
This named argument is used in the `TEI xml` output to define an attribute common to all elements representing the variation.

Here follows how the technique of explicit grouping would apply to the same passage as above:—

```
As I was walking home through Times Square, I saw my friend
\app{
  \rdgGrp[type=subvariation]{
    \lem[wit=A, alt={Peter\---Street}]{Peter at the station
      on 42nd Street}
    \rdg[wit=B, alt={bookstore \emph{pro} station}]{Peter at the
      bookstore on 42nd Street}
  }
  \rdg[wit=C]{John on Broadway}
}.
```

PDF output:—

1   As I was walking home through Times Square, I saw my friend Peter at the station on
2 42nd Street.

1–2 Peter—Street A] bookstore *pro* station B John on Broadway C

> REM. In this example, the subvariation is emphasized with a Latin technical term and may be expressed in one single entry in a more economical manner.

`TEI xml` output:—

```
<p>As I was walking home through Times Square, I saw my
friend
```

```xml
<app>
  <rdgGrp type="subvariation">
    <lem wit="#A">Peter at the station on 42nd
    Street</lem>
    <rdg wit="#B">Peter at the bookstore on 42nd
    Street</rdg>
  </rdgGrp>
  <rdg wit="#C">John on Broadway</rdg>
</app>.</p>
```

3   Emendations and Conjectures

From a technical standpoint, "conjectures" are readings that are not supported by manuscript evidence, but are instead proposed by scholars to be taken into consideration for establishing the edition text. A conjecture is called an "emendation" when it is adopted in place of what is provided by or missing from the text provided by the manuscripts. Emendations and conjectures are therefore readings and as such expected to be found within `<lem>` or `<rdg>` elements. However, as both come from editions or scholars, not from manuscripts, they are naturally associated with `source` or `resp` attributes as described above on page 14,[29] and can be distinguished from one another by the `type` attribute, eg. either `emendation` or `conjecture`.

As an example, the representation of witnesses, editors and shorthands of Hippocrates' *Epidemics*, Book 2 could be summarized as follows:—

```
1   % Witnesses:
2   \DeclareWitness{V}{V}{\emph{Vaticanus Gr.} 276}
3   \DeclareWitness{I}{I}{\emph{Parisinus Gr.} 2140}
4   \DeclareHand{Iac}{I}{I\textsuperscript{ac}}[Lectio ante correctionem]
5   \DeclareHand{Ipc}{I}{I\textsuperscript{pc}}[Lectio post correctionem]
6   \DeclareWitness{R}{R}{\emph{Vaticanus Gr.} 277}
7   \DeclareWitness{H}{H}{\emph{Parisinus Gr.} 2142}
8   % Sources (the first arguments below must refer to biblatex labels and
9   % an xml bibliographical database must be supplied):
10  \DeclareSource{Lit}{Littré}
11  \DeclareSource{Erm}{Ermerins}
12  \DeclareSource{Sm}{Smith}
13  % Persons:
14  \DeclareScholar{ego}{ego}[
15               forename=Robert,
16               surname=Alessi]
17  % Useful shorthands:
18  \DeclareShorthand{codd}{codd.}{V,I,R,H}
19  \DeclareShorthand{edd}{edd.}{Lit,Erm,Sm}
20  \DeclareShorthand{egoscr}{\emph{scripsi}}{ego}
```

As can be seen from lines 18–20, three useful shorthands have been defined: `codd` prints "codd." for Latin pl. *codices* viz. "all manuscripts" and refers to the three `xml` identifiers V, I, R and H declared at ll. 2–3 and 6–7; `edd` prints "edd." for Latin pl. *editores* viz. "all editors" and refers to the three `xml` identifiers Lit, Erm and Sm declared at ll. 10–12;[30]

---

29. See also on pages 10–11.

30. For detailed information on how to use `\DeclareSource` and insert references to cited works, the reader is invited to refer to sect. 12.7 on page 71.

finally, `egoscr` (l. 20) is used to print the technical Latin term "*scripsi*", "I wrote", to denote a personal conjecture. Then, the `.tex` source file can be structured as follows:—

```
1  \begin{ekdosis}
2    καὶ ἐγίνετο μᾶλλον \app{
3      \lem[wit={V, Ipc,R,H}]{νότῳ}
4      \rdg[wit=Iac]{νότου}
5      \rdg[source=Erm, type=conjecture]{ἐν νώτῳ}}· [...] % conjecture
6
7    εἰ
8    \app{
9      \lem[resp=egoscr, type=emendation]{μὲν} % emendation
10     \rdg[wit=codd, source=edd]{μὴ}
11   } εἴη διὰ ταῦτα [...]
12 \end{ekdosis}
```

Rem. 1 Line 5 introduces a *conjecture* which has been annotated with `type=conjecture` to facilitate its identification. Other optional arguments could have been used, such as `prewit=coni.` or `prewit=falso coni.`, to print explanatory words in the apparatus criticus before the abridged name of the scholar.

Rem. 2 Conversely, line 9 introduces an *emendation* for which the shorthand `egoscr` has been used to print the exact term *scripsi* in the apparatus criticus while keeping `ego` as an `xml:id` for the TEI `xml` output file. Other strategies could have been used. For example, one could have defined a specific shorthand to print nothing in place of `ego` and leave the insertion of technical terms to the `post` optional argument of `\lem`, like so:—

```
% Preamble:
% (\unskip is for removing the space left by the empty 2nd argument
% below.)
\DeclareShorthand{egomute}{\unskip}{ego}

% Document:
  \app{
    \lem[resp=egomute, post=\emph{scripsi}, type=emendation]{μὲν}
    \rdg[wit=codd, source=edd]{μὴ}
  } εἴη διὰ ταῦτα [...]
```

PDF output:—

```
1    καὶ ἐγίνετο μᾶλλον νότῳ· [...]
2    εἰ μὲν εἴη διὰ ταῦτα [...]
```

1 νότῳ V I^pc RH] νότου I^ac ἐν νώτῳ Ermerins   **2** μὲν *scripsi*] μὴ codd. edd.

TEI `xml` output:—

```
<p xml:lang="grc">καὶ ἐγίνετο μᾶλλον
<app>
  <lem wit="#V #Ipc #R #H">νότῳ</lem>
  <rdg wit="#Iac">νότου</rdg>
  <rdg source="#Erm" type="conjecture">ἐν νώτῳ</rdg>
</app>· [...]</p>
<p>εἰ
<app>
  <lem resp="#ego" type="emendation">μὲν</lem>
  <rdg wit="#V #I #R #H" source="#Lit #Erm #Sm">
```

```
  μὴ</rdg>
</app>εἴη διὰ ταῦτα [...]</p>
```

3.1 Editorial Addition and Deletion

ekdosis provides a set of commands to indicate that text has been supplied or removed by conjecture. As regards critical symbols conventionally used for representing emendations, lacunae, omissions, gaps, editorial deletions or additions and the like, ekdosis follows the standards as described by West:[31]—

`<>` text added by conjecture or from a parallel source.

`***` lacuna in the whole textual tradition.

`<***>` conjectured lacuna.

`{}` editorial deletion.

†† text judged by the editor to be corrupt. Note that if only one word be suspect, only one crux is needed.

\SetCritSymbols \SetCritSymbols{⟨*csv list of options*⟩} can be used to change the critical symbols
New feature v1.1 described above. This command accepts the following list of `key-value` optional arguments:—

suppbegin **suppbegin**=⟨*symbol*⟩   Default: <
The opening symbol used to mark the text that is supplied.

suppend **suppend**=⟨*symbol*⟩   Default: >
The closing symbol used to mark the text that is supplied.

delbegin **delbegin**=⟨*symbol*⟩   Default: {
The opening symbol used to mark the text that is deleted.

delend **delend**=⟨*symbol*⟩   Default: }
The closing symbol used to mark the text that is deleted.

sicbegin **sicbegin**=⟨*symbol*⟩   Default: †
The opening symbol used to mark the text that is deemed to be suspect.

sicend **sicend**=⟨*symbol*⟩   Default: †
The closing symbol used to mark the text that is deemed to be suspect.

gapmark **gapmark**=⟨*symbols*⟩   Default: ***
The symbols used to mark lacunae.

keepinapp **keepinapp**=true|false   Default: false
New feature v1.4 This named argument does not need a value as it defaults to **true** if used. By default, the critical symbols used by `\supplied`, `\surplus` and `\sic` described below on the following page are printed in the edition text but removed from the apparatus. `keepinapp` instructs ekdosis to print these symbols in both places.

As an example, what follows sets `[]` for deletions and ... for lacunae:—

```
\SetCritSymbols{
  delbegin = [,
  delend = ],
  gapmark = \dots
}
```

◈ If modified, brackets can be adapted to languages that are written from right to left. To that effect, ekdosis provides a boolean expression `al@rlmode` which is evaluated

---

31. Martin L. West, *Textual Criticism and Editorial Technique* [Applicable to Greek and Latin Texts] (Stuttgart: B. G. Teubner, 1973), 80–2.

as `true` if the writing direction be set from right to left and as `false` otherwise. As the `etoolbox` package is loaded by `ekdosis`, `\ifboolean{al@rlmode}{⟨rtl symbol⟩}{⟨ltr symbol⟩}` can be used to perform the test.

Editorial Addition   `\supplied{⟨text⟩}` is used to mark ⟨text⟩ that is by definition missing from the tradition as supplied by the editor or some other scholar. This command is normally expected in `\lem{}` or `\rdg{}`.

New feature v1.1 — `\supplied`

Editorial Deletion   `\surplus{⟨text⟩}` is used to mark ⟨text⟩ that is deemed to be inauthentic, but nevertheless retained between braces in the edition text as it is transmitted by all witnesses. This command is normally expected in `\lem{}` or `\rdg{}`.

New feature v1.1 — `\surplus`

Crux   `\sic{⟨text⟩}` takes as mandatory argument the text deemed by the editor to be readable but not understandable. `\sic` inserts ⟨text⟩ between cruces while `\sic*` prints only one crux before ⟨text⟩.

New feature v1.1 — `\sic`

Lacuna   `\gap{⟨csv list of options⟩}` indicates that some amount of text has fallen away from the entire tradition. It takes as mandatory argument a comma-separated list of options that can be used to further specify the reason for omission, the unit of measurement, the quantity or the extent, as follows:—

New feature v1.1 — `\gap`

`reason`=⟨*reason*⟩
`reason` gives the reason for omission.

— `reason`

`unit`=⟨*unit*⟩
`unit` provides some regularized measurement, such as `character`, `word`, `line` and the like.

— `unit`

`quantity`=⟨*n*⟩
`quantity` specifies the number of the given unit that comprise the measurement.

— `quantity`

`extent`=⟨*description*⟩
`extent` describes the size, including quantity and unit in a single string of words.

— `extent`

Conjectured Lacuna   Assumably, the conjectured lacuna should be enclosed by `\supplied` and as such contained by `\lem` with `type=emendation` to indicate that the lacuna has been accepted by the editor.
    Examples follow:[32]—

Listing 5: Emendations, conjectures and corrections

```
1   % Preamble:
2   \DeclareShorthand{egomute}{\unskip}{ego}
3
4   % Document:
5   \begin{ekdosis}
6     σχεδὸν \app{
7       \lem[resp=egomute, nosep, post={post σχεδὸν quattuor uerba
8         excidisse uid.}, type=emendation]{\supplied{\gap{reason=lost,
9             unit=word, quantity=4}}}
10    } οὗτοι
11
12    subsidiis magnis \sic*{epicuri} constabilitas
13
14    declinare quis est qui \sic{possit cernere sese}.
15
```

---

32. On the use of `egomute` (l. 2), see above REM. 2 on page 21.

23

```
16    \app{
17      \lem[resp=egomute, type=emendation, nosep, post={ante
18        ὑπογίν.}]{\surplus{καὶ}}
19      \note{deleui e Gal.P}
20    } ὑπογίνονται
21
22    Πάντων δὲ \app{
23      \lem[resp=egomute, type=emendation, nosep]{\supplied{τῶν πυρετῶν}}
24      \note[sep]{addidi (\arb{^gamI`a 'l-.hummayAti}
25        \getsiglum{Gal})}
26      \rdg[nordg, source=Gal]{\arb{al-.hummayAti}}
27      \rdg[wit=codd, source=edd, alt=om.]{}
28    },
29  \end{ekdosis}
```

PDF output:—

```
1    σχεδὸν ⟨***⟩ οὗτοι
2    subsidiis magnis †epicuri constabilitas
3    declinare quis est qui †possit cernere sese†.
4    {καὶ} ὑπογίνονται
5    Πάντων δὲ ⟨τῶν πυρετῶν⟩,
```

---

1 *** post σχεδὸν quattuor uerba excidisse uid.   **4** καὶ ante ὑπογίν. deleui e Gal.P   **5** τῶν πυρετῶν addidi (جَمِيع
الحُمَّيَاتِ Gal.)] om. codd. edd.

TEI xml output:—

```
<p>σχεδὸν
<app>
  <lem resp="#ego" type="emendation">
    <supplied>
      <gap reason="lost" unit="word" quantity="4" />
    </supplied>
  </lem>
</app>οὗτοι</p>
<p>subsidiis magnis
<sic>epicuri</sic> constabilitas</p>
<p>declinare quis est qui
<sic>possit cernere sese</sic>.</p>
<p>
<app>
  <lem resp="#ego" type="emendation">
    <surplus>καὶ</surplus>
  </lem>
  <note>deleui e Gal.P</note>
</app>ὑπογίνονται</p>
<p>Πάντων δὲ
<app>
  <lem resp="#ego" type="emendation">
    <supplied>τῶν πυρετῶν</supplied>
  </lem>
  <note>addidi (
```

```
  <foreign xml:lang="ar-Latn" type="transliterated"
  subtype="arabtex">^gamI`a 'l-.hummayAti</foreign>
  <ref target="#Gal">Gal.</ref>)</note>
  <rdg source="#Gal">
    <foreign xml:lang="ar-Latn" type="transliterated"
    subtype="arabtex">al-.hummayAti</foreign>
  </rdg>
  <rdg wit="#V #I #R #H" source="#Lit #Erm #Sm" />
</app>,</p>
```

4   Alignment of Parallel Texts

As already said above,[33] ekdosis can arrange sundry texts in parallel columns—synchronized or not—either on the same page or on facing pages. Depending on what is needed, any text can be equipped with an apparatus criticus. The most common example is that of an edition of a classical text with an apparatus criticus accompanied by a translation into a modern language on the facing page. One can also imagine an edition of two classical texts or two different recensions of the same text, each of which provides variants recorded in separate apparatus criticus, laid out on the left-hand pages, with one or more translations on the corresponding right-hand pages, and so forth.

The `alignment` Environment   \begin{alignment}[⟨*options*⟩]...\end{alignment}
This environment can be used as it is provided to typeset a standard critical edition, namely an edition text, equipped with an apparatus criticus and laid out on the left-hand pages, accompanied by a translation into a modern language on the facing pages.

Within `alignment`, two environments are available by default: \begin{edition} ...\end{edition} and \begin{translation}...\end{translation}. Obviously, the former is used to typeset the edition text with an apparatus criticus on the left, while the latter is used to typeset the translation on the right, like so:—

```
\begin{alignment}
  \begin{edition}
    First § of the edition text.
  \end{edition}
  \begin{translation}
    First § of the translation.
  \end{translation}
  \begin{edition}
    Second § of the edition text.
  \end{edition}
  \begin{translation}
    Second § of the translation.
  \end{translation}
\end{alignment}
```

Furthermore, so-called "starred" versions of these environments can be used at any point to synchronize texts, that is to print them in such a way that the tops of all paragraphs are vertically aligned. To that effect, it must be noted that merely applying this command on a single environment—for instance the leftmost one—will have all other associated paragraphs printed aligned.

33. See point (a) on page 4.

⚠ While the whole edition text and the whole translation can be inserted in a single **edition**/**translation** environment respectively, it is recommended to enter both texts paragraph by paragraph as shown in the example above. Not only this method of encoding allows not to lose sight of paragraphs that are meant to be read together, but it is also the only way to align paragraphs in print, and it is much more suitable to mark up correspondence between spans of texts.

As an illustration, a short extract of Caesar's *Gallic War*, VI, XIII.1 follows.[34] See the list of sigla for manuscripts and manuscript families above on page 11. As this document is not set for duplex printing, both texts have been put together on the same page. However, the reader will find the full `.tex` source file in and `TEI xml` output in . The corresponding PDF output is available in a separate file:[35]—

Listing 6: Caesar's *Gallic War*, VI, 13.1

```
1   \begin{alignment}
2     \begin{edition}
3       \ekddiv{head=XIII, depth=2, n=6.13, type=section}
4       In omni Gallia eorum hominum qui \app{
5         \lem[wit=a]{aliquo}
6         \rdg[wit=b, alt=in al-]{in aliquo}}
7       sunt numero atque honore genera sunt duo. Nam plebes paene
8       seruorum habetur loco, quae \app{
9         \lem[wit={A,M}, alt={nihil audet (aut et \getsiglum{A1})
10          per se}]{nihil audet per se}
11        \rdg[wit=A1,nordg]{nihil aut et per se}
12        \rdg[wit={R,S,L,N}]{nihil habet per se}
13        \rdg[wit=b]{per se nihil audet}}, \app{
14        \lem[wit=a]{nullo}
15        \rdg[wit=b]{nulli}} adhibetur \app{
16        \lem{consilio}
17        \rdg[wit={T, U}, alt=conc-]{concilio}}.
18    \end{edition}
19    \begin{translation}
20      \ekddiv{head=XIII, depth=2, n=6.13, type=section}
21        Throughout all Gaul there are two orders of those men who are of
22        any rank and dignity: for the commonality is held almost in the
23        condition of slaves, and dares to undertake nothing of itself,
24        and is admitted to no deliberation.
25    \end{translation}
26  \end{alignment}
```

1 XIII. In omni Gallia eorum hominum qui
2 aliquo sunt numero atque honore genera sunt
3 duo. Nam plebes paene seruorum habetur
4 loco, quae nihil audet per se, nullo adhibetur
5 consilio.

XIII. Throughout all Gaul there are two orders of those men who are of any rank and dignity: for the commonality is held almost in the condition of slaves, and dares to undertake nothing of itself, and is admitted to no deliberation.

---

2 aliquo α] in al- β   **4** nihil audet (aut et A¹) per se AM] nihil habet per se RSLN per se nihil audet β   nullo α] nulli β   **5** consilio] conc- T U

---

34. Latin text: Caesar, *Gallic War* (*Guerre des Gaules*), ed. L.-A. Constans (Collection des Universités de France; Paris: Les Belles Lettres, 1987) (originally pub. 1926); English translation: Caesar, *Gallic War*, ed. W. A. McDevitte and W. S. Bohn (Harper's New Classical Library; 1st edn., New York: Harper & Brothers, 1869).

35. On the use of `\ekddiv` (ll. 3 and 20), see below .

Rem. 2 For examples of abbreviations, see ll. 6 and 17.

Finally, the corresponding **TEI xml** output follows:—

```xml
<div xml:id="div-edition_1" xml:lang="la">
  <div type="section" n="6.13">
    <head>XIII</head>
    <p>In omni Gallia eorum hominum qui
    <app>
      <lem wit="#A #M #B #R #S #L #N">aliquo</lem>
      <rdg wit="#T #f #U #l">in aliquo</rdg>
    </app>sunt numero atque honore genera sunt duo. Nam
    plebes paene seruorum habetur loco, quae
    <app>
      <lem wit="#A #M">nihil audet per se</lem>
      <rdg wit="#A1">nihil aut et per se</rdg>
      <rdg wit="#R #S #L #N">nihil habet per se</rdg>
      <rdg wit="#T #f #U #l">per se nihil audet</rdg>
    </app>,
    <app>
      <lem wit="#A #M #B #R #S #L #N">nullo</lem>
      <rdg wit="#T #f #U #l">nulli</rdg>
    </app>adhibetur
    <app>
      <lem>consilio</lem>
      <rdg wit="#T #U">concilio</rdg>
    </app>.</p>
  </div>
</div>
<div xml:id="div-translation_1" xml:lang="en">
  <div type="section" n="6.13">
    <head>XIII</head>
    <p>Throughout all Gaul there are two orders of those men
    who are of any rank and dignity: for the commonality is
    held almost in the condition of slaves, and dares to
    undertake nothing of itself, and is admitted to no
    deliberation.</p>
  </div>
</div>
```

4.1 Alignment of Several Texts

As described above on page 25, the `alignment` environment may receive an optional argument in which the following "name=value" arguments are accepted:—

tcols   `tcols`=⟨*number*⟩   `Default: 2`
`tcols` stores the total number of columns of text to be aligned.

lcols   `lcols`=⟨*number*⟩   `Default: 1`
`lcols` stores the number of columns to be printed on the left-hand page, *out of the total number* of columns specified with `tcols`. As can be seen from the preceding two default

values, `alignment` initially sets two columns of text on facing pages. Of course, for this setting to work properly, one must ensure that the `alignment` environment is started on a left page.

texts   **texts**=⟨*semicolon-separated values*⟩   ┌─────────────────────────────┐
                                                    │ Default: `edition;translation` │
                                                    └─────────────────────────────┘

Depending on the total number of columns that has been specified with `tcols` above, `texts` is then used to define the names of the environments that shall receive edition texts, translations, *&c.* Furthermore, as described on page 25, ekdosis also defines "starred" versions of these environments to be used to synchronize columns so that corresponding paragraphs are printed vertically aligned. Some very important points need to be emphasized in this respect:—

    (a) Only unaccented letters of the alphabet (whatever the case) are allowed to compose the names of LaTeX environments.

    (b) These names must be separated from one another by *semicolons*, as shown in red in the listing below at the end of lines 1 and 2.

         ⚠ The comma at the end of line 3 closes the whole value of `text` and acts as a higher level separator.

    (c) Each name may be followed by a 'suboptional' argument between square brackets which will then be used to insert `TEI xml` attributes in the corresponding `<div>` element. For example,

```
1  texts=latin[xml:lang="la"];
2        english[xml:lang="en"];
3        french[xml:lang="fr"],
```

will be converted into `TEI xml` as follows:—

```
<div xml:id="div-latin_1" xml:lang="la">
...
</div>
<div xml:id="div-english_1" xml:lang="en">
...
</div>
<div xml:id="div-french_1" xml:lang="fr">
...
</div>
```

         ⚠ As can be seen, ekdosis takes care of computing and inserting the `xml:id` attributes which are therefore not accepted in the 'suboptional' arguments of `texts`.

    (d) The names of the environments must be specified in exactly the same order as they are supposed to appear in the print edition, from left to right.

apparatus   **apparatus**=⟨*semicolon-separated values*⟩   ┌──────────────────┐
                                                      │ Default: `edition` │
                                                      └──────────────────┘

Then, the `apparatus` option, just as `texts`, takes a semicolon-separated list of previously defined environments that shall receive at least one layer of apparatus criticus.

paired   **paired**=true|false   ┌──────────────────────────────────┐
                                     │ Default: `true (initially not set)` │
                                     └──────────────────────────────────┘

This named argument does not need a value as it defaults to `true` if used. By default, ekdosis follows the LaTeX page numbering scheme when multiple texts are arranged on facing pages. The `paired` option leaves every right-hand page number unchanged, so that both facing pages hold the same page number.

lineation   **lineation**=page|document   ┌──────────────────┐
                                             │ Default: `document` │
                                             └──────────────────┘

This option applies to edition texts initially set to receive an apparatus criticus. By default, lines are continuously numbered throughout the document. `lineation=page` sets the

numbering to start afresh at the top of each page.

flush   `flush`=`true`|`false`   Default: `false`

This named argument does not need a value as it defaults to `true` if used. This option applies when two or more distinct `alignment` environments are started on the same page. Should this happen, any subsequent `alignment` environment must be set with the `flush` option so that every one of them carry its own apparatus criticus.

    As an example, the alignment of the Latin edition text of Caesar's *Gallic War*, printed on left-hand pages, along with two translations into English and French, printed on right-hand pages, can be set as follows:—

```
\begin{alignment}[tcols=3,
                  lcols=1,
                  texts=latin[xml:lang="la"];
                        english[xml:lang="en"];
                        french[xml:lang="fr"],
                  apparatus=latin,
                  lineation=page]
  \begin{latin}
    Gallia est omnis divisa in partes tres quarum unam incolunt
    Belgae, [...]
  \end{latin}
  \begin{english}
    All Gaul is divided into three parts, one of which the Belgae
    inhabit, [...]
  \end{english}
  \begin{french}
    L'ensemble de la Gaule est divisé en trois parties: l'une est
    habitée par les Belges, [...]
  \end{french}
\end{alignment}
```

\SetAlignment   **\SetAlignment**{⟨*alignment settings*⟩}

If the same alignment settings be shared by several `alignment` environments, common settings can be collected in the argument of **\SetAlignment**, like so:—

```
\SetAlignment{
  tcols=3,
  lcols=1,
  texts=latin[xml:lang="la"];
        english[xml:lang="en"];
        french[xml:lang="fr"],
  apparatus=latin,
  lineation=page
}
\begin{alignment}
  ...
\end{alignment}
```

    \SetAlignment can be used either in the preamble or at any point of the document to set or to modify alignment settings.

4.1.1   Appending Hooks to Environments

\AtBeginEnvironment   Once environments corresponding to texts to be aligned have been defined, it is advisable

to use the `\AtBeginEnvironment{⟨environment⟩}{⟨code⟩}` command to further adjust languages, hyphenation rules, and/or fonts to be applied in each environment. To return to the example provided above, once `\SetAlignment` has been used, the languages can be set as follows:—

```
\AtBeginEnvironment{latin}{\selectlanguage{latin}}
\AtBeginEnvironment{english}{\selectlanguage{english}}
\AtBeginEnvironment{french}{\selectlanguage{french}}
```

4.2 Laying Out Parallel Texts

As ekdosis uses the paracol package for the layout of parallel texts, most of the commands provided by this package apply. In this respect, quite useful are the commands described in sections 7.3 to 7.6 on pp. 15−21 of the documentation of this package.[36]

It must be noted that all these commands are to be inserted *before* the `alignment` environments on which they are supposed to operate.

4.2.1 Columns and Gutters

`\columnratio` **Column Ratio on Single Pages** `\columnratio{⟨r_1, r_2, … , r_n⟩}`, where r_1 refers to the leftmost column, can be used to set the ratio of the columns in relation to each other. Depending on the total number of columns on which one wishes to operate, a comma-separated list of decimal numbers is expected. As an example, `\columnratio{0.6}` will instruct ekdosis to have the first column spread over 60 % of the total width of the text block, minus the total width of intercolumnar gutters.

Column Ratio on Facing Pages `\columnratio` accepts an optional argument which can be used as described above to set the ratio of columns to be printed on right-hand pages, like so: `\columnratio{⟨r_1, r_2, … , r_n⟩}[⟨r_1, r_2, … , r_n⟩]`.

`\setcolumnwidth` **Column Width on Single Pages** `\setcolumnwidth{⟨w_1, w_2, … , w_n⟩}` operates the same way as `\columnratio` described above, except that dimensions are expected instead of ratios. As an example, `\setcolumnwidth{1in}` will have the width of the first column set to 1 in.

Gutter Width Each value accepted by `\setcolumnwidth` can be expressed as a pair as in `\setcolumnwidth{⟨w_1/g_1, w_2/g_2, … , w_n/g_n⟩}` where the character `/` acts as a separator, in which case g_x is used to set the width of the gutter that follows the x^{th} column. As an example, `\setcolumnwidth{1in/0.25in}` will print a 1 in first column, followed by a 0.25 in gutter.

Automatically Computed Values Widths of columns and widths of gutters can be replaced with `\fill` and `\columnsep` respectively. As an example, `\setcolumnwidth{\fill/0.25 in}` will only operate on the width that follows the first column, all remaining values being computed automatically.

---

36. Hiroshi Nakashima, *The Paracol package* (version 1.35) [Multiple columns with texts "in parallel"] (Dec. 31, 2018), http://www.ctan.org/pkg/paracol.

Column and Gutter Width on Facing Pages Just like `\columnratio`, `\setcolumnwidth` accepts an optional argument which can be used to set the width of columns and gutters to be printed on right-hand pages, like so: `\setcolumnwidth{⟨w₁, w₂, ... , wₙ⟩}[⟨w₁, w₂, ... , wₙ⟩]` for columns only, and `\setcolumnwidth{⟨w₁/g₁, w₂/g₂, ... , wₙ/gₙ⟩} [⟨w₁/g₁, w₂/g₂, ... , wₙ/gₙ⟩]` for columns and gutters.

Vertical Rules Vertical rules between columns can be drawn by setting the length of the LaTeX `\columnseprule` register to a non-zero value, like so:—

```
\setlength{\columnseprule}{0.4pt}
```

4.2.2 Marginal Notes

By default, marginal notes that refer to the first column are printed in the left margin, while notes that refer to subsequent columns are printed in the right margin.

\marginparthreshold `\marginparthreshold{⟨n⟩}`, where *n* is an integer, can be used to change the default settings. This command instructs ekdosis that columns of text, up to the n^{th} column included, shall have their marginal notes printed to the left. As a result, to take an example, `\marginparthreshold{0}` will have all marginal notes printed in the right margin. `\marginparthreshold` also accepts an optional argument, namely `\marginparthreshold {⟨n⟩}[⟨n'⟩]`, that can be used to set the threshold for columns printed in right-hand pages.

4.2.3 Regular Footnotes

\footnotelayout By default, regular footnotes are printed at the bottom of the column on which they are called. `\footnotelayout{⟨key-letter⟩}` can be used to change this setting. This command accepts as mandatory argument a key-letter which can be either `c`, `p` or `m`. `c` means *column-wise* footnotes, which is the default value. `p` means *page-wise*: footnotes from all columns are gathered in a single spanning block at the bottom of the page. Finally, `m` stands for *merge*, which means that all footnotes that are called on a given page, including notes that are called outside the `alignment` environment, are printed in a single spanning block at the bottom of the page.

Regular footnotes are printed above the block of critical notes. The respective places of these blocks can be interchanged by just loading the fnpos package in the preamble.[37]

5 Laying Out the Apparatus Criticus

5.1 General Hooks

Some hooks are shared by all layers of notes that are inserted in the apparatus criticus (e.g. sources, testimonia, variant readings &c.)

\SetHooks `\SetHooks{⟨csv list of hooks⟩}` can be used either in the preamble or at any point of the document. The list of accepted hooks at the time of writing follows:—

appfontsize `appfontsize=⟨command⟩`   ⟨ Default: `\footnotesize` ⟩
This option sets the size of the font to be used in the whole apparatus criticus. By default, it is the same as the size used for footnotes.

refnumstyle `refnumstyle=⟨command⟩`   ⟨ Default: `\bfseries` ⟩

---

37. Hiroshi Nakashima, *The Fnpos package* (version 1.0) [Control the position of footnotes on the page] (Sept. 3, 2018), http://www.ctan.org/pkg/fnpos.

refnumstyle can be used to set the family, series or shape of the font used to print references to line numbers in the apparatus criticus. By default, numbers are printed in bold face. As an example, `refnumstyle=\normalfont` will have them printed in the font and shape selected by default for the document, while `refnumstyle=\bfseries\itshape` will have them printed in bold and italic.

postrefnum   `postrefnum=`⟨*command | chars*⟩   Default: ~

`postrefnum` can be used to set what immediately follows the reference to line numbers. By default, it is ~, namely an unbreakable space. As an example, `postrefnum=\hskip 0.5em` will insert a 0.5 em space between the numerals and the beginning of all subsequent notes.

lemmastyle   `lemmastyle=`⟨*command*⟩   Default: not set
New feature v1.2   `lemmastyle` can be used to set the family, series or shape of the font used to print lemma texts in the apparatus criticus. For example, `lemmastyle=\bfseries` will print all instances of lemma text in bold while `lemmastyle=\color{blue}` will print them in blue.

readingstyle   `readingstyle=`⟨*command*⟩   Default: not set
New feature v1.2   `readingstyle` operates in the same way as `lemmastyle` but applies to variant readings.

familysep   `familysep=`⟨*symbol*⟩`|reset`   Default: not set
New feature v1.4   As described above on page 14, multiple witnesses must be recorded in the `wit` optional argument of the `\lem` and `\rdg` commands as comma-separated lists of sigla which can be further grouped into families by inserting spaces as separators just after commas at specific places. **ekdosis** saves and prints these spaces in the apparatus criticus but can be instructed to print any other symbol instead by means of `familysep`. For instance, `familysep={,}` has the separating spaces replaced with commas and `familysep={,\allowbreak}` does the same while further allowing breaks after commas at the end of lines. Finally, `familysep=reset` can be used to restore the default behavior.

initialrule   `initialrule=`⟨*command*⟩   Default: \rule{0.4\columnwidth}{0.4pt} (initially not set)
New feature v1.2   `initialrule` draws a separating rule between the edition text and all subsequent layers of critical notes. Of course, this option only makes sense when multiple-layer apparatus criticus are set. Therefore, it has no effect on single-layer apparatus criticus.

noinitialrule   Default: not set

This is a no-value option. It removes any previously set `initialrule`.

An example of the way these hooks may be used is provided below in listing 7 on page 44.

Option Specific to the `layout=keyfloat` Global Setting[38]

keyparopts   `keyparopts=`⟨*csv options*⟩   Default: empty
New feature v1.3   The comma-separated options that can be used are those described in the documentation of the keyfloat package.[39] As an example, `keyparopts={ft, tr={made with ekdosis}, lw=1.2}` will draw a tight frame around the apparatus block, have the words "made with ekdosis" printed below this block on the right and set its width to `1.2\linewidth`.

Options Specific to the `layout=fitapp` Global Setting[40]

appheight   `appheight=`⟨*dimension*⟩   Default: 0.5\textheight
New feature v1.3   This option is used to change the maximum height up to which the apparatus block is allowed to grow before the size of the characters is reduced to allow for more entries. The value must be a dimension, namely a number followed by a length unit, such as `0.65\textheight`, `18cm` or `6in`.

fitalgorithm   `fitalgorithm=fontsize|hybrid|areasize|squeeze`   Default: fontsize
New feature v1.3   The four algorithms that can be used to have the entries inserted in the apparatus criticus fit to the selected height are presented here from the tightest to the loosest, that is, the

---

38. See above (c) on page 6.
39. Dunn (cf. n. 4), sect. 2.3, pp. 13–5.
40. See above (d) on page 6.

slowest to the fastest.[41] While it is advisable to limit the use of `fontsize` to high quality typesetting for camera-ready copies, `areasize` offers a satisfactory settlement when speed must be given an advantage for intermediate or draft copies. `squeeze` should be avoided as it gives results that are offensive to the sight and unacceptable to any reader.

5.2 Single-Layer Apparatus Criticus

Specific Commands   Single-layer apparatus criticus can be laid out in a variety of ways with the following specialized commands, all of which can be used in the preamble or at any point of the document:—

`\SetLTRapp`   `\SetLTRapp` and `\SetRTLapp` are two argument-less commands to set the direction of `\SetRTLapp` the apparatus criticus, either left-to-right or right-to-left.

`\SetSeparator`   `\SetSeparator{⟨*separator*⟩}` is used to change the separator between lemma texts and variant readings. By default, the separator is a closing square bracket followed by a space (]␣).

`\SetSubseparator`   `\SetSubseparator{⟨*subseparator*⟩}` is used to set or change the "subseparator" be-
New feature v1.4   tween succeeding variant readings. By default, no subseparator is set.

As the subseparator applies to subsequent variant readings only, it is naturally preceded by a breakable space. This space can be removed by `\unskip`. As an example, what follows replaces the breakable space with an unbreakable space, then prints a colon as subseparator followed by a space:—

```
\SetSubseparator{\unskip~: }
```

`\ekdsep`   Once the separator and if applicable the subseparator have been set, they can be
`\ekdsubsep`   accessed by `\ekdsep` and `\ekdsubsep` respectively. It is therefore advisable to use these commands instead of the mere symbols at whatever place one would have them printed.

`\SetBeginApparatus`   `\SetBeginApparatus{⟨*characters|commands*⟩}` can be used to append ⟨*characters*⟩ or ⟨*commands*⟩ at the beginning of the apparatus block. By default, nothing is appended. For instance, `\SetBeginApparatus{\textbf{Apparatus:}}` will append "**Apparatus:**" at the beginning of the apparatus block, while `\SetBeginApparatus{\hskip 1em}` will set an indentation of one em.

`\SetEndApparatus`   `\SetEndApparatus{⟨*characters*⟩}` can be used to append ⟨*characters*⟩ at the end of the apparatus block. By default, nothing is appended. As an example of use, `\SetEndApparatus{.}` will have a period printed at the end of the apparatus as it is customary in some editions.[42]

`\SetUnitDelimiter`   `\SetUnitDelimiter{⟨*delimiter*⟩}` can be used to set the delimiter between entries in the apparatus criticus. By default, there is no delimiter except a simple space. ⟨*delimiter*⟩ can be a broad space (such as `\hskip 0.75em` for instance as in the OCT series) or the divider-sign (‖, as in the Budé series).

`\SetDefaultRule`   By default, `ekdosis` draws a separating line between the edition text and the apparatus criticus. This line is initially defined as `\rule{0.4\columnwidth}{0.4pt}`. `\SetDefaultRule{⟨*line definition*⟩}` can be used in the preamble or at any point of the document to change the default setting. Leaving this argument empty as in `\SetDefaultRule{}` removes the line.

`\SetApparatusLanguage`   `\SetApparatusLanguage{⟨*languagename*⟩}` can be used when it is needed to apply in
New feature v1.2   the apparatus criticus a language different from the one that is selected in the edition text.

`\SetApparatusNoteLanguage`   `\SetApparatusNoteLanguage{⟨*languagename*⟩}` can be used when it is needed to apply
New feature v1.3

---

41. See Sturm (cf. n. 7), 446–9 for details and illustrative examples.
42. See also below on page 62 on how to remove superfluous dots.

in text entries introduced by the mandatory argument of the `\note` command as described in sect. 6.2 on page 37—namely `\note[⟨options⟩]{⟨text⟩}`—a language different from the one that is selected in the edition text.

\SetApparatus **General Command**   `\SetApparatus{⟨csv list of apparatus settings⟩}`

Finally, all the settings described above can also be collected in the argument of `\SetApparatus`. `\SetApparatus` accepts the following list of comma-separated `key=value` options:—

direction `direction=LR|RL`   `Default: LR`

The writing direction of the apparatus criticus, either left-to-right (`LR`) or right-to-left (`LR`).

sep `sep=⟨command | chars⟩`   `Default: ]␣`

The separator between lemma texts and variant readings.

subsep `subsep=⟨command | chars⟩`   `Default: not set`

The "subseparator" between succeeding variant readings.

delim `delim=⟨delimiter⟩`   `Default: not set`

The delimiter between entries in the apparatus criticus. As said above, there is no default delimiter except a simple space.

bhook `bhook=⟨characters|commands⟩`   `Default: empty`

The characters or commands to be appended at the beginning of the apparatus block.

ehook `ehook=⟨characters⟩`   `Default: empty`

The characters to be appended at the end of the apparatus block.[43]

rule `rule=⟨command⟩`   `Default: \rule{0.4\columnwidth}{0.4pt}`

As described above, `rule` is used to draw the separating line between the edition text and the apparatus criticus.

norule   `Default: not set`

`norule` does not accept any value and is used to remove the line.

lang `lang=⟨languagename⟩`   `Default: not set`
New feature v1.2 `lang=<languagename>` is used as described on the preceding page when it is needed to apply in the apparatus criticus a language different from the one that is selected in the edition text. `languagename` can be any value accepted by babel or polyglossia.

notelang `notelang=⟨languagename⟩`   `Default: not set`
New feature v1.3 `notelang=<languagename>` is used as described on the previous page when is needed to apply in text entries introduced by the mandatory argument of the `\note` command as described in sect. 6.2 on page 37—namely `\note[⟨options⟩]{⟨text⟩}`—a language different from the one that is selected in the edition text. `languagename` can be any value accepted by babel or polyglossia.

As an example, an apparatus criticus with references to line numbers printed in normal font, a colon as a separator between lemma texts and variant readings, a broad space as a delimiter between entries and a 0.7 in line above could be laid out as follows:—

```
\SetHooks{
  refnumstyle=\normalfont
}
\SetApparatus{
  sep={: },
  delim=\hskip 1em,
  rule=\rule{0.7in}{0.4pt}
}
```

---

43. See also n. 42 on the previous page.

Footnote Separator As already seen above, ekdosis takes care of drawing a separating line between the edition text and the apparatus criticus. Therefore, it may be not desirable to have the standard LaTeX "footnoterule" printed on every page where regular footnotes are found. \footnoterulefalse removes it while \footnoteruletrue leaves it untouched. The latter is set by default.

5.3 Multiple-Layer Apparatus Criticus

As said above in (b) on page 4, ekdosis can print edition texts equipped with multiple-layer apparatus criticus. To take an example, most classical editions provide at least two layers of notes: one to collect references to testimonia or parallel passages (apparatus testium) and the other to record variant readings (the apparatus criticus *stricto sensu*). The former is always printed above the latter.

The default single-layer apparatus criticus that is described above in sect. 5.2 on page 33 is called `default` internally. If any additional layer of notes be declared in the preamble, this `default` layer must be included in the list of declared layers.

 \SetDefaultApparatus{⟨*name*⟩} can be used at any point of the document to change the name to be used as the default one by ekdosis.

5.3.1 Declaring Additional Layers

 \DeclareApparatus{⟨*name*⟩}[⟨*csv list of apparatus settings*⟩] is a preamble-only command. As a mandatory argument, it takes the name of the new layer of notes to be inserted in the apparatus block. Declared layers are then printed one below the other in the exact same order as they are declared in the preamble. Therefore, one additional layer meant to print the testimonia above the variant readings (apparatus testium) can be declared as follows:—

```
1  % preamble:
2  \DeclareApparatus{testium}
3  \DeclareApparatus{default}
```

In this example, `testium` is a new name for `default`, as said just above, is already known to ekdosis and used as the default layer of notes. Furthermore, as `testium` is declared before `default`, ekdosis will print the testimonia at the top of the apparatus block.

5.3.2 Laying Out Layers With The Optional Argument of \DeclareApparatus

direction
sep
subsep
delim
bhook
ehook
rule
norule
lang
notelang

 With regard to layout, any declared layer inherits the default values described above in sect. 5.2 on page 33. That said, as the optional argument of \DeclareApparatus accepts the exact same `key-value` options as \SetApparatus described on the preceding page, ekdosis provides a straightforward mechanism to have any layer printed in a distinct layout.

To return to the example provided on the previous page, one could keep the same settings as above for the variant readings, declare an apparatus testium with a closing square bracket as a separator and finally remove the line between the testimonia and the variant readings like so:—

```
1  \SetHooks{
2    refnumstyle=\normalfont,
3    initialrule=\rule{0.7in}{0.4pt}
4  }
5  \DeclareApparatus{testium}[
```

```
 6    sep={] },
 7    delim=\hskip 1em,
 8    norule
 9  ]
10  \DeclareApparatus{default}[
11    sep={: },
12    delim=\hskip 1em,
13    rule=\relax
14  ]
```

Rem. 1 The general hook `initialrule` used here (l. 3) is described above on page 32.

Rem. 2 `\relax` (l. 13) is a TEX primitive that instructs to do nothing. Therefore, `rule=\relax` is not strictly equivalent to `norule`: with the former, `\relax` removes the rule but leaves untouched the subsequent carriage return: as a result, the layers are visually separated from one another by a blank line. With the latter everything is removed, carriage return included.

Limiting the Number of Entries per Page   In some instances, it can be useful to set a limit to the number of entries per page that a given layer of critical notes may accept, notably when entries are so abundant in number that ekdosis may oscillate indefinitely between different sets of page decisions without being able to settle down.

maxentries   **maxentries**$=\langle n \rangle$ (where $n \geq 10$)   `Default: not set`

If `maxentries`$=\langle n \rangle$ be set, then ekdosis will issue `\pagebreak` (namely `\penalty-10000`) just after the n^{th} entry has been inserted in the layer of the apparatus criticus this option is related to. As a result, the page will actually break at the end of the current line. The particulars of this technique will be discussed below in sect. 11.1 on page 60.

6   Inserting Notes in Multiple-Layer Apparatus

As said above in sect. 5.3 on the preceding page, ekdosis initially sets one layer of notes that is called the "`default`" layer. As a result, any note inserted within the argument of `\app{}` as described on page 13 will go into that layer of the apparatus, unless `\SetDefaultApparatus` has been used to set another name for the default layer (see above on the preceding page).

6.1   Variant Readings

In most cases, all variant readings go into the "`default`" layer of the apparatus criticus. But in some other cases, for example when the manuscripts used refer to different recensions, it may happen that one wishes to record the related variants in separate layers. As already described on page 13, the `type` optional argument of the `\app` command can be used to insert lemma texts and associated variants in any other 'declared' layer of the apparatus criticus.

The following example assumes that some edition text is received in two different recensions and the variant readings that belong to the first recension are recorded in the default layer of notes while those of the second recension are to be printed in a second layer, below the default one. First, both layers must be declared in the preamble in sequence, like so:—

```
\DeclareApparatus{default} % default layer
\DeclareApparatus{rec2} % additional layer below the default one
```

Should one wish to refer to `rec1` as the default layer, then `\SetDefaultApparatus` must be used, like so:—

```
\SetDefaultApparatus{rec1}
\DeclareApparatus{rec1} % new layer set as default
\DeclareApparatus{rec2} % additional layer below the default one
```

Then, whatever option has been chosen, lemma texts and variants inserted with `\app{}` will go into the upper, default layer of notes, while those inserted with `\app[type=rec2]{}` will go into the lower one:—

```
Some \app{
  \lem{word}
  \rdg{reading}
} to go into the default layer of notes.

Some \app[type=rec2]{
  \lem{note}
  \rdg{comment}
} to be recorded as part of the second recension.
```

At any rate, `type=default` or `type=rec1`, depending on what has been chosen, must be used should the editor wish to retain that information in the `TEI xml` output file.

6.2   Other Notes for Comments, Sources or Testimonia

Additional layers of notes can be used to print short comments or to record references to texts quoted by the author of the edited text or references to the edited text by other authors or translators. The former set is called an *apparatus fontium* while the latter is called an *apparatus testium*.

From a technical standpoint, these notes are very different from the short editorial notes inserted between lemma texts and variant readings that have been described above on page 16. However, for the sake of consistency with `TEI xml` encoding, ekdosis uses the same command `\note` to insert both kinds of notes.

One must also keep in mind that the notes that are described in this section refer either to a single word or to a span of text. By consequence, as boundaries must always be set outside spans of text, notes must be inserted immediately before the word or words they are related to. As a result of this rule, all spaces subsequent to `\note` are ignored.

\note   `\note[`⟨*options*⟩`]{`⟨*text*⟩`}`
As said above, `\note`, when found outside `\app{}`, is used to insert in additional layers of the apparatus short comments or references to texts quoted or cited in the edition text. It accepts the following comma-separated list of `key-value` optional arguments:—

type   `type=`⟨*type*⟩
`type` is used to specify the name of the layer where the note is to be printed.[44]

sep   `sep=`⟨*command | chars*⟩
The separator between the lemma text and the contents of the note.

nosep   `nosep=true|false`
This named argument does not need a value as it defaults to `true` if used. Obviously, `nosep` removes the separator mentioned above.

lem   `lem=`⟨*lemma text*⟩
`lem` is the span of text the note is about. It may consist of one or more words, or of an abridged lemma text.

num   (no-value argument)

New feature v1.3
───────────────────────
44. See to learn how to declare and lay out new layers of notes.

num takes no value. If used, this argument instructs to print any line number that ekdosis may have decided not to print in the apparatus criticus before the note.

nonum (no-value argument)

Compared to **num**, **nonum** does the opposite. If used, any number that ekdosis may have decided to print before the note is suppressed.

labelb **labelb**=⟨*label*⟩ [Mandatory]

labelb is the unique label to serve as a reference for the point immediately preceding the lemma text.

> **labelb** is used by ekdosis to print the line numbers in the apparatus criticus and to set the **left()** XPointer should **TEI** output be required. Therefore, it must be specified. Otherwise, ekdosis will issue an error message. However, two strictly consecutive **\note** commands are allowed to share the same **labelb** value for it may happen that consecutive notes need to refer to spans of text that begin at the exact same location. In this case, ekdosis generates only one **\linelabel** and one corresponding **<anchor>** element in the **TEI xml** file.

labele **labele**=⟨*label*⟩

labele is the unique label to serve as a reference for the point immediately following the lemma text. Contrary to **labelb**, **labele** may be left unspecified if the note be only about one word. If the note be about a span, then **labele** must be specified.

\linelabel **\linelabel{**⟨*label*⟩**}**

If **labele**=⟨*some_label*⟩ be specified in the optional argument of **\note**, **\linelabel{**⟨*some _label*⟩**}** must be inserted immediately after the span of text that the note is about so that ekdosis can locate the exact point where the lemma text addressed by the note ends, like so:—

```
% Preamble:
% \DeclareApparatus{fontium}[
%          delim=\hskip0.75em,
%          bhook=\textbf{Sources:},
%          ehook=.]
% \DeclareApparatus{default}[
%          delim=\hskip0.75em,
%          ehook=.]
% Document:
\begin{ekdosis}
  The oldest monument of the Germans is their language, which, before
  untold centuries, was the companion of their travels from central
  Asia; a language, copious, elastic, inviting self-explaining
  combinations and independent development; lending itself alike to
  daily life and imagination, to description and abstract thought.
  \note[type=fontium, labelb=B61e, labele=B62a, lem={They
    had... slave}]{Waitz, \emph{Deutsche Verfassungs Geschichte},
    i. 86} They had a class of nobles, but their tongue knew no word
  for slave.\linelabel{B62a}\footnote{George Bancroft, \emph{History
      of the United States from the Discovery of the American
      Continent}, II.61--2.}
\end{ekdosis}
```

PDF output:—

1   The oldest monument of the Germans is their language, which, before untold centuries,
2   was the companion of their travels from central Asia; a language, copious, elastic, inviting
3   self-explaining combinations and independent development; lending itself alike to daily life
4   and imagination, to description and abstract thought. They had a class of nobles, but their
5   tongue knew no word for slave.[45]

Sources: 4–5 They had... slave] Waitz, *Deutsche Verfassungs Geschichte*, i. 86

TEI `xml` output:—

```
<p>The oldest monument of the Germans is their language,
which, before untold centuries, was the companion of their
travels from central Asia; a language, copious, elastic,
inviting self-explaining combinations and independent
development; lending itself alike to daily life and
imagination, to description and abstract thought.
<note type="fontium" target="#range(right(B61e),left(B62a))">Waitz,
<emph>Deutsche Verfassungs Geschichte</emph>, i. 86</note>
<anchor xml:id="B61e" />They had a class of nobles, but
their tongue knew no word for slave.
<anchor xml:id="B62a" />
<note place="bottom">George Bancroft,
<emph>History of the United States from the Discovery of
the American Continent</emph>, II.61--2.</note></p>
```

\note or \linelabel inside \lem   It may happen that the **\note** or **\linelabel** command is found inside the argument of **\lem**. Obviously, inserting such a command in the apparatus criticus in print makes no sense and will lead to an error. The solution is to insert in the value of the **alt** optional argument of **\lem** a duplicate of the lemma text devoid of that command, like so:—

```
This is some \app{
  \lem[alt=dummy]{\note[type=fontium, labelb=bnote, labele=enote,
    lem=dummy... command]{Text of the note.}
    dummy}
  \rdg{pseudo}}
text to demonstrate how to insert a note in the argument of the
\emph{lem} command.\linelabel{enote}
```

PDF output:—

1   This is some dummy text to demonstrate how to insert a note in the argument of the
2   *lem* command.

Sources: 1–2 dummy... command] Text of the note.

1 dummy] pseudo

TEI `xml` output:—

45. George Bancroft, *History of the United States from the Discovery of the American Continent*, II.61–2.

```
1   <p>This is some
2   <app>
3     <lem>
4     <anchor xml:id="bnote" />dummy</lem>
5     <note type="fontium"
6     target="#range(right(bnote),left(enote))">Text of the
7     note.</note>
8     <rdg>pseudo</rdg>
9   </app>text to demonstrate how to insert a note in the
10  argument of the
11  <emph>lem</emph>command.
12  <anchor xml:id="#enote" /></p>
```

As can be seen from the `TEI xml` output above, the span of text the note is about has been carefully delimited by two anchors (ll. 4 and 12), the first of which falls within `<lem>` (l. 4), but ekdosis has taken care of moving the note itself out of this element (ll. 5–7). Otherwise, the `TEI` output would not be valid.

7   Poetry

7.1   The Standard `verse` Environment

In order to typeset verse texts or poems, LaTeX provides the standard `verse` environment. Within this environment, `\\` is normally used to end lines, with the exception of the last line. As a result, stanzas are separated from one another by a blank line.

ekdosis provides `ekdverse` which is recommended for use in place of the standard `verse` environment. By default, `ekdverse` produces the same result as `verse`. However, ekdosis deviates a little from the standard usage for it needs all lines of poetry to be ended by `\\` as a distinct marker. In the following listing, stanzas are visually separated from one another by an additional vertical space of 2 ex (l. 5). Between stanzas, `%` is used to prevent TeX from introducing a blank line. But a blank line—or even no blank line—would produce the exact same result:—

```
1   \begin{ekdverse}
2     It is an ancient Mariner,\\
3     And he stoppeth one of three.\\
4     'By thy long grey beard and glittering eye,\\
5     Now wherefore stopp'st thou me?\\[2ex]
6     %
7     The Bridegroom's doors are opened wide,\\
8     And I am next of kin;\\
9     The guests are met, the feast is set:\\
10    May'st hear the merry din.'\\
11  \end{ekdverse}
```

PDF output:—

```
1       It is an ancient Mariner,
2       And he stoppeth one of three.
3       'By thy long grey beard and glittering eye,
4       Now wherefore stopp'st thou me?

5       The Bridegroom's doors are opened wide,
```

40

6	And I am next of kin;
7	The guests are met, the feast is set:
8	May'st hear the merry din.'

`TEI xml` output:—

```xml
<lg>
  <l>It is an ancient Mariner,</l>
  <l>And he stoppeth one of three.</l>
  <l>'By thy long grey beard and glittering eye,</l>
  <l>Now wherefore stopp'st thou me?</l>
  <l>The Bridegroom's doors are opened wide,</l>
  <l>And I am next of kin;</l>
  <l>The guests are met, the feast is set:</l>
  <l>May'st hear the merry din.'</l>
</lg>
```

One would have expected here the `<lg>` element to be used as delimiter to encode the stanzaic verse forms. But as can be seen, only the outermost level of line group has been converted into `TEI xml`, let alone the vertical spacing between stanzas which has been ignored. This is because it is about as much as the standard `verse` environment provides.

7.2 The verse Package

New feature v1.2 — ekdosis can use the facilities offered by the excellent **verse** package[46] to which it adds a specific environment for the encoding of line groups such as stanzas. Furthermore, as the **verse** package provides its own numbering mechanism, the lines can be numbered independently of prose text.[47]

⚠ For what is described in this section to operate, ekdosis must be loaded with the global option `poetry=verse` as explained above on page 7. Simply loading the **verse** package by means of `\usepackage` will have no effect.

⚠ The foregoing does not apply if the **memoir** class be used.[48] In this case, ekdosis automatically uses the code provided by this class without the need to set the global option `poetry=verse`.

Compatible Verse Commands The reader is invited to refer to the documentation of the **verse** package for detailed information. Within the `ekdverse` environment, `\\` *must be used* at the end of each line, as follows:—

(a) `\\` is the standard command to be used at the end of each line.
(b) `\\!` must be used at the end of stanzas or line groups instead of `\\`.
(c) `\\*` does the same as `\\` except that it prohibits a page break after the line.
(d) `\\>` is for line breaks within a verse line.

New feature v1.4 — (e) `\\+` does the same as `\\>` but without indenting the subsequent line which further complies to any already defined indent pattern.

All of these commands can take a dimension as optional argument, like so: `\\[30pt]`, `\\![30pt]`, `\\*[30pt]`, `\\>[30pt]` or `\\+[30pt]`. If `\\`, `\\!`, `\\*` or `\\+` be used, a

---

46. Peter R. Wilson and Will Robertson, *The Verse package* (version 2.4b) [Aids for typesetting simple verse] (May 10, 2014), http://www.ctan.org/pkg/verse.

47. See on page 49 for details.

48. Lars Madsen and Peter R. Wilson, *The Memoir package* (version 3.7o) [Typeset fiction, non-fiction and mathematical books] (Mar. 23, 2021), http://www.ctan.org/pkg/memoir.

vertical space of the dimension specified is added between lines, whereas \\>[...] adds an horizontal space after the line break.

\vin   \vin indents a verse line by a length which is by default 1.5 em. This length is stored as \vgap and can be changed by \setlength or \addtolength.

ekdverse   **The ekdverse Environment**   \begin{ekdverse}[⟨*options*⟩] ... \end{ekdverse}
This environment is used to hold verse lines as described above and may receive an optional argument in which the following "name=value" arguments are accepted:—

width   width=⟨*length*⟩   `Default: \linewidth`
If width be supplied, it is taken as a length in relation to which the entire contents of the environment are to be horizontally centered. If given, this dimension may correspond to an average line or to the longest line of the line group. To this end, the standard LaTeX command \settowidth can be used, like so:—

```
\settowidth{\versewidth}{This is the average line,}
\begin{ekdverse}[width=\versewidth]
...
\end{ekdverse}
```

> Rem. \versewidth is provided by the verse package as a convenience and can be used by ekdosis.

type   type=⟨*type*⟩   `Default: not set`
This named argument is used in the TEI xml output to name the type of unit encoded within the <lg> element, viz. "sonnet", "quatrain", "couplet" and the like.

Unlike the TEI xml element <lg>, ekdverse may not nest hiearchichally. Within this environment, ekdstanza must be used instead to encode stanzas as described below on the following page.

As an example, the first five lines of Homer's *Odyssey* could be encoded like so:[49]—

```
\begin{alignment}[tcols=2,
                  lcols=2,
                  texts=homer[xml:lang="grc"];murray[xml:lang="en"],
                  apparatus=homer]
  \begin{homer}
    \begin{ekdverse}
      Ἄνδρα μοι ἔννεπε, Μοῦσα, πολύτροπον, ὃς μάλα πολλὰ \\
      πλάγχθη, ἐπεὶ Τροίης ἱερὸν πτολίεθρον ἔπερσεν· \\
      πολλῶν δ' ἀνθρώπων ἴδεν ἄστεα καὶ
                  \app{\lem{νόον}
                       \rdg[resp=Zen]{νόμον}
                       \note{Cf. Schol.}} ἔγνω, \\
      πολλὰ δ' ὅ γ' ἐν πόντῳ πάθεν ἄλγεα ὃν κατὰ θυμόν, \\
      ἀρνύμενος ἥν τε ψυχὴν καὶ νόστον ἑταίρων. \\
    \end{ekdverse}
  \end{homer}
  \begin{murray}
    Tell me, O Muse, of the man of many devices, who wandered full
    many ways after he had sacked the sacred citadel of Troy. Many
    were the men whose cities he saw and whose mind he learned, aye,
    and many the woes he suffered in his heart upon the sea, seeking
    to win his own life and the return of his
    comrades.
```

---

49. Homer, *The Odyssey*, ed. A. T. Murray, 2 vols. (Cambridge, MA. – London: Harvard University Press – William Heinemann, 1919).

```
      \end{murray}
\end{alignment}
```

PDF output:—

Ἄνδρα μοι ἔννεπε, Μοῦσα, πολύτροπον, ὃς μάλα πολλὰ 1
πλάγχθη, ἐπεὶ Τροίης ἱερὸν πτολίεθρον ἔπερσεν· 2
πολλῶν δ᾽ ἀνθρώπων ἴδεν ἄστεα καὶ νόον ἔγνω, 3
πολλὰ δ᾽ ὅ γ᾽ ἐν πόντῳ πάθεν ἄλγεα ὃν κατὰ θυμόν, 4
ἀρνύμενος ἥν τε ψυχὴν καὶ νόστον ἑταίρων. 5

_____

3 νόον] νόμον Zen. Cf. Schol.

   Tell me, O Muse, of the man of 1
many devices, who wandered full 2
many ways after he had sacked 3
the sacred citadel of Troy. Many 4
were the men whose cities he saw 5
and whose mind he learned, aye,
and many the woes he suffered in
his heart upon the sea, seeking to
win his own life and the return of
his comrades.

TEI `xml` output:—

```xml
<div xml:id="div-homer_1" xml:lang="grc">
  <lg>
    <l>Ἄνδρα μοι ἔννεπε, Μοῦσα, πολύτροπον, ὃς μάλα πολλὰ</l>
    <l>πλάγχθη, ἐπεὶ Τροίης ἱερὸν πτολίεθρον ἔπερσεν·</l>
    <l>πολλῶν δ' ἀνθρώπων ἴδεν ἄστεα καὶ
    <app>
      <lem>νόον</lem>
      <rdg resp="#Zen">νόμον</rdg>
      <note>Cf. Schol.</note>
    </app>ἔγνω,</l>
    <l>πολλὰ δ' ὅ γ' ἐν πόντῳ πάθεν ἄλγεα ὃν κατὰ θυμόν,</l>
    <l>ἀρνύμενος ἥν τε ψυχὴν καὶ νόστον ἑταίρων.</l>
  </lg>
</div>
<div xml:id="div-murray_1" xml:lang="en">
  <p>Tell me, O Muse, of the man of many devices, who
  wandered full many ways after he had sacked the sacred
  citadel of Troy. Many were the men whose cities he saw and
  whose mind he learned, aye, and many the woes he suffered
  in his heart upon the sea, seeking to win his own life and
  the return of his comrades.</p>
</div>
```

Stanzas   As can be seen above, the LaTeX `ekdverse` environment is translated into the TEI `xml` `<lg>` element. The `type` attribute may then be used to name the type of unit encoded by this element.

ekdstanza   \begin{ekdstanza}[⟨*options*⟩] ... \end{ekdstanza}

This environment is used within `ekdverse` to encode succeeding stanzaic forms. Within `ekdstanza`, the last line is ended by \\! or \\ depending on whether an additional vertical space is required between stanzas. This environment may receive an optional argument in which the following "name=value" argument is accepted:—

type   **type**=⟨*type*⟩   `Default: not set`

As in the case of `ekdverse`, this named argument is used in the TEI `xml` output to name the type of unit encoded within the `<lg>` element, viz. "quatrain", "couplet" and the like.

Indentation Patterns   ekdosis can use the `patverse` environment and its associated command `\indentpattern` that are provided by the `verse` package. As described in the documentation of this package,[50] the indentation pattern consists of an array of digits, d_1 to d_n, where the n^{th} line is indented by d_n times the amount of `\vgap` described above on page 42.

The overall structure of lines grouped into stanzas may look as follows:—

```
1   \begin{ekdverse}[type={overall type}]
2     \identpattern{digits}
3     \begin{patverse}
4       \begin{ekdstanza}[type={stanza 1 type}]
5         line 1 \\
6         line 2 \\
7         [...]
8         final line \\!
9       \end{ekdstanza}
10    \end{patverse}
11  \end{ekdverse}
```

Of course, if no indentation pattern be required or be only required occasionally, `patverse` (ll. 3 and 10) and `\indentpattern` (l. 2) are of no use:—

```
1   \begin{ekdverse}[type={overall type}]
2     \begin{ekdstanza}[type={stanza 1 type}]
3       line 1 \\
4       line 2 \\
5       \vin indented line 3 \\
6       [...]
7       final line \\!
8     \end{ekdstanza}
9   \end{ekdverse}
```

A detailed example follows. It is taken from Raymond MacDonald Alden's edition of Shakespeare's *Sonnets* from the Quarto of 1609 with variorum readings.[51] Compared to MacDonald's edition, an effort has been made to use the typography and punctuation of the original edition which can be consulted online at the British Library's website.[52] However, this typographical refinement has been retained for the sonnet only. For the sake of clarity, the line numbers and the apparatus criticus use modern typography. The references to line numbers in the apparatus criticus have been made consistent with MacDonald's edition, as have the entries in the apparatus criticus, namely the bare line number followed by a dot, then the lemma text in bold face, then the variant in italic shape:—

Listing 7: Poetry: Shakespeare's Sonnet 1

```
1   \junicode % Use the Junicode font with 'hist' feature enabled for
2              % long-s
3   % MacDonald's style for numbers and entries in the apparatus
4   % criticus:
5   \SetHooks{
6     refnumstyle=\normalfont,
7     postrefnum=.~,
```

50. Wilson and Robertson (cf. n. 46), 6.

51. Raymond MacDonald Alden (ed.), *The Sonnets of Shakespeare* [From the Quarto of 1609 with Variorum Readings and Commentary] (Boston & New York: The Riverside Press Cambridge, 1916), Sonnet 1, p. 15.

52. Shake-speares *Sonnets*. Neuer before Imprinted. (A Louers Complaint. By William Shake-speare.). `https://www.bl.uk/collection-items/first-edition-of-shakespeares-sonnets-1609`. Call number `C.21.c.44`, fol. B.

```
 8    lemmastyle=\bfseries,
 9    readingstyle=\itshape
10  }
11  % The lines are to be centered horizontally:
12  \settowidth{\versewidth}{Feed'st thy lights flame with selfe
13  substantiall fewell,}
14  % Format of the outermost <div> element:
15  \NewDocumentEnvironment{ekdcenter}{}{\par\centering}{\nobreak\par}
16  \FormatDiv{1}{\begin{ekdcenter}}{\end{ekdcenter}}
17  \begin{ekdosis}
18    \ekddiv{type=sonnets, n=1, head=1}
19    \begin{ekdverse}[type=sonnet, width=\versewidth]
20      \indentpattern{00000000000011}
21      \begin{patverse}
22        \begin{ekdstanza}[type=quatrain]
23          \ekdlettrine{F}{r}om fairest creatures we desire
24          increase,\\
25          That thereby beauties \emph{Rose}
26          \app{
27            \lem{might}
28            \rdg[source={Gildon1710, Sewell1725, Ewing1771}]{may}
29          } neuer die,\\
30          But as the riper should by time
31          \app{
32            \lem{decease}
33            \rdg[source=Hudson1856]{decrease}
34          },\\
35          His tender heire might beare his memory:\\
36        \end{ekdstanza}
37        \begin{ekdstanza}[type=quatrain]
38          But thou contracted to thine owne bright eyes,\\
39          Feed'st thy
40          \app{
41            \lem{lights}
42            \rdg[source={Butler1899, Walsh1908}]{life's}
43          } flame with
44          \app{
45            \lem{selfe substantiall}
46            \rdg[source=Gildon1714,
47            alt={\textnormal{Hyphened by}}]{selfe-substantiall}
48            \note{etc.}} fewell,\\
49          Making a famine where aboundance lies,\\
50          Thy selfe thy foe,to thy sweet selfe too cruell:\\
51        \end{ekdstanza}
52        \begin{ekdstanza}[type=quatrain]
53          Thou that art now the worlds fresh ornament,\\
54          And
55          \app{
56            \lem{only}
57            \rdg[resp=God, type=conjecture]{early}
58            \note{conj.}
59          } herauld to the gaudy spring,\\
60          Within thine owne bud buriest thy content,\\
61          And tender
62          \app{
```

```
63          \lem{chorle}
64          \rdg[source=Gildon1710]{churl}
65          \note{etc.}
66        } makst wast in niggarding:\\
67      \end{ekdstanza}
68      \begin{ekdstanza}[type=couplet]
69        Pitty the world,or else this glutton be,\\
70        To eate the worlds due,\app{
71          \lem{by the}
72          \rdg[resp=Stee, type=conjecture]{be thy}
73          \note{conj.}
74          \rdg[resp=God, type=conjecture]{by thy}
75          \note{conj.}
76        } graue
77        \app{
78          \lem{and}
79          \rdg[resp=God, type=conjecture]{as}
80          \note{conj.}
81        } thee.\\!
82      \end{ekdstanza}
83      \end{patverse}
84    \end{ekdverse}
85  \end{ekdosis}
```

REM. 1 `Gildon1710`, `Gildon1714`, `Sewell1725`, `Ewing1771`, `Hudson1856`, `Butler1899` and `Walsh1908` have been declared as sources.[53] `God` and `Stee`, resp. Godwin and Steevens, have been declared as scholars.[54]

REM. 2 `\ekdlettrine` (l. 23) is a specific command for the lettrine package does not work in list environments. `\TeXtoTEIPat` has been used as described below on page 68 to instruct ekdosis to convert this command into an acceptable TEI equivalent. The definition of `\ekdlettrine` follows:—

```
% Preamble:
\usepackage{adjustbox}
% This basic command actually requires an adjustment of the vertical
% space at the end of the current line (eg. \\[-1.875ex]) and \vin at
% the beginning of the next line:---
\NewDocumentCommand{\ekdlettrine}{mm}{%
\adjustbox{valign=t,raise=-0.75ex}{\Huge #1}\textsc{#2}%
}
\TeXtoTEIPat{\ekdlettrine {#1}{#2}}{<hi rend="smallcaps">#1#2</hi>}
```

PDF output:—

1

Fʀᴏᴍ faireſt creatures we deſire increaſe,   1
 That thereby beauties *Roſe* might neuer die,   2
But as the riper ſhould by time deceaſe,   3
His tender heire might beare his memory: 4
But thou contracted to thine owne bright eyes,   5
Feed'ſt thy lights flame with ſelfe ſubſtantiall fewell,   6

2. **might**] *may* G S E   3. **decease**] *decrease* Hu[2]   6. **lights**] *life's* But Wa   **selfe substantiall**] Hyphened by G[2] etc.

<div style="text-align:right">

Making a famine where aboundance lies,   7
Thy selfe thy foe,to thy sweet selfe too cruell: 8
Thou that art now the worlds fresh ornament,   9
And only herauld to the gaudy spring,   10
Within thine owne bud buriest thy content,   11
And tender chorle makst wast in niggarding: 12
    Pitty the world,or else this glutton be,   13
    To eate the worlds due,by the graue and thee.   14

</div>

---

10. **only**] *early* Godwin conj.   12. **chorle**] *churl* G etc.   14. **by the**] *be thy* Stee conj. *by thy* Godwin conj.   **and**] *as* Godwin conj.

`TEI xml` output:—

```xml
<div type="sonnets" n="1">
  <head>1</head>
  <lg type="sonnet">
    <lg type="quatrain">
      <l>
      <hi rend="smallcaps">Fr</hi>om fairest creatures we
      desire increase,</l>
      <l>That thereby beauties
      <emph>Rose</emph>
      <app>
        <lem>might</lem>
        <rdg source="#Gildon1710 #Sewell1725 #Ewing1771">
        may</rdg>
      </app>neuer die,</l>
      <l>But as the riper should by time
      <app>
        <lem>decease</lem>
        <rdg source="#Hudson1856">decrease</rdg>
      </app>,</l>
      <l>His tender heire might beare his memory:</l>
    </lg>
    <lg type="quatrain">
      <l>But thou contracted to thine owne bright eyes,</l>
      <l>Feed'st thy
      <app>
        <lem>lights</lem>
        <rdg source="#Butler1899 #Walsh1908">
        life's</rdg>
      </app>flame with
      <app>
        <lem>selfe substantiall</lem>
        <rdg source="#Gildon1714">
        selfe-substantiall</rdg>
        <note>etc.</note>
      </app>fewell,</l>
      <l>Making a famine where aboundance lies,</l>
      <l>Thy selfe thy foe,to thy sweet selfe too
      cruell:</l>
```

```
      </lg>
      <lg type="quatrain">
        <l>Thou that art now the worlds fresh ornament,</l>
        <l>And
        <app>
          <lem>only</lem>
          <rdg resp="#God" type="conjecture">early</rdg>
          <note>conj.</note>
        </app>herauld to the gaudy spring,</l>
        <l>Within thine owne bud buriest thy content,</l>
        <l>And tender
        <app>
          <lem>chorle</lem>
          <rdg source="#Gildon1710">churl</rdg>
          <note>etc.</note>
        </app>makst wast in niggarding:</l>
      </lg>
      <lg type="couplet">
        <l>Pitty the world,or else this glutton be,</l>
        <l>To eate the worlds due,
        <app>
          <lem>by the</lem>
          <rdg resp="#Stee" type="conjecture">be thy</rdg>
          <note>conj.</note>
          <rdg resp="#God" type="conjecture">by thy</rdg>
          <note>conj.</note>
        </app>graue
        <app>
          <lem>and</lem>
          <rdg resp="#God" type="conjecture">as</rdg>
          <note>conj.</note>
        </app>thee.</l>
      </lg>
    </lg>
  </div>
```

8 Lineation Settings

ekdosis uses lineno internally for line numbering.[55] But it must be noted that ekdosis strictly prohibits the "pagewise" mode of operation that is provided by lineno. As a result of this hinderance, all "margin switching" functions of lineno are disabled within the environments that are specific to ekdosis, viz. ekdosis and `alignment`.

That said, ekdosis provides equivalents of its own to handle the line numbers the same way as lineno's "pagewise" mode of operation does.

\SetLineation   \SetLineation{⟨*csv list of options*⟩} may be used in the preamble or at any point of the document to set lineation preferences. Its argument processes the `key=value` options that follow:—

General Options

lineation   lineation=page|document|none   Default: document

---

55. Uwe Lück and Stephan Böttcher, *The Lineno package* (version 4.41) [Line numbers on paragraphs] (Nov. 2, 2005), http://www.ctan.org/pkg/lineno.

`lineation=document` has the lines numbered continuously throughout the document while `lineation=page` instructs ekdosis that the numbering should start afresh at the top of each page. `none` does the same as `page` but prevents the numbers from being printed in the margins while keeping them in use in the apparatus criticus.

modulo | `modulo` | Default: not set
`modulo` does not accept any value. When this option is set, every fifth line is numbered.

modulonum | `modulonum`=n (where n is an integer) | Default: not set
`modulonum` allows to modify the interval between the numbers that are printed. `modulo` must be set for this option to have effect. As examples, `modulo, modulonum=3` has every third line numbered and `modulonum=1` disables modulo numbering.

margin | `margin`=`right|left|inner|outer` | Default: left
`margin` sets the margin in which the line numbers are to be printed.

numbers | `numbers`=`elided|full` | Default: elided
This option only has effect on the numbers that are printed in the apparatus criticus. `numbers=elided` applies on spans of numbers and elides the last number of a range to the fewest number of figures possible—viz. 35–7, 129–31 &c.—without eliding digits in the group 10 to 19 in each hundred—viz. 17–19, 115–18 &c. `numbers=full` leaves the numbers untouched.

\innerlinenumbers
\outerlinenumbers | `\innerlinenumbers` and `\outerlinenumbers` are equivalent to `\SetLineation{numbers=outer}` and `\SetLineation{numbers=inner}` respectively. Both commands are complementary to `\rightlinenumbers` and `\leftlinenumbers` already provided by the lineno package.

Options Specific to the `poetry=verse` Global Setting[56]

vlineation | `vlineation`=`page|document` | Default: document
`vlineation` operates on verse texts in the same way as `lineation` on prose texts.

vmodulo | `vmodulo`=n (where n is an integer) | Initially: 1, Default: 5
`vmodulo`=n has every n^{th} lines of verse printed in the margin. If used without value, this option is equivalent to `vmodulo=5`. `vmodulo=0` prevents the numbers from being printed.

vnumbrokenlines | `vnumbrokenlines`=`true|false` | Initially: false
New feature v1.4 | This named argument does not need a value as it defaults to `true` if used. `vnumbrokenlines` has both parts of lines broken by `\\>` or `\\+`[57] numbered with the same number for disambiguation purposes. By default, only the second part of broken lines is numbered.

vmargin | `vmargin`=`right|left` | Default: right
`vmargin` sets the margin in which the verse line numbers are to be printed.

continuousvnum | | Default: not set
The `poetry=verse` global option has the succeeding lines of verse numbered independently of prose text. `continuousvnum` has all lines numbered continuously, irrespective of whether they are lines of prose or poetry text.

Useful Lineation Commands   As implied above, pretty much all commands that are provided by the "running" mode of operation of the lineno package will work with ekdosis, notably the following:—

\modulolinenumbers | `\modulolinenumbers[`⟨n⟩`]` can be used to enable or modify modulo line numbering as described above.

\resetlinenumber | `\resetlinenumber[`⟨n⟩`]` resets the line number to one or to n if specified.

\linenumberfont | `\renewcommand{\linenumberfont}{`⟨*commands*⟩`}` can be used to set the font used for the line numbers that are printed in the margins.   By default, the definition is

---

56. See above sect. 7.2 on page 41.

57. See above (d) to (e) on page 41 for more information.

	`\normalfont\footnotesize.`
`\linenumbersep`	`\linenumbersep` is the distance between the numbers and the margin. By default, this distance is set to 10 pt. It can be redefined like so: `\setlength\linenumbersep{⟨length⟩}`.

Poetry Lineation Commands In addition to these commands, if ekdosis be loaded with the global option `poetry=verse` as described above in , the commands dedicated to line numbering that are provided by the verse package can be used.

`\vmodulolinenumbers` *New feature* v1.4	`\vmodulolinenumbers[⟨n⟩]` can be used to enable or modify verse modulo line numbering as described above.
`\resetvlinenumber`	`\resetvlinenumber[⟨n⟩]` has for lines of verse the same effect as `\resetlinenumber` for lines of prose text.
`\verselinenumfont`	`\verselinenumfont{⟨commands⟩}` can be used to set the font used for lines of verse. By default, the definition is `\normalfont\footnotesize`.
`\vrightskip`	The verse package prints the numbers at the distance `\vrightskip` into the right margin. This distance can be redefined by means of `\setlength` like so: `\setlength\vrightskip{⟨length⟩}`.

`\linelabel` `\ref`	**Labels** In prose as well as in poetry texts, `\linelabel{⟨label⟩}` sets a line label that can be referred to with `\ref{⟨label⟩}`.

As an example, what follows has every fifth line number printed in the inner margins. Additionally, the numbering shall start afresh at the top of each page:—

```
\SetLineation{
  lineation=page,
  modulo,
  margin=inner
}
```

9 Languages

ekdosis is fully compatible with babel. "Fully compatible" means that all features provided by babel, including language switching commands, are supported by ekdosis. ekdosis is also compatible with polyglossia with one notable exception: luabidi, which polyglossia loads for languages written from right to left, is not supported by ekdosis, and most probably never will be. That said, as far as the author could see, single-layer apparatus, as described in , can be typeset within the Arabic environment that is provided by polyglossia. Unfortunately, the same cannot be said for multiple-layer apparatus.

Whether babel or polyglossia is used, ekdosis automatically applies the current language to the entries of the apparatus criticus, including the fonts that may have been associated to the languages in the preamble. In this respect, as polyglossia can use the same language switching commands as babel,[58] the general advice given above in applies in all cases. As regards setting languages in the `TEI xml` output file, the reader is invited to refer to point , and including the example provided on page .

In some cases, it may be needed to apply in the apparatus criticus a language different from the one that is selected in the edition text. To this end, ekdosis provides a set of

---

58. See François Charette and Arthur Reutenauer, *The Polyglossia package* (version 1.49) [An alternative to babel for XeLaTeX and LuaLaTeX] (Apr. 8, 2020), http://www.ctan.org/pkg/polyglossia, 3.2 p. 14.

facilities which are described on pages 33–34 for single-layer apparatus and on page 35 for multiple-layer apparatus.

9.1   Languages Written From Right to Left

As said above, polyglossia is not supported by ekdosis for languages that are written and read from right to left, like Arabic, Hebrew or Syriac. However, as babel is supported and can be loaded concurrently with polyglossia, an easy way is to use babel to print such languages.

The reader is invited to refer to and become acquainted with the relevant parts of the documentation of the babel package.[59]

babel Only   In the following example, babel is used exclusively to set three different languages: Arabic, ancient Greek and English:—

Listing 8: Multilingual editions with babel only

```
1   \usepackage{fontspec}
2
3   \usepackage[greek.ancient,english]{babel}
4   \babelprovide[onchar=fonts]{arabic}
5
6   \babelfont{rm}{Old Standard}
7   \babelfont[greek]{rm}[RawFeature={+ss05;+ss06}]{Old Standard}
8   \babelfont[*arabic]{rm}{Amiri}
9
10  \babeltags{ancientgreek = greek}
11  \newcommand{\sg}[1]{\textancientgreek{#1}}
12
13  \newcommand{\RL}[1]{\bgroup\textdir TRT#1\egroup}
14  \newenvironment{Arabic}{\par\pardir TRT\textdir TRT}{\par}
```

REM. 1   As can be seen, fontspec has been loaded before babel. To the author's knowledge, this gives better results when \babelfont is used.

REM. 2   Line 3 loads babel and instructs it to use English as the default language and ancient Greek as a second optional language. The built-in bidi mechanism provided by babel is not enabled. As a result, specific language switching commands for Arabic must be defined just as it must be for every other language.

REM. 3   Line 4 does not load any Arabic, but instructs babel that it should use the Arabic font that is set below with \babelfont whenever an Arabic letter is encountered.

REM. 4   Lines 6–8 select the fonts: Old Standard is the default font to be used for Roman shape (l. 6); the same font is used for Greek, with some additional Open Type features enabled; finally, the Amiri font is used for Arabic.

REM. 5   Lines 10–11 define so-called "tags" for easier access to ancient Greek through \begin{ancient greek} … \end{ancientgreek} for running paragraphs and \textancientgreek{⟨text⟩} for short insertions of Greek in English text. \sg{⟨text⟩} is just a shorthand for this latter command.

REM. 6   Finally, lines 13–14 define simple language switching commands for Arabic. As can be seen, no commands other than the LuaTEX primitives \pardir and \textdir have been used for babel already takes care of selecting the Arabic font. \RL is for short insertions of Arabic words in English paragraphs while \begin{Arabic} … \end{Arabic} is for running paragraphs of Arabic text.

\setRL   **Changing the Writing Direction**   \setRL and \setLR are two argument-less commands
\setLR   provided by ekdosis that can be used to change the writing direction of running paragraphs.

59. Javier Bezos López and Johannes L. Braams, *The Babel package* (version 3.47) [Multilingual support for Plain TeX or LaTeX] (July 13, 2020), http://www.ctan.org/pkg/babel.

The former sets the direction from right to left and the latter form left to right. If babel be set as above, \setRL ... \setLR can be used in place of \begin{Arabic} ... \end{Arabic}.

polyglossia **Associated With** \babelprovide   What follows illustrates how babel can be used conjointly with polyglossia for the same three languages as above without having to load luabidi:—

Listing 9: Multilingual editions with babel and polyglossia

```
1   \usepackage{fontspec}
2
3   \usepackage{babel}
4   \babelprovide[onchar=fonts]{arabic}
5
6   \setmainfont{Old Standard}
7   \newfontfamily\greekfont{Old Standard}[RawFeature={+ss05;+ss06}]
8   \babelfont[*arabic]{rm}{Amiri}
9
10  \usepackage{polyglossia}
11  \setdefaultlanguage{english}
12  \setotherlanguage[variant=ancient]{greek}
13
14  \newcommand{\textarabic}[1]{\bgroup\textdir TRT#1\egroup}
15  \newenvironment{Arabic}{\par\pardir TRT\textdir TRT}{\par}
```

REM. 1 Line 3 just loads babel with no default language.
REM. 2 Lines 4 and 8 are used to have the Arabic font automatically selected as above.
REM. 3 Lines 14–15 define the exact language switching commands that would have been defined if polyglossia and luabidi had been used for Arabic.

As one can see, the important points about languages written from right to left are to use babel only to select the Arabic fonts, avoid using the bidirectional mechanism it provides and define commands and environments that use only LuaTeX primitives to set the writing direction. Then, an Arabic edition text—to continue with this example—can be entered as plainly as follows:—

```
\begin{ekdosis}
  \begin{Arabic}
    \app{ إِنَّ أَبِي كَانَ مِنَ
      \lem{اَلْمُقَاتِلَةِ}
      \rdg{اَلْمُقَاتِلِينَ}
    وَ كَانَتْ أُمِّي مِنْ عُظَمَاءِ بُيُوتِ الزَّمَازِمَةِ. }
  \end{Arabic}
\end{ekdosis}
```

It should be reminded that the writing direction of the apparatus criticus itself is independent of that of the edition text and must be set either with \Set(LTR|RTL)app or with the direction optional argument of \SetApparatus for single-layer apparatus criticus, or by means of \DeclareApparatus for multiple-layer apparatus criticus.[60]

The PDF output with left-to-right apparatus criticus follows:—

---

60. See above sect. 5.2 on page 33 (single-layer apparatus criticus) and sect. 5.3 on page 35 (multiple-layer apparatus criticus).

1   إِنَّ أَبِي كَانَ مِنَ ٱلْمُقَاتِلَةِ وَكَانَتْ أُمِّي مِنْ عُظَمَآءِ بِيُوتِ ٱلزَّمَازِمَةِ.

ٱلْمُقَاتِلِينَ [ٱلْمُقَاتِلَةِ **1**

And here follows the PDF output with right-to-left apparatus criticus:—

1   إِنَّ أَبِي كَانَ مِنَ ٱلْمُقَاتِلَةِ وَكَانَتْ أُمِّي مِنْ عُظَمَآءِ بِيُوتِ ٱلزَّمَازِمَةِ.

---

1 ٱلْمُقَاتِلَةِ] ٱلْمُقَاتِلِينَ

9.2   Using arabluatex

arabluatex is a LuaL^ATEX package that provides commands and environments which return Arabic writing from an ASCII transliteration (either ArabTEX or Buckwalter scheme).[61] It is particularly well-suited for complex documents such as critical editions where a lot of commands intertwine with Arabic writing. arabluatex can output Unicode Arabic in the same modes as arabtex[62] or in different accepted standards of romanization. It is also able to produce a duplicate of the original `.tex` source file in which all `arabtex` or `buckwalter` strings are replaced with Unicode equivalents, either in Arabic script or in any accepted standard of transliteration.[63]

    arabluatex is fully supported by ekdosis. The following example illustrates how arabluatex and ekdosis interact with each other to produce distinct `TEI xml` outputs from a single `.tex` source file:—

Listing 10: ekdosis and arabluatex

```
1   % Preamble:
2   % load ekdosis and ask for TEI xml output:
3   \usepackage[teiexport]{ekdosis}
4   % load arabluatex and request a LaTeX output with Unicode Arabic:
5   \usepackage[export,fullvoc]{arabluatex}
6
7   % document:
8   \begin{arabexport} % export arabtex strings to Unicode Arabic
9     \begin{ekdosis}
10      \begin{arab}
11        'inna 'abI kAna mina
12        \app{
13          \lem{'l-muqAtilaTi}
14          \rdg{'l-muqAtilIna}
15        }
16        wa-kAnat 'ummI min `u.zamA'i buyUti 'l-zamAzimaTi.
17      \end{arab}
```

---

61. Robert Alessi, *The Arabluatex package* (version 1.20) [ArabTeX for LuaLaTeX] (Mar. 23, 2020), http://ctan.org/pkg/arabluatex.

62. Klaus Lagally, *The Arabtex package* (version 4.00) [Macros and fonts for typesetting Arabic] (Mar. 11, 2004), http://baobab.informatik.uni-stuttgart.de/ifi/bs/research/arab_e.html.

63. Alessi, *The Arabluatex package* (cf. n. 61), "Exporting Unicode Arabic to an External File."

```
18      \end{ekdosis}
19   \end{arabexport}
```

The PDF output with left-to-right apparatus criticus is of course the same as above:—

إِنَّ أَبِي كَانَ مِنَ ٱلْمُقَاتِلَةِ وَكَانَتْ أُمِّي مِنْ عُظَمَآءِ بِيُوتِ ٱلزَّمَازِمَةِ.

1

---

١ ٱلْمُقَاتِلَةِ] ٱلْمُقَاتِلِينَ

However, assuming that the source file is called `source.tex`, ekdosis produces as instructed from this file an additional `source-tei.xml` as follows:—

```
<p xml:lang="ar-Latn" type="transliterated"
subtype="arabtex">'inna 'abI kAna mina
<app>
  <lem>'l-muqAtilaTi</lem>
  <rdg>'l-muqAtilIna</rdg>
</app>wa-kAnat 'ummI min `u.zamA'i buyUti
'l-zamAzimaTi.</p>
```

At the same time, `arabluatex` is instructed to produce on its own from the same `source.tex` an additional `source_out.tex` in which all `arabtex` strings found within `\begin{arabexport}` … `\end{arabexport}` (see listing 10 on the previous page, ll. 9–19) are replaced with full-vocalized Arabic Unicode script. Finally, compiling this latter file produces the following `sample-arabic_out-tei.xml` an extract of which follows:—

```
<p xml:lang="arb">إِنَّ أَبِي كَانَ مِنَ
<app>
  <lem>ٱلْمُقَاتِلَةِ</lem>
  <rdg>ٱلْمُقَاتِلِينَ</rdg>
وَكَانَتْ أُمِّي مِنْ عُظَمَآءِ بِيُوتِ<app/>
ٱلزَّمَازِمَةِ.<p/>
```

The reader will find the full `arabic-sample.tex` source file with instructions in sect. 17 on page 91, and is invited to refer to the documentation of the `arabluatex` package for more information on the way to use its Arabic environments and built-in functions dedicated to export `arabtex` ASCII strings to Unicode.[64]

10   Divisions of the Body

The features that are described in this section call for one general remark. ekdosis is designed to figure out where any LaTeX command that is converted to a TEI opening element allowed to nest recursively, such as `<div>`, `<lg>` and the like, is to be closed, even though there is no explicit indication of the point where the closure occurs. Thoroughly scanning LaTeX source files with Lua functions which involve complex string matching and recursions was required, as LaTeX 'open' commands such as `\chapter` or `\section` only act as milestones, contrary to TEI elements.

---

64. Alessi, *The Arabluatex package* (cf. n. 61).

54

It must be noted that the two styles described hereinafter are mutually exclusive. `TEI xml` forbids that both be combined within a single `<body>` element.[65] As a result, ekdosis will disregard whichever one is not selected.

10.1 LaTeX Standard Divisions

ekdosis can use the LaTeX standard textual divisions, such as `\book`, `\chapter`, `\section` and the like.

However, to have these divisions properly translated into `TEI` numbered `<div>` elements, the `divs` general option must be set to `latex` explicitly—viz. `divs=latex`—as described above on page 6.

As the `alignment` environment that is provided by ekdosis places all aligned texts within `TEI xml` un-numbered `<div>` elements and LaTeX textual divisions are converted into numbered `<div`$_n$`>` elements, inserting such divisions in texts to be aligned will result in an invalid `TEI xml` output. Instead, un-numbered divisions through `\ekddiv` must be used as described below in sect. 10.2 on the following page.

Once `divs` has been set to `latex`, ekdosis converts `\book`, `\part`, `\chapter`, `\section`, `\subsection` and `\subsubsection` into corresponding TEI 'numbered' `<div`$_n$`>` elements, where $1 \leq n \leq 6$.

`\MkBodyDivs` **Adjusting the Levels of Textual Subdivisions** `\MkBodyDivs{`⟨*div1*⟩`}{`⟨*div2*⟩`}{`⟨*div3*⟩`}` `{`⟨*div4*⟩`}{`⟨*div5*⟩`}{`⟨*div6*⟩`}` takes six mandatory arguments. This command can be used in the preamble or at any point of the document to make the number of the first-level subdivision of the edition text, viz. `<div1>`, match to any LaTeX command other than `\book`. For example, if `\section` be the highest-level sectional command used, then `\MkBodyDivs{section}{subsection}{subsubsection}{}{}{}` will have `\section`, `\subsection` and `\subsubsection` converted into `<div1>`, `<div2>` and `<div3>` respectively.

Inserting Variants in Headings Variant readings can be inserted in headings. In this case, the optional argument of the LaTeX sectional command must naturally be used to prevent variants from going into headers, footers or the table of contents, like so:[66]—

```
1   % Preamble:
2   \usepackage[teiexport=tidy, divs=latex]{ekdosis}
3   \MkBodyDivs{chapter}{section}{}{}{}{}
4
5   % Document:
6   \chapter[Ἱπποκράτους ἐπιδημιῶν βιβλίον δεύτερον]{Ἱπποκράτους ἐπιδημιῶν
7     \app{
8       \lem[wit={I,R,H}]{βιβλίον δεύτερον}
9       \rdg[wit=V]{λόγος β'}}}
10
11  \section[Τμῆμα πρῶτον]{
12    \app{
13      \lem[resp=egomute, type=emendation, nosep,
14       post=suppleui]{\supplied{Τμῆμα πρῶτον}}
15    }}
16  Ἄνθρακες θερινοὶ ἐν Κραννῶνι· [...]
```

---

65. See https://tei-c.org/release/doc/tei-p5-doc/en/html/DS.html#DSDIV.
66. On the use of `egomute` (l. 13), see above Rem. 2 on page 21.

TEI `xml` output:—

```
<div1 type="chapter">
  <head>Ἱπποκράτους ἐπιδημιῶν
  <app>
    <lem wit="#I #R #H">βιβλίον δεύτερον</lem>
    <rdg wit="#V">λόγος β'</rdg>
  </app></head>
  <div2 type="section">
    <head>
      <app>
        <lem><supplied resp="#ego" type="emendation">Τμῆμα
        πρῶτον</supplied></lem>
      </app>
    </head>
    <p>Ἄνθρακες θερινοὶ ἐν Κραννῶνι· [...]</p>
  </div2>
</div1>
```

10.2   `TEI` Un-numbered Divisions

As already described on page 6, the un-numbered style of division is the one that is set by default. It is congruous to the general option `divs=ekdosis`.

This style provides a flexible mechanism in which format and presentation are separated from content. It is designed to meet the requirements of classical and literary texts the divisions of which may depend on many different received traditions.

\ekddiv   `\ekddiv{`⟨*key-value arguments*⟩`}` is the unique sectional command provided by `ekdosis`. This command converts the divisions into un-numbered TEI `<div>` elements allowed to nest recursively and takes one mandatory argument in which the following `key-value` arguments are accepted:—

type   `type`=⟨*name*⟩   Default: none
`type` corresponds to the `TEI` class `att.typed` and can be used to classify the element in which it is found in any way. Suitable values here can be `book`, `chapter`, `section` and the like.

n   `n`=⟨*value*⟩   Default: none
`n` is meant to provide a number or any kind of label for the division and does not have to be unique in the document.

head   `head`=⟨*name*⟩   Default: none
`head` holds the title of the division and may further contain variant readings.

barehead   `barehead`=⟨*name*⟩   Default: none
`barehead` is supposed to be used to prevent unwanted commands from going into such places as headers, footers and the table of contents.

depth   `depth`=⟨*n*⟩ where $1 \leq n \leq 9$ Default: 1
As `TEI` un-numbered divisions are simply `<div>` elements allowed to nest recursively to indicate their hierarchic depth and `\ekddiv` is an 'open' LᴬTᴇX command, `n` is needed to indicate the depth of the division within the hierarchy, the largest being `1` and the smallest being `9`.

toc   `toc`=`book|part|chapter|section|subsection|subsubsection|paragraph|`
      `subparagraph`   Default: not set
If `toc` be set, the title of the division goes into the table of contents at the hierarchic level that is specified as value.

mark=⟨*signpost*⟩ `Default: none`

mark holds the signpost to be emitted as marker for headers and footers. Its value is recalled by `\ekdmark` as described below in .

`\FormatDiv` **Formatting the Titles** By design, ekdosis does not format the titles. Instead, depending on what is needed for the edition text, `\FormatDiv{`⟨*n*⟩`}{`⟨*code before*⟩`}{`⟨*code after*⟩`}` is provided to lay out the titles of any hierarchic depth of division. This command takes three mandatory arguments as follows: ⟨*n*⟩, which is the number referring to the particular depth of division to be formatted and some LaTeX commands to go before and after the title itself. The following example illustrates how the titles of the largest division can be printed horizontally centered in a larger size:—

```
\FormatDiv{1}{\begin{center}\Large}{\end{center}}
```

To elaborate on the example provided above in , here follows how the first three hierarchical levels could be formatted as un-numbered divisions:—

Listing 11: Divisions of the body text

```
1   % Preamble:
2   \FormatDiv{1}{\begin{center}\Large}{\end{center}}
3   \FormatDiv{2}{\begin{center}\large}{\end{center}}
4   \FormatDiv{3}{\bfseries}{.}
5
6   % Document:
7   \begin{ekdosis}
8     \ekddiv{
9       head={Ἱπποκράτους ἐπιδημιῶν
10        \app{
11          \lem[wit={I,R,H}]{βιβλίον δεύτερον}
12          \rdg[wit=V]{λόγος β'}}},
13      type=book,
14      depth=1,
15      n=II
16    }
17
18    \ekddiv{
19      head={\app{
20          \lem[resp=egomute, post=suppleui,
21          type=emendation]{\supplied{Τμῆμα πρῶτον}}
22          \rdg[wit=codd, alt=om.]{}}},
23      type=section,
24      depth=2,
25      n=II.1
26    }
27
28    \ekddiv{head=1, type=paragraph, depth=3, n=II.1.1}
29    Ἄνθρακες θερινοὶ ἐν Κραννῶνι· [...]
30  \end{ekdosis}
```

PDF output:—

<div style="text-align: center">

1   Ἱπποκράτους ἐπιδημιῶν βιβλίον δεύτερον

2   ⟨Τμῆμα πρῶτον⟩

</div>

3   **1.** Ἄνθρακες θερινοὶ ἐν Κραννῶνι· [...]

---

1 βιβλίον δεύτερον IRH] λόγος β' V   **2** Τμῆμα πρῶτον suppleui] om. codd.

TEI `xml` output:—

```xml
<div xml:id="div-hippocrates_1" xml:lang="grc">
  <div type="book" n="II">
    <head>Ἱπποκράτους ἐπιδημιῶν
    <app>
      <lem wit="#I #R #H">βιβλίον δεύτερον</lem>
      <rdg wit="#V">λόγος β'</rdg>
    </app></head>
    <div type="section" n="II.1">
      <head>
        <app>
          <lem resp="#ego" type="emendation">
            <supplied>Τμῆμα πρῶτον</supplied>
          </lem>
          <rdg wit="#V #I #R #H" />
        </app>
      </head>
      <div type="paragraph" n="II.1.1">
        <head>1</head>
        <p>Ἄνθρακες θερινοὶ ἐν Κραννῶνι· [...]</p>
      </div>
    </div>
  </div>
</div>
```

10.3   Headers and Footers

New feature v1.3   ekdosis provides a mechanism of its own for emitting header and footer marks. The first operation consists in recording the information to be printed as signpost by means of the `mark` optional argument of the `\ekddiv` command described above in sect. 10.2 on page 56.

\ekdmark   Once this is done, `\ekdmark` can be inserted in commands used to make headers and footers where the mark is to be printed.

A common layout is that of headers in which one finds printed in sequence on even pages the page number, then the author's name, and on odd pages the title of the edited text, then the current division, then the page number, like so:—

Even pages:

\thepage	Hippocratis

Odd pages:

Epidemiarum liber II, \ekdmark	\thepage

To return to the example provided by , the mark of the current division would be inserted in the third-level **\ekddiv** command printed at line 28 like so:—

```
28        \ekddiv{head=1, type=paragraph, depth=3, n=II.1.1, mark={1, 1}}
```

The following example finally illustrates how the corresponding headers and footers can be prepared in a straightforward way with the help of the titleps package:[67]—

```
% Preamble:
\usepackage{titleps}
\newpagestyle{edition}{
  \sethead[\thepage][Hippocratis][]
          {}{Epidemiarum liber II, \ekdmark}{\thepage}
}
% Apply the page style:
\pagestyle{edition}
```

\endmark   It must be noted that **\ekdmark** is designed to print the first mark that is emitted on a given page and ignore the mark corresponding to any portion of text that may be printed between the top of the page and the point where the first mark is called. **\endmark** is an argument-less command that can be used just at the end of that portion of text to instruct ekdosis to print the last-emitted mark of the preceding page instead of the first-emitted mark of the current page.

Removing Headers and Footers   Pages such as title pages must be printed with empty headers and footers. ekdosis must be given control over every item of information inserted in these areas beforehand.

\ekdprintmark   **\ekdprintmark{**⟨*selector*⟩**}{**⟨*signpost*⟩**}** The signposts printed in headers and footers must be passed as second argument of **\ekdprintmark** so that ekdosis can remove them on pages where printing them is not desirable. ⟨*selector*⟩ refers to three symbolic letters where the first can be either H or F—for header or footer—, the second E or O—for odd or even—and the third L, C or R—for left, center or right. The example provided above would then read as follows:—

```
% Preamble:
\usepackage{titleps}
\newpagestyle{edition}{
  \sethead[\ekdprintmark{HEL}{\thepage}]
          [\ekdprintmark{HEC}{Hippocratis}]
          []
          {}
          {\ekdprintmark{HOC}{Epidemiarum liber II, \ekdmark}}
          {\ekdprintmark{HOR}{\thepage}}
}
% Apply the page style:
\pagestyle{edition}
```

---

67. Javier Bezos López, *The Titleps package* (version 2.13) [Page style control] (Oct. 16, 2019), https://ctan.org/pkg/titleps.

Once all signposts are marked with **\ekdprintmark**, **\ekdnohfmarks** can be used at any point of the document with the same effect as the LaTeX standard command **\thispagestyle{empty}**.

Finally, **\ekdresethfmarks** is provided in rare cases when it is needed to reset headers and footers to their original, viz. printable state.

11   The Tricks of the Trade

As the **.tex** source file is compiled, **ekdosis** has to compute a tremendous amount of data. Most of this work is performed by **Lua** functions. An edition text narrowed down to a single page needs to be compiled at least three times. On the first run, the apparatus criticus does not show. Instead, **ekdosis** produces an auxiliary file named **\jobname.ekd** in which all the entries of the apparatus criticus are collected. Then, on the second run a test is performed on this auxiliary file to determine whether there are entries—and if so, which ones—to be printed on the current page. At the same time, references to the line numbers are updated if necessary. Finally, on the third run, the apparatus criticus is printed.

Of course, every change made to the input may similarly require LuaLaTeX to be run three more times to get everything to the right place with the right numbers.

11.1   The Oscillating Problem

In some instances, notably when on a given page entries are very abundant in number, specifically when the edition text is getting close to the bottom of the page, **ekdosis** may oscillate indefinitely between different sets of page decisions without being able to settle down. The condition may be typically illustrated as follows: after LuaLaTeX has been run, an entry is attached to the last line of the page. As said above, this entry does not show yet. But when it does, should it result in an additional line being printed in the apparatus criticus, the last line of the edition text—the one the entry was previously attached to— goes to the next page. As a result, this entry also moves to the next page with the line it belongs to. This point is literally critical, because unless a **\pagebreak** is inserted just here so as to keep the contentious line on the next page, **ekdosis** enters a vicious circle from which it cannot escape, not to mention that right entries with right line numbers cannot come on pages that follow a wrong page either.

An alert reader may have guessed that inserting a **\pagebreak** is a good way to get out of the vicious circle. And surely, if only a few pages be at stake, this is the way to go. However, **\pagebreak** commands should only be inserted when the whole edition text is ready for any substantial change in the preceding pages may result in pages that break just after they begin.

Conditional page breaks   \ekdpb[⟨*page no*⟩]{⟨*line no*⟩} \ekdpb*{} \ekdpb*\ One way to avoid this inconvenience is to use **\ekdpb** instead of the standard **\pagebreak** command provided by LaTeX to insert conditional page breaks. **\ekdpb** takes as mandatory argument the line number, as it is printed in the margin, where the page break should take place. An optional argument allows to further specify the page number where the page break should occur. The value that is expected is the page number as it is printed—e.g. an Arabic, Roman or alphanumeric number. If the specified conditions be not met, then the page break is not triggered. Finally, the "starred" version of this command forces the page break, irrespective of the values specified as page or line numbers. Unlike **\ekdpb**, which requires the lines to be numbered, **\ekdpb*** is allowed at any point of the document: as **\ekdpb*** disregards the number given as argument, it is equivalent to the standard LaTeX

`\pagebreak` command. Yet it can be used instead of the latter to have marks further printed in the margins so as to spot with a fleeting glance the locations where induced page breaks occur.[68]

Using `maxentries`   Another way—should the edition text fall into the vicious circle too often—is to limit the number of entries per page that a given layer of apparatus criticus may accept as described above on page 36. As a result, ekdosis will take care of inserting automatic breakpoints between pages whenever the number of entries on a given page reaches the value set as `maxentries`.

   `maxentries` must not be too small: otherwise offensive to look at vertical spaces may come between the edition text and the apparatus criticus. Conversely, `maxentries` must not be too big: otherwise, should entries overflow on a given page, the edition text and the apparatus criticus may clash again. As said above, a couple of clashes can be managed with a couple of manually inserted page breaks. But if there be too many of them, it is a good indication that the selected value of `maxentries` is too high.

   Complex edition texts do have a magic number. An advisable way to figure it out would be to start from a sample of only a few pages, selected as evidence for the complexity of the whole. As only a few pages would need to be compiled, the magic number should emerge quite rapidly.

Adding and Removing Entries   `\addentries[⟨layer⟩]{⟨n⟩}`
`\addentries`
New feature v1.1   If `maxentries` be set for a given layer of critical notes, `\addentries[⟨layer⟩]{⟨n⟩}`, where ⟨n⟩ is an integer, can be used to add ⟨n⟩ to—or remove it from if ⟨n⟩ be negative—the number of accepted entries on the current page. `\addentries` operates on the default layer of notes, but any other declared layer can be specified in the optional argument of the command.

   ⊘ Of course, `\addentries` must be issued before the number of entries on a given page has reached the value set as `maxentries`.

   Once a sensible value for `maxentries` has been found, `\addentries` can further be used with a positive integer to allow for more entries and more lines on some pages so that offending vertical spaces are decreased. Conversely, `\addentries` with a negative integer will remove entries on pages where there are too many of them and ekdosis still oscillates between different sets of page decisions.

New feature v1.3   **The `fitapp` Global Option**   The rationale of this option is discussed above (see (d) on page 6). As this mechanism has the characters of the apparatus block scaled down to allow for more entries once a predefined height has been reached, ekdosis should settle down in most of the contentious cases.[69] However, it is advisable to use `fitapp` conjointly with `maxentries` to prevent the number of allowed entries from being too high, which would result in the characters being too small or even illegible.

11.2   Variae Quaestiones

This section is about issues that are not strictly speaking part of the documentation of ekdosis but may nevertheless circumstantially arise.

---

68. This requires the `showpagebreaks` option to be set to `true` as described above on page 7.
69. That is, cases that arise *after* the predefined height has been reached.

Superfluous Dots   As said above on page 33, it is customary in some editions to have a full stop printed at the end of the apparatus criticus. ekdosis provides specific commands to achieve this in a straightforward way, such as **\SetEndApparatus** and the **ehook** optional argument of **\SetApparatus** and **\DeclareApparatus**.[70] However, if the last word of the apparatus criticus on a given page be an abbreviation followed by a dot, such a setting will have two dots printed at the end of the apparatus instead of one. The solution is to define a command to have a dot printed only if not followed by a dot, and append this command to the abbreviated form of the word, like so:—

```
1   % Preamble:
2   \usepackage{xspace}
3   \usepackage{ekdosis}
4
5   \makeatletter
6   \newcommand{\ekddot}{%
7     \ltx@ifnextchar{.}{\xspace}{.\xspace}}
8   \makeatother
9
10  \DeclareApparatus{default}[ehook=.]
11  \DeclareScholar{Erm}{Erm\ekddot}
```

> REM. 1   Line 2: The xspace package is needed for **\xspace** is used by the **\ekddot** command that is defined at l. 6.
>
> REM. 2   Line 7: **\ltx@ifnextchar** is part of the ltxcmds package which is loaded by ekdosis. As this command uses a private control sequence, it must be found within **\makeatletter** ... **\makeatother**.
>
> REM. 3   Line 10: **\ekddot** will only work with multiple-layer apparatus criticus. Therefore, **\DeclareApparatus** must be used even if only one layer of critical notes be needed.

Backup of Essential Files   Each time the **.tex** source file is compiled, ekdosis reads the **.aux** corresponding LaTeX auxiliary file and its own **.ekd** auxiliary file so as to process labels and collect entries of the apparatus criticus. If for whatever reason—e.g. some unknown command has been inserted—the compilation be frozen and so must be aborted, it may happen that most of the edition text has to be reconstructed page after page. For large and complex editions, this makes advisable to have current versions of those files backed up each time a new compilation begins, which can be achieved by inserting the following lines before the line that loads the document class:—

```
\RequirePackage{verbatimcopy}
\IfFileExists{\jobname.aux}{%
  \OldVerbatimCopy{\jobname.aux}{\jobname.aux.bak}}{}
\IfFileExists{\jobname.ekd}{%
  \OldVerbatimCopy{\jobname.ekd}{\jobname.ekd.bak}}{}
\documentclass{book}
```

This way, both **.aux** and **.ekd** files can be recovered from **.aux.bak** and **.ekd.bak** just after the compilation has been aborted. Should this be needed, one must proceed carefully as follows:—

(a) Just after the compilation has been aborted, move both **aux.bak** and **ekd.bak** files to a safe place.

(b) Remove or correct the offending command or lines that broke the compilation and make sure that the issue is solved.

(c) Restore the **.aux** and **.ekd** files from **aux.bak** and **.ekd.bak** and resume work where it was left off.

---

70. See above on pages 33–35.

12 `TEI xml` Output

Several examples of `TEI xml` output have been provided hitherto. Before proceeding, the reader is invited to return to every one of them. In this respect, it may be of interest to review carefully the excerpt of Caesar's *Gallic War* of which the LaTeX source file and its corresponding `TEI xml` output are printed in full below in sect. 16 on page 85. Once ekdosis has been instructed to convert the edition text into `TEI xml` (l. 11), the preamble of this file shows how to set languages and fonts to be used in the document (ll. 2–6), format the titles (l. 16) and lay out the alignment of an edition text associated with two translations (ll. 18–25) in modern languages. Furthermore, it shows how information related to each language (Latin, English and French) is to be found in two different places, namely for `TEI xml` output (ll. 21–3) and for PDF output through LaTeX (ll. 27–9). Finally, it provides examples of declaring witnesses, hands and shorthands (ll. 31–60). As to the document itself, it shows how to lay out a conspectus siglorum in a table (ll. 64–80), before giving detailed examples of how the edition text is entered (ll. 85–101) and sectional commands provided by ekdosis are used (ll. 86, 103 and 110).[71]

12.1 Requesting `TEI xml` Output

`TEI xml` output is requested by means of the `teiexport` global option as described above on page 7. Once instructed to output `TEI`, ekdosis converts and exports in sequence the contents of ekdosis environments (see above sect. 2.5 on page 13). As regards the contents of `alignment` environments (see above sect. 4 on page 25), ekdosis first collates the contents of the environments that have been declared as values of the `texts` optional argument of `alignment` or `\SetAlignment`,[72] then places each of the corresponding `TEI xml` outputs within distinct `<div>` elements named after the declared environments themselves. For example, to return to Caesar's text, the Latin edition text is found between a `\begin{latin}` ... `\end{latin}` environment (see the `.tex` source file, sect. 16.1 on page 85, ll. 85–101) which is declared at l. 21. Then, the corresponding `xml` output is found within a `<div>` element, the `xml:id` of which has been given by ekdosis the value `div-latin_1` (see sect. 16.2 on page 87, ll. 176–200).

`\SetTEIFilename`   **TEI File Name**   `\SetTEIFilename{`⟨*basename*⟩`}` is a preamble-only command. It can be used to set the base name of the `TEI xml` output file, to which the suffix `.xml` is appended. By default, the base name is `\jobname-tei`.

12.2 General Principles

Validation of the `TEI xml` Structure   The reference tool that the author relies on is that provided by the *TEI by Example Project*.[73] As for ekdosis, it is designed to produce on request, in addition to an edition in print, a `TEI xml`-compliant output file. That said, one must keep in mind that the LaTeX packages that are part of TeXLive can be counted in thousands, and the commands they provide in tens of thousands. There may even be grounds in asserting that the possibilities offered by TeX and LaTeX quite exceed what can be afforded by `TEI xml`. On another hand, many LaTeX commands make no sense in `TEI`.

---

71. The PDF output is available as a separate file.
72. See above sect. 4.1 on page 27.
73. Ron Van den Branden, Melissa Terras, and Edward Vanhoutte, "TEI by Example," `http://www.teibyexample.org`, accessed Aug. 4, 2020. The `TEI` validator is here: `http://teibyexample.com/xquery/TBEvalidator.xq`.

Therefore, a sensible choice is to keep them out of the environments the contents of which are to be translated into `xml` elements, as will be illustrated by the following.

Converting a LaTeX document into `TEI xml` can be quite an intricate business. In many cases, however, LaTeX strings are found within environments or groups that are easy to convert into `TEI` equivalents: unless instructed otherwise, whether such groups are delimited by opening and closing braces or by explicit `\begin ... \end` commands, ekdosis translates them into `xml` so that for example `\emph{word}` and `\begin{quote}` ⟨*quoted words*⟩ `\end{quote}` become `<emph>` ⟨*word*⟩ `</emph>` and `<quote>` ⟨*quoted words*⟩ `</quote>` respectively.

But LaTeX does not place everything into groups or environments. To take here but a few examples, sectional divisions are marked in LaTeX with "open" commands such as `\chapter` or `\section` with no clear indication where the closure of divisions occurs, contrary to `TEI xml` markup with numbered or un-numbered `<div>` elements allowed to nest recursively. As regards running paragraphs of text, the situation is even worse than in the latter case, as the following simple example shows:—

```
1   \begin{document}
2   \begin{ekdosis}
3     ...
4
5     ... These are the final words of some section in the body text.
6
7     \section{New Section}
8
9     Here is how some new section begins...
10
11    ... Final words.
12    \section{Other Section}
13    Opening words of the section...
14
15    ... Final words
16
17    \section{Other Section}
18    Opening words...
19
20    ... Final words.
21  \end{ekdosis}
22  \end{document}
```

Obviously, construing this LaTeX source file into `TEI xml` is a fairly complex task. For example, line 6 only closes a paragraph for line 7 opens a division (hence `</p><div1>`), line 8 only opens a paragraph just after the heading of the section (hence `</head><p>`) while line 14 both closes the foregoing paragraph and opens a new one (hence `</p><p>`), contrary to line 16 which both closes a paragraph and a sectional division (hence `</p></div1>`), not to mention lines 20–1, where notwithstanding the absence of blank line or any other indication, `</p></div1></body></text></TEI>` is needed.

ekdosis has been designed to implement this task through `Lua` functions which involve string matching (both forward and reverse matching) and recursions.

`\SetTEIxmlExport`   **`TEI xml` Export Settings**   `\SetTEIxmlExport{`⟨*csv list of options*⟩`}` can be used in the preamble or at any point of the document, except inside environments set to receive an apparatus criticus, namely the **ekdosis** environment or any other similar environment

declared by means of the `alignment` environment or `\SetAlignment`.[74] At the time of writing, there is only one option, as follows:—

autopar   `autopar=true|false` `Default: true`

The algorithm described above applies for edition texts composed in running paragraphs or lines of poetry, but it may fail to produce a valid `TEI xml` output with other arrangements, such as performance texts or transcriptions of speech for which the `TEI` Guidelines define specific rules. `autopar=false` instructs ekdosis to ignore blank lines in the `.tex` source file as markers for paragraph boundaries. As a result, each paragraph of the edition text must be found within an environment associated with the `xml` element `<p>`, such as ekdpar or any other environment declared as such by means of `\EnvtoTEI` described below in sect. 12.4 on page 67. A typical use case of `autopar=false` is provided below in sect. 12.6 on page 70.

ekdpar   `\begin{ekdpar}` ... `\end{ekdpar}` is a simple environment that does nothing but insert `\par` primitives. It can be used to instruct ekdosis to place paragraphs within `<p>` elements when `autopar` has been set to `false` by means of `\SetTEIxmlExport` described above.

The `xml:id` Attribute   As a general rule, the `xml:id` global attribute must be unique for the element that bears the attribute. Furthermore, it must begin with a letter or an underscore and contain no characters other than letters of the Latin alphabet—from `a` to `z`, either upper or lower case—digits, hyphens, underscores and full stops. ekdosis issues a warning when it finds that any ⟨*unique id*⟩ of ⟨*unique label*⟩ expected in the first argument of `\DeclareWitness`, `\DeclareHand`, `\DeclareSource` or `\DeclareScholar` is not unique or breaks the rules just described, but does not prevent the `.tex` source file from compiling. Instead, it prints the string `<??>` in place of the expected formatted siglum so that the error in the `.tex` source file can be easily spotted and corrected.

As the ⟨*unique id*⟩ declared with `\DeclareShorthand` is not to be exported in the `TEI xml` output file, ekdosis checks neither its uniqueness nor its validness.

It must be noted that LaTeX labels that are provided in commands such as `\label`, `\cite` and the like must also be unique in the document. As LaTeX will issue warnings if duplicates be found, `\ekdosis` does not check their uniqueness but will issue warnings if such labels contain invalid strings.

12.3   Routine LaTeX Commands and Environments

The list of LaTeX commands known by ekdosis at the time of writing follows. To this list must be added the LaTeX standard commands that are used for sectional divisions as described above in sect. 10.1 on page 55 and most of the commands provided by the arabluatex and icite[75] packages. Standard citation commands are also supported as will be described below in sect. 12.8 on page 74:—

LaTeX command	TEI xml element
`\textsuperscript{}`	`<hi rend="sup"></hi>`
`\textsubscript{}`	`<hi rend="sub"></hi>`
`\textbf{}`	`<hi rend="bold"></hi>`
`\textit{}`	`<hi rend="italic"></hi>`
`\textsc{}`	`<hi rend="smallcaps"></hi>`

---

74. See above sect. 4.1 on page 27.

75. Robert Alessi, *The Icite package* (version 1.3a) [Indices locorum citatorum] (Mar. 5, 2020), http://ctan.org/pkg/icite.

LATEX command	TEI xml element
`\textsf{}`	`<hi rend="sf"></hi>`
`\footnote{}`	`<note place="bottom"></note>`
`\marginpar{}`	`<note place="margin"></note>`
`\enquote⟨*⟩{}`	`<quote></quote>`
`\label{label}`	`<anchor xml:id="label"/>`
`\linelabel{label}`	`<anchor xml:id="label"/>`
`\ref{label}`	`<ptr ="#label"/>`
`\pageref{label}`	`<ptr ="#label"/>`
`\vref{label}`	`<ptr ="#label"/>`
`\vpageref{label}`	`<ptr ="#label"/>`
`\pagebreak⟨[⟨1-4⟩]⟩`	no output
`\mbox{⟨text⟩}`	⟨text⟩

From the extdash[76] package:

`\---` or `\===`	—
`\--` or `\==`	–
`\-/` or `\=/`	-

As for environments:—

LATEX environment	TEI xml element
`flushright`	`<p rend="align(right)"></p>`
`flushleft`	`<p rend="align(left)"></p>`
`center`	`<p rend="align(center)"></p>`
`quotation`	`<quote></quote>`
`quoting`	`<quote></quote>`
`verse`	`<lg></lg>`

Regarding other, very frequently used commands or environments, some do not need to be inserted in the translation tables: as already said above, ekdosis converts by default the original names of these into xml elements. For instance, `\emph{}` and `\begin{quote}` ... `\end{quote}` will result in `<emph></emph>` and `<quote></quote>` respectively.

For the same simple reason, should one wish to have words within a TEI xml element that does not have any LATEX equivalent, all is needed is to define an inoperative LATEX command named after the TEI element, like so:—

```
% Preamble:
\newcommand{\mentioned}[1]{#1}

% Document:

Our usage corresponds to the \mentioned{aggregate} of many
mathematical writings and to the sense of \mentioned{class} found in
older logical writings.
```

TEI xml output:—

---

76. Alexander I. Rozhenko, *The Extdash package* (version 1.3) [A range of dash commands for compound words] (June 24, 2018), http://www.ctan.org/pkg/extdash.

```xml
<p>Our usage corresponds to the <mentioned>aggregate</mentioned> of
many mathematical writings and to the sense of
<mentioned>class</mentioned> found in older logical writings.</p>
```

Of course, it is also possible to have the "mentioned" words printed in a different font family:—

```latex
\newcommand{\mentioned}[1]{\textsf{#1}}
```

This command will print them in a sans serif font family, with the exact same `TEI xml` output as above.

12.4   Processing New Commands or Environments

The following three commands are provided to instruct ekdosis how to convert unknown or unusual (LA)TEX commands or environments into `TEI xml` equivalents.

\TeXtoTEI   `\TeXtoTEI{`⟨*csname*⟩`}{`⟨*TEI element*⟩`}[`⟨*TEI attribute(s)*⟩`]`
`\TeXtoTEI` takes two mandatory arguments and one optional argument, namely: the control sequence name to be converted, the `TEI` element it is to be converted into and any additional `xml` attributes to be appended to the opening `TEI` element. For example, the `\sidenote` command that is provided by the sidenotes package can be processed like so:—

```latex
% Preamble:
\TeXtoTEI{sidenote}{note}[place="margin"]

% Document:
\begin{ekdosis}
  \begin{ekdverse}
    The self-same moment I could pray;\sidenote{The spell begins to
      break}\footnote{The turning point of the poem...}
  \end{ekdverse}
\end{ekdosis}
```

`TEI xml` output:—

```xml
<lg>
  <l>The self-same moment I could pray;
  <note place="margin">The spell begins to break</note>
  <note place="bottom">The turning point of the
  poem...</note></l>
</lg>
```

Even more subtly, provided that the code `#STC` points to some more information identifying the agency concerned:[77]—

```latex
% Preamble:
\usepackage{sidenotes}
\usepackage[teiexport=tidy]{ekdosis}
```

---

77. At the time of writing, 'sources' can be declared with `\DeclareSource` as described above on page 10. Then the unique identifier used in the first argument of this command can point to the list of references inserted by ekdosis in the back matter section of the `TEI` output file. See below sect. 12.7 on page 71 for more information on how to do this. Scholars can also be referred to as individuals by means of the `\DeclareScholar` command. See above on page 10.

```
\TeXtoTEI{sidenote}{note}[place="margin"]

\newcommand{\STCsnote}[1]{\sidenote{#1}}
\TeXtoTEI{STCsnote}{note}[place="margin" resp="#STC"]

% Document:
\begin{ekdosis}
  \begin{ekdverse}
    The self-same moment I could pray;\STCsnote{The spell begins to
      break}\footnote{The turning point of the poem...}
  \end{ekdverse}
\end{ekdosis}
```

TEI xml output:—

```
<lg>
  <l>The self-same moment I could pray;
  <note place="margin" resp="#STC">The spell begins to
  break</note>
  <note place="bottom">The turning point of the
  poem...</note></l>
</lg>
```

\EnvtoTEI ⟨*⟩{⟨*env name*⟩}{⟨*TEI element*⟩}[⟨*TEI attribute(s)*⟩]

\EnvtoTEI instructs ekdosis how to convert LaTeX environments into TEI xml equivalents. It takes two mandatory arguments and one optional argument, namely the name of the LaTeX environment to be converted, the TEI element it is to be converted into and any additional attributes to be appended to the TEI opening element. \EnvtoTEI* is restricted to TEI elements that must never appear within <p> elements, such as <p> itself, <div>, <lg> and the like. The following example illustrates how \EnvtoTEI can be used conjointly with babel to convey information about the languages used from LaTeX to TEI:—

```
% Preamble:
% Use babel and babeltags:
\usepackage[greek.ancient, english]{babel}
\babeltags{ancientgreek = greek}

\EnvtoTEI{ancientgreek}{p}[xml:lang="grc"]

% Document:
\begin{ekdosis}
  \begin{ancientgreek}
    περὶ πολλοῦ ἂν ποιησαίμην, ὦ ἄνδρες, τὸ τοιούτους ὑμᾶς ἐμοὶ
    δικαστὰς περὶ τούτου τοῦ πράγματος γενέσθαι, οἷοίπερ ἂν ὑμῖν
    αὐτοῖς εἴητε τοιαῦτα πεπονθότες...
  \end{ancientgreek}
\end{ekdosis}
```

TEI xml output:—

```
<p xml:lang="grc">περὶ πολλοῦ ἂν ποιησαίμην, ὦ ἄνδρες, τὸ
τοιούτους ὑμᾶς ἐμοὶ δικαστὰς περὶ τούτου τοῦ πράγματος
γενέσθαι, οἷοίπερ ἂν ὑμῖν αὐτοῖς εἴητε τοιαῦτα πεπονθότες...</p>
```

\TeXtoTEIPat   \TeXtoTEIPat{⟨*T_EX pattern*⟩}{⟨*TEI pattern*⟩}

Finally, this more flexible—and more delicate to handle—command uses pattern matching to instruct ekdosis how to convert (LA)TEX commands into TEI equivalents. In the first mandatory argument, strings to be captured are marked in sequence with numbers prefixed by `#`, like so: `#1`, `#2`, `#3` and so forth. Then, in the second mandatory argument, the strings captured are inserted where each of them is expected in the TEI element.

If the entire string to be captured be enclosed in square or curly brackets, it is advisable to use `@bn` (for curly brackets) or `@sn` (for square brackets) instead of `#n`, where *n* is the number that is expected in the sequence. This will prevent any brackets that may be found in the captured string from being interpreted.

Strings must be entered exactly as ekdosis will find them as the `.tex` source file is compiled. Specifically, *control sequences*, namely the coded commands immediately preceded by '`\`' are always found followed by a space. For instance, `\emph{}` will be seen and processed by ekdosis as `\emph␣{}`.

The following example illustrates how ekdosis can be instructed to process the `\textcolor{⟨color⟩}{⟨text⟩}` command:—

```
1  \TeXtoTEIPat{\textcolor␣{#1}@b2}{<hi rend="#1">@b2</hi>}
2
3  Sample text with a \textcolor{red}{word} in red.
```

> REM. As can be seen from l. 1, it is safe to use `#1` for the first string for color names are naturally formed of letters without braces. However, `@b2` is preferable to capture the whole second argument of `\textcolor` for it may contain words within braces.

```
<p>Sample text with a
<hi rend="red">word</hi>in red.</p>
```

12.5   Inserting Code in the `TEI xml` Ouput File

It may be needed to insert code in the `TEI xml` output file only, for example when clear enough information is written in the apparatus criticus by means of such optional arguments as `pre`, `post`, `prewit` or `postwit` that are not processed for `TEI xml` ouput.[78]

`\teidirect`
New feature v1.3
`\teidirect[⟨xml attributes⟩]{⟨xml element⟩}{⟨code⟩}`
Two mandatory arguments are expected by `\teidirect`, namely the `TEI xml` element followed by the contents to be found in the ouput file between the opening and closing tags. Additionally, attribute-value pairs to be found inside the start-tag of the element can be specified in the optional argument of the command. An example follows:

```
1  % Preamble:
2  \DeclareWitness{GalE1.M}{Gal.E1(M)}{\emph{Monacencis Gr.}
3    231}[origDate=s. XVI]
4  \DeclareWitness{GalE1.Q}{Gal.E1(Q)}{\emph{Parisinus Gr.}
5    2174}[origDate=s. XIV]
6    \DeclareShorthand{GalE1.M.Q}{Gal.E1(MQ)}{GalE1.M,GalE1.Q}
7
8  % Document:
9  ἐν \app{
10     \lem[wit=codd]{καύμασιν}
11     \rdg[wit=GalE1.M.Q, postwit=\unskip(23.16)]{καύματι}
12     \teidirect{note}{p. 23, l. 16 Wenkebach}}
```

---

78. See above sect. 2.5 on page 13.

Rem. 1 `GalE1.M.Q` (l. 11) has been defined as a shorthand to denote the agreement of two otherwise defined manuscripts by means of `\DeclareWitness`: `GalE1.M` and `GalE1.Q`. (See ll. 2–6.)

Rem. 2 The `postwit` optional argument has been used to further specify the location where this variant reading can be found in the critical edition of Galen's Commentary on Hippocrates' *Epidemics*, Book 1 (l. 11). But as the effect of `postwit` is limited to the PDF output, `\teidirect` has been used to convey this item of information to the `TEI xml` ouput file (l. 12).

PDF output:—

```
1     ἐν καύμασιν
```

---

1 καύμασιν codd.] καύματι Gal.E1(MQ)(23.16)

TEI xml output:—

```
1   <p xml:lang="grc">ἐν
2   <app>
3     <lem wit="#V #I #R #H">καύμασιν</lem>
4     <rdg wit="#GalE1.#M #GalE1.Q">καύματι</rdg>
5     <note>p. 23, l. 16 Wenkebach</note>
6   </app></p>
```

12.6 Specific TEI Modules

The following example illustrates how ekdosis can be adapted in a straightforward way to modules provided by the TEI for encoding specific texts such as transcriptions of speech.[79] The technique applied below uses `\EnvtoTEI` conjointly with `\SetTEIxmlExport{autopar= false}` described above on page 64:—

```
1   % Preamble:
2   \newenvironment{speech}{\par}{\par}
3   \newcommand{\speaker}[1]{\textbf{#1}\par}
4   \EnvtoTEI{speech}{sp}
5
6   \SetTEIxmlExport{autopar=false}
7
8   % Document:
9   \begin{ekdosis}
10    \begin{speech}
11      \speaker{Σωκράτης}
12      \begin{ekdpar}
13        κατέβην χθὲς εἰς Πειραιᾶ μετὰ Γλαύκωνος τοῦ Ἀρίστωνος
14        προσευξόμενός τε τῇ θεῷ καὶ ἅμα τὴν ἑορτὴν βουλόμενος θεάσασθαι
15        τίνα τρόπον ποιήσουσιν ἅτε νῦν πρῶτον ἄγοντες. καλὴ μὲν οὖν μοι
16        καὶ ἡ τῶν ἐπιχωρίων πομπὴ ἔδοξεν εἶναι, οὐ μέντοι ἧττον ἐφαίνετο
17        πρέπειν ἣν οἱ θρᾷκες ἔπεμπον.
18      \end{ekdpar}
19    \end{speech}
20  \end{ekdosis}
```

Rem. 1 Lines 2–3 define a basic environment meant to contain individual speeches and a command to hold the name of the speaker. This name is printed in bold face and followed by a new paragraph in the PDF output.

---

79. See https://tei-c.org/release/doc/tei-p5-doc/en/html/TS.html.

Rᴇᴍ. 2 Line 4 instructs **ekdosis** to convert `speech` LᴬTₑX environments into `<sp>` TEI xml elements.

Rᴇᴍ. 3 Line 6 disables the `autopar` algorithm that **ekdosis** provides by default for running paragraphs of text. As a consequence, `ekdpar` is used to mark the paragraphs.

PDF output:—

1   **Σωκράτης**
2   κατέβην χθὲς εἰς Πειραιᾶ μετὰ Γλαύκωνος τοῦ Ἀρίστωνος προσευξόμενός τε τῇ θεῷ καὶ
3 ἅμα τὴν ἑορτὴν βουλόμενος θεάσασθαι τίνα τρόπον ποιήσουσιν ἅτε νῦν πρῶτον ἄγοντες.
4 καλὴ μὲν οὖν μοι καὶ ἡ τῶν ἐπιχωρίων πομπὴ ἔδοξεν εἶναι, οὐ μέντοι ἧττον ἐφαίνετο πρέπειν
5 ἣν οἱ Θρᾷκες ἔπεμπον.

TEI xml output:—

```
<sp>
  <speaker>Σωκράτης</speaker>
  <p>κατέβην χθὲς εἰς Πειραιᾶ μετὰ Γλαύκωνος τοῦ Ἀρίστωνος
  προσευξόμενός τε τῇ θεῷ καὶ ἅμα τὴν ἑορτὴν βουλόμενος
  θεάσασθαι τίνα τρόπον ποιήσουσιν ἅτε νῦν πρῶτον ἄγοντες.
  καλὴ μὲν οὖν μοι καὶ ἡ τῶν ἐπιχωρίων πομπὴ ἔδοξεν εἶναι, οὐ
  μέντοι ἧττον ἐφαίνετο πρέπειν ἣν οἱ θρᾷκες ἔπεμπον.</p>
</sp>
```

12.7   References to Cited Works

A full example of what is technically called a *Conspectus Siglorum* can be found above in sect. 2.4.1 on page 12. Such a list of manuscript sigla should be found immediately before the edition text. Traditionally, this section is followed by a list of other sources used to establish the text, so that the edited text is in the end established both from manuscript evidence (the "witnesses") and other works based on a scholarly approach of the text (the "sources") which are called in Latin *Editiones uel Studia*. As a consequence of this classification as "witness" or "source", the former must go within the `<listWit>` element of the TEI header, whereas the latter is to be found within the `<listBibl>` element.

\AddxmlBibResource   `\AddxmlBibResource{⟨basename or name.xml⟩}` is a preamble-only command. If a base name (either suffixed with `.xml` or not) for a TEI xml-compliant bibliographical database be provided, **ekdosis** will use it and insert formatted data in the back matter section of its own TEI xml output file, as `<biblStruct>` elements within a `listBibl` section.

As an example, the following Bib(Lᴬ)TₑX entry and its TEI equivalent are provided:[80]—

```
1 @Book{Drak,
2   title = {Punicorum Libri Septemdecim},
3   author = {Silius Italicus, Tiberius Catius},
4   editor = {Drakenborch, Arnold},
5   date = {1717},
6   publisher = {Trajecti ad Rhenum},
7   location = {Utrecht}
8 }
```

```
1 <?xml version="1.0" encoding="UTF-8"?>
2 <listBibl xmlns="http://www.tei-c.org/ns/1.0">
3   <biblStruct type="book" xml:id="Drak">
4     <monogr>
```

---

80. To the author's knowledge, Zotero (https://www.zotero.org) provides excellent TEI xml output from Bib(Lᴬ)TₑX input files.

71

```
 5            <title level="m">Punicorum libri septemdecim</title>
 6            <author>
 7              <forename>Tiberius Catius</forename>
 8              <surname>Silius Italicus</surname>
 9            </author>
10            <editor>
11              <forename>Arnold</forename>
12              <surname>Drakenborch</surname>
13            </editor>
14            <imprint>
15              <pubPlace>Utrecht</pubPlace>
16              <publisher>Trajecti ad Rhenum</publisher>
17              <date>1717</date>
18            </imprint>
19          </monogr>
20        </biblStruct>
21    </listBibl>
```

As can be seen, the same string `Drak` is used as a label in the Bib(LA)TEX file (l. 1) and an `xml:id` in the `TEI` file (l. 3). This same label must be used again in the preamble of the `.tex` source file to declare Arnold Drakenborch as a source,[81] like so:—

```
 1  % Use 'bibl.xml' as a TEI xml bibliographical database:
 2  \AddxmlBibResource{bibdata.xml}
 3
 4  % Declare A. Drakenborch as source:
 5  \DeclareSource{Drak}{\emph{Drakenborch}}
```

Finally, an extract of Silius Italicus' *Punica*, Book 9, ll. 30-2 follows (`.tex` source file, PDF output and `TEI` output files):—

```
 1  % Preamble:
 2  \usepackage[style=oxnotes]{biblatex}
 3  \addbibresource{bibdata.bib}
 4
 5  \usepackage[teiexport=tidy]{ekdosis}
 6
 7  % basename of the .xml bibliographical database:
 8  \AddxmlBibResource{bibdata.xml}
 9
10  % Witnesses:
11  \DeclareWitness{L}{L}{Laurentianus, plut, XXXVII, cod. 16}[
12                       origDate=s. XV]
13  % Other witnesses [...]
14
15  % Sources:
16  \DeclareSource{Drak}{\emph{Drakenborch}}
17  % Alternatively, use BibLaTeX for the rendition:
18  % \DeclareSource{Drak}{\citename{Drak}{editor}}
19  % Other sources [...]
20
21  % Document:
22  \begin{ekdosis}
```

---

81. See above on page 10.

```
23    \begin{ekdverse}
24      Sed uos, quorum oculos atque ora humentia uidi,\\
25      uertere cum consul terga et remeare iuberet,\\
26      \app{
27        \lem[source=Drak, type=emendation]{ne morem}
28        \rdg[wit={L, F}]{me morem}
29        \rdg[wit={O, V}]{memorem}
30      } et pugnae signum exspectate petendae:\\
31    \end{ekdverse}
32  \end{ekdosis}
```

PDF output:—

Sed uos, quorum oculos atque ora humentia uidi,	30
uertere cum consul terga et remeare iuberet,	31
ne morem et pugnae signum exspectate petendae:	32

---

32 ne morem *Drakenborch*] me morem L F memorem O V

TEI xml output file produced by ekdosis (narrowed down to the `<text>` element):—

```
1   <text>
2     <body>
3       <lg>
4         <l>Sed uos, quorum oculos atque ora humentia uidi,</l>
5         <l>uertere cum consul terga et remeare iuberet,</l>
6         <l>
7         <app>
8           <lem source="#Drak" type="emendation">ne morem</lem>
9           <rdg wit="#L #F">me morem</rdg>
10          <rdg wit="#O #V">memorem</rdg>
11        </app>et pugnae signum exspectate petendae:</l>
12      </lg>
13    </body>
14    <back>
15      <listBibl>
16        <biblStruct type="book" xml:id="Drak">
17          <monogr>
18            <title level="m">Punicorum libri septemdecim</title>
19            <author>
20              <forename>Tiberius Catius</forename>
21              <surname>Silius Italicus</surname>
22            </author>
23            <editor>
24              <forename>Arnold</forename>
25              <surname>Drakenborch</surname>
26            </editor>
27            <imprint>
28              <pubPlace>Utrecht</pubPlace>
29              <publisher>Trajecti ad Rhenum</publisher>
30              <date>1717</date>
31            </imprint>
32          </monogr>
```

73

```
33          </biblStruct>
34        </listBibl>
35      </back>
36  </text>
```

12.8   Citation Commands

ekdosis can also convert into `TEI xml` references to cited works. Depending on the optional arguments used in the citation command, references will be converted into `<ptr>` or `<bibl>` elements with the appropriate identifier supplied by means of the `target` or `corresp` attributes.

Of course, for this mechanism to work, BibTEX or BibLATEX must be used and connected to some `.bib` bibliographical database file. Additionally, this `.bib` file must have been converted into a `TEI xml`-compliant file where all the Bib(LA)TEX entries that are used in the document are found within `<biblStruct>` elements.[82]   Finally, this `.xml` bibliographical database must have been connected to the `.tex` source file by means of `\AddxmlBibResource` described above in sect. 12.7 on page 71.

As an example, the following `sample.bib` file is used:—

```
@Book{ReynoldsWilson1991,
  author =           {Reynolds, L. D. and Wilson, N. G.},
  title =           {Scribes and Scholars},
  year =           {1991},
  subtitle =           {A Guide to the Translation of Greek and Latin
                   Literature},
  edition =           {3},
  publisher =           {Clarendon Press},
  location =           {Oxford}
}
```

It has been converted into `sample.xml` as follows:—

```
<?xml version="1.0" encoding="UTF-8"?>
<listBibl xmlns="http://www.tei-c.org/ns/1.0">
  <biblStruct type="book" xml:id="ReynoldsWilson1991">
    <monogr>
      <title level="m">Scribes and Scholars</title>
      <author>
        <forename>L. D.</forename>
        <surname>Reynolds</surname>
      </author>
      <author>
        <forename>N. G.</forename>
        <surname>Wilson</surname>
      </author>
      <edition>3</edition>
      <imprint>
        <pubPlace>Oxford</pubPlace>
        <publisher>Clarendon Press</publisher>
        <date>1991</date>
      </imprint>
    </monogr>
```

---

82. See above n. 80 on page 71 for information on how to do this.

```
      </biblStruct>
</listBibl>
```

Once both files have been prepared, inserting references and exporting them into the `TEI xml` output file can be achieved in a straightforward way. (The full `sample.tex` is provided below.)—

```
\documentclass{article}

\usepackage[teiexport=tidy]{ekdosis}
\AddxmlBibResource{sample.xml}

\usepackage[style=oxnotes]{biblatex}
\addbibresource{sample.bib}

\begin{document}
\begin{ekdosis}
  On textual criticism, see \cite[207--241]{ReynoldsWilson1991}.
\end{ekdosis}
\end{document}
```

PDF output:—

1 On textual criticism, see L. D. Reynolds and N. G. Wilson, *Scribes and Scholars: A*
2 *Guide to the Translation of Greek and Latin Literature* (3rd edn., Oxford: Clarendon Press,
3 1991), 207−41.

`TEI xml` output narrowed down to the contents of the `<text>` element:—

```
<text>
  <body>
    <p>On textual criticism, see
    <bibl corresp="#ReynoldsWilson1991">
      <biblScope>207--241</biblScope>
    </bibl>.</p>
  </body>
  <back>
    <listBibl>
      <biblStruct type="book" xml:id="ReynoldsWilson1991">
        <monogr>
          <title level="m">Scribes and Scholars</title>
          <author>
            <forename>L. D.</forename>
            <surname>Reynolds</surname>
          </author>
          <author>
            <forename>N. G.</forename>
            <surname>Wilson</surname>
          </author>
          <edition>3</edition>
          <imprint>
            <pubPlace>Oxford</pubPlace>
            <publisher>Clarendon Press</publisher>
            <date>1991</date>
          </imprint>
        </monogr>
```

```
        </biblStruct>
      </listBibl>
    </back>
</text>
```

At the time of writing, the following citation commands are converted into `TEI xml` by ekdosis:—

(a) `\icite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`[83]
(b) `\cite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(c) `\Cite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(d) `\cite*[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(e) `\parencite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(f) `\Parencite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(g) `\parencite*[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(h) `\footcite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(i) `\footcitetext[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(j) `\textcite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(k) `\Textcite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(l) `\smartcite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(m) `\Smartcite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(n) `\autocite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(o) `\Autocite[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(p) `\autocite*[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`
(q) `\Autocite*[⟨prenote⟩][⟨postnote⟩]{⟨key⟩}`

The next release of ekdosis will include all citation commands with the exception of so-called "qualified citation lists".

13   Future Work

A short, un-commented list of what is planned in the versions of ekdosis to come follows:—
(a) Very short-term (weeks):—
    (a) Text structure: milestone elements.
    (b) Marginal edition texts: It may happen that the marginalia of manuscripts contain texts worth editing in addition to and along the main text to which they are linked by reference signs.
(b) Short-term (months):—
    (a) Poetry: ekdosis is now able to load and use the facilities provided by the verse package. Refined options will be added, such as metrical analysis. Arabic poetry through the environments and commands provided by the arabluatex package will also be supported. Other packages will also be considered for inclusion, such as poetry or teubner. In the end, ekdosis will provide a way for the typesetting of poetry which will allow for more flexibility and compatibility with `TEI xml`.
    (b) Correspondence and alignment, segmentation: The functions are being tested at the time of writing and will be included in ekdosis.
(c) Medium-term: Indexing, commands and environments for specific modules of the `TEI`.

---

83. From the icite package. `\icite` can be used in place of almost any standard citation command. See Alessi, *The Icite package* (cf. n. 75).

14   GNU Free Documentation License

Version 1.3, 3 November 2008

Preamble

The purpose of this License is to make a manual, textbook, or other functional and useful document "free" in the sense of freedom: to assure everyone the effective freedom to copy and redistribute it, with or without modifying it, either commercially or noncommercially. Secondarily, this License preserves for the author and publisher a way to get credit for their work, while not being considered responsible for modifications made by others.

This License is a kind of "copyleft", which means that derivative works of the document must themselves be free in the same sense. It complements the GNU General Public License, which is a copyleft license designed for free software.

We have designed this License in order to use it for manuals for free software, because free software needs free documentation: a free program should come with manuals providing the same freedoms that the software does. But this License is not limited to software manuals; it can be used for any textual work, regardless of subject matter or whether it is published as a printed book. We recommend this License principally for works whose purpose is instruction or reference.

1. APPLICABILITY AND DEFINITIONS

This License applies to any manual or other work, in any medium, that contains a notice placed by the copyright holder saying it can be distributed under the terms of this License. Such a notice grants a world-wide, royalty-free license, unlimited in duration, to use that work under the conditions stated herein. The "**Document**", below, refers to any such manual or work. Any member of the public is a licensee, and is addressed as "**you**". You accept the license if you copy, modify or distribute the work in a way requiring permission under copyright law.

A "**Modified Version**" of the Document means any work containing the Document or a portion of it, either copied verbatim, or with modifications and/or translated into another language.

A "**Secondary Section**" is a named appendix or a front-matter section of the Document that deals exclusively with the relationship of the publishers or authors of the Document to the Document's overall subject (or to related matters) and contains nothing that could fall directly within that overall subject. (Thus, if the Document is in part a textbook of mathematics, a Secondary Section may not explain any mathematics.) The relationship could be a matter of historical connection with the subject or with related matters, or of legal, commercial, philosophical, ethical or political position regarding them.

The "**Invariant Sections**" are certain Secondary Sections whose titles are designated, as being those of Invariant Sections, in the notice that says that the Document is released under this License. If a section does not fit the above definition of Secondary then it is not

allowed to be designated as Invariant. The Document may contain zero Invariant Sections. If the Document does not identify any Invariant Sections then there are none.

The "**Cover Texts**" are certain short passages of text that are listed, as Front-Cover Texts or Back-Cover Texts, in the notice that says that the Document is released under this License. A Front-Cover Text may be at most 5 words, and a Back-Cover Text may be at most 25 words.

A "**Transparent**" copy of the Document means a machine-readable copy, represented in a format whose specification is available to the general public, that is suitable for revising the document straightforwardly with generic text editors or (for images composed of pixels) generic paint programs or (for drawings) some widely available drawing editor, and that is suitable for input to text formatters or for automatic translation to a variety of formats suitable for input to text formatters. A copy made in an otherwise Transparent file format whose markup, or absence of markup, has been arranged to thwart or discourage subsequent modification by readers is not Transparent. An image format is not Transparent if used for any substantial amount of text. A copy that is not "Transparent" is called "**Opaque**".

Examples of suitable formats for Transparent copies include plain ASCII without markup, Texinfo input format, LaTeX input format, SGML or XML using a publicly available DTD, and standard-conforming simple HTML, PostScript or PDF designed for human modification. Examples of transparent image formats include PNG, XCF and JPG. Opaque formats include proprietary formats that can be read and edited only by proprietary word processors, SGML or XML for which the DTD and/or processing tools are not generally available, and the machine-generated HTML, PostScript or PDF produced by some word processors for output purposes only.

The "**Title Page**" means, for a printed book, the title page itself, plus such following pages as are needed to hold, legibly, the material this License requires to appear in the title page. For works in formats which do not have any title page as such, "Title Page" means the text near the most prominent appearance of the work's title, preceding the beginning of the body of the text.

The "**publisher**" means any person or entity that distributes copies of the Document to the public.

A section "**Entitled XYZ**" means a named subunit of the Document whose title either is precisely XYZ or contains XYZ in parentheses following text that translates XYZ in another language. (Here XYZ stands for a specific section name mentioned below, such as "**Acknowledgements**", "**Dedications**", "**Endorsements**", or "**History**".) To "**Preserve the Title**" of such a section when you modify the Document means that it remains a section "Entitled XYZ" according to this definition.

The Document may include Warranty Disclaimers next to the notice which states that this License applies to the Document. These Warranty Disclaimers are considered to be included by reference in this License, but only as regards disclaiming warranties: any other implication that these Warranty Disclaimers may have is void and has no effect on the meaning of this License.

2. VERBATIM COPYING

You may copy and distribute the Document in any medium, either commercially or noncommercially, provided that this License, the copyright notices, and the license notice saying this License applies to the Document are reproduced in all copies, and that you add no other conditions whatsoever to those of this License. You may not use technical measures to obstruct or control the reading or further copying of the copies you make or distribute. However, you may accept compensation in exchange for copies. If you distribute a large enough number of copies you must also follow the conditions in section 3.

You may also lend copies, under the same conditions stated above, and you may publicly display copies.

3. COPYING IN QUANTITY

If you publish printed copies (or copies in media that commonly have printed covers) of the Document, numbering more than 100, and the Document's license notice requires Cover Texts, you must enclose the copies in covers that carry, clearly and legibly, all these Cover Texts: Front-Cover Texts on the front cover, and Back-Cover Texts on the back cover. Both covers must also clearly and legibly identify you as the publisher of these copies. The front cover must present the full title with all words of the title equally prominent and visible. You may add other material on the covers in addition. Copying with changes limited to the covers, as long as they preserve the title of the Document and satisfy these conditions, can be treated as verbatim copying in other respects.

If the required texts for either cover are too voluminous to fit legibly, you should put the first ones listed (as many as fit reasonably) on the actual cover, and continue the rest onto adjacent pages.

If you publish or distribute Opaque copies of the Document numbering more than 100, you must either include a machine-readable Transparent copy along with each Opaque copy, or state in or with each Opaque copy a computer-network location from which the general network-using public has access to download using public-standard network protocols a complete Transparent copy of the Document, free of added material. If you use the latter option, you must take reasonably prudent steps, when you begin distribution of Opaque copies in quantity, to ensure that this Transparent copy will remain thus accessible at the stated location until at least one year after the last time you distribute an Opaque copy (directly or through your agents or retailers) of that edition to the public.

It is requested, but not required, that you contact the authors of the Document well before redistributing any large number of copies, to give them a chance to provide you with an updated version of the Document.

4. MODIFICATIONS

You may copy and distribute a Modified Version of the Document under the conditions of sections 2 and 3 above, provided that you release the Modified Version under precisely this License, with the Modified Version filling the role of the Document, thus licensing distribution and modification of the Modified Version to whoever possesses a copy of it. In addition, you must do these things in the Modified Version:

A. Use in the Title Page (and on the covers, if any) a title distinct from that of the Document, and from those of previous versions (which should, if there were any, be listed in the History section of the Document). You may use the same title as a previous version if the original publisher of that version gives permission.

B. List on the Title Page, as authors, one or more persons or entities responsible for authorship of the modifications in the Modified Version, together with at least five of the principal authors of the Document (all of its principal authors, if it has fewer than five), unless they release you from this requirement.

C. State on the Title page the name of the publisher of the Modified Version, as the publisher.

D. Preserve all the copyright notices of the Document.

E. Add an appropriate copyright notice for your modifications adjacent to the other copyright notices.

F. Include, immediately after the copyright notices, a license notice giving the public permission to use the Modified Version under the terms of this License, in the form shown in the Addendum below.

G. Preserve in that license notice the full lists of Invariant Sections and required Cover Texts given in the Document's license notice.

H. Include an unaltered copy of this License.

I. Preserve the section Entitled "History", Preserve its Title, and add to it an item stating at least the title, year, new authors, and publisher of the Modified Version as given on the Title Page. If there is no section Entitled "History" in the Document, create one stating the title, year, authors, and publisher of the Document as given on its Title Page, then add an item describing the Modified Version as stated in the previous sentence.

J. Preserve the network location, if any, given in the Document for public access to a Transparent copy of the Document, and likewise the network locations given in the Document for previous versions it was based on. These may be placed in the "History" section. You may omit a network location for a work that was published at least four years before the Document itself, or if the original publisher of the version it refers to gives permission.

K. For any section Entitled "Acknowledgements" or "Dedications", Preserve the Title of the section, and preserve in the section all the substance and tone of each of the contributor acknowledgements and/or dedications given therein.

L. Preserve all the Invariant Sections of the Document, unaltered in their text and in their titles. Section numbers or the equivalent are not considered part of the section titles.

M. Delete any section Entitled "Endorsements". Such a section may not be included in the Modified Version.

N. Do not retitle any existing section to be Entitled "Endorsements" or to conflict in title with any Invariant Section.

O. Preserve any Warranty Disclaimers.

If the Modified Version includes new front-matter sections or appendices that qualify as Secondary Sections and contain no material copied from the Document, you may at your option designate some or all of these sections as invariant. To do this, add their titles to the list of Invariant Sections in the Modified Version's license notice. These titles must be distinct from any other section titles.

You may add a section Entitled "Endorsements", provided it contains nothing but endorsements of your Modified Version by various parties—for example, statements of peer review or that the text has been approved by an organization as the authoritative definition of a standard.

You may add a passage of up to five words as a Front-Cover Text, and a passage of up to 25 words as a Back-Cover Text, to the end of the list of Cover Texts in the Modified Version. Only one passage of Front-Cover Text and one of Back-Cover Text may be added by (or through arrangements made by) any one entity. If the Document already includes a cover text for the same cover, previously added by you or by arrangement made by the same entity you are acting on behalf of, you may not add another; but you may replace the old one, on explicit permission from the previous publisher that added the old one.

The author(s) and publisher(s) of the Document do not by this License give permission to use their names for publicity for or to assert or imply endorsement of any Modified Version.

5. COMBINING DOCUMENTS

You may combine the Document with other documents released under this License, under the terms defined in section 4 above for modified versions, provided that you include in the combination all of the Invariant Sections of all of the original documents, unmodified,

and list them all as Invariant Sections of your combined work in its license notice, and that you preserve all their Warranty Disclaimers.

The combined work need only contain one copy of this License, and multiple identical Invariant Sections may be replaced with a single copy. If there are multiple Invariant Sections with the same name but different contents, make the title of each such section unique by adding at the end of it, in parentheses, the name of the original author or publisher of that section if known, or else a unique number. Make the same adjustment to the section titles in the list of Invariant Sections in the license notice of the combined work.

In the combination, you must combine any sections Entitled "History" in the various original documents, forming one section Entitled "History"; likewise combine any sections Entitled "Acknowledgements", and any sections Entitled "Dedications". You must delete all sections Entitled "Endorsements".

6. COLLECTIONS OF DOCUMENTS

You may make a collection consisting of the Document and other documents released under this License, and replace the individual copies of this License in the various documents with a single copy that is included in the collection, provided that you follow the rules of this License for verbatim copying of each of the documents in all other respects.

You may extract a single document from such a collection, and distribute it individually under this License, provided you insert a copy of this License into the extracted document, and follow this License in all other respects regarding verbatim copying of that document.

7. AGGREGATION WITH INDEPENDENT WORKS

A compilation of the Document or its derivatives with other separate and independent documents or works, in or on a volume of a storage or distribution medium, is called an "aggregate" if the copyright resulting from the compilation is not used to limit the legal rights of the compilation's users beyond what the individual works permit. When the Document is included in an aggregate, this License does not apply to the other works in the aggregate which are not themselves derivative works of the Document.

If the Cover Text requirement of section 3 is applicable to these copies of the Document, then if the Document is less than one half of the entire aggregate, the Document's Cover Texts may be placed on covers that bracket the Document within the aggregate, or the electronic equivalent of covers if the Document is in electronic form. Otherwise they must appear on printed covers that bracket the whole aggregate.

8. TRANSLATION

Translation is considered a kind of modification, so you may distribute translations of the Document under the terms of section 4. Replacing Invariant Sections with translations requires special permission from their copyright holders, but you may include translations of some or all Invariant Sections in addition to the original versions of these Invariant Sections. You may include a translation of this License, and all the license notices in the Document, and any Warranty Disclaimers, provided that you also include the original English version of this License and the original versions of those notices and disclaimers. In case of a disagreement between the translation and the original version of this License or a notice or disclaimer, the original version will prevail.

If a section in the Document is Entitled "Acknowledgements", "Dedications", or "History", the requirement (section 4) to Preserve its Title (section 1) will typically require changing the actual title.

9. TERMINATION

You may not copy, modify, sublicense, or distribute the Document except as expressly provided under this License. Any attempt otherwise to copy, modify, sublicense, or distribute it is void, and will automatically terminate your rights under this License.

However, if you cease all violation of this License, then your license from a particular copyright holder is reinstated (a) provisionally, unless and until the copyright holder explicitly and finally terminates your license, and (b) permanently, if the copyright holder fails to notify you of the violation by some reasonable means prior to 60 days after the cessation.

Moreover, your license from a particular copyright holder is reinstated permanently if the copyright holder notifies you of the violation by some reasonable means, this is the first time you have received notice of violation of this License (for any work) from that copyright holder, and you cure the violation prior to 30 days after your receipt of the notice.

Termination of your rights under this section does not terminate the licenses of parties who have received copies or rights from you under this License. If your rights have been terminated and not permanently reinstated, receipt of a copy of some or all of the same material does not give you any rights to use it.

10. FUTURE REVISIONS OF THIS LICENSE

The Free Software Foundation may publish new, revised versions of the GNU Free Documentation License from time to time. Such new versions will be similar in spirit to the present version, but may differ in detail to address new problems or concerns. See https://www.gnu.org/licenses/.

Each version of the License is given a distinguishing version number. If the Document specifies that a particular numbered version of this License "or any later version" applies to it, you have the option of following the terms and conditions either of that specified version or of any later version that has been published (not as a draft) by the Free Software Foundation. If the Document does not specify a version number of this License, you may choose any version ever published (not as a draft) by the Free Software Foundation. If the Document specifies that a proxy can decide which future versions of this License can be used, that proxy's public statement of acceptance of a version permanently authorizes you to choose that version for the Document.

11. RELICENSING

"Massive Multiauthor Collaboration Site" (or "MMC Site") means any World Wide Web server that publishes copyrightable works and also provides prominent facilities for anybody to edit those works. A public wiki that anybody can edit is an example of such a server. A "Massive Multiauthor Collaboration" (or "MMC") contained in the site means any set of copyrightable works thus published on the MMC site.

"CC-BY-SA" means the Creative Commons Attribution-Share Alike 3.0 license published by Creative Commons Corporation, a not-for-profit corporation with a principal place of business in San Francisco, California, as well as future copyleft versions of that license published by that same organization.

"Incorporate" means to publish or republish a Document, in whole or in part, as part of another Document.

An MMC is "eligible for relicensing" if it is licensed under this License, and if all works that were first published under this License somewhere other than this MMC, and subsequently incorporated in whole or in part into the MMC, (1) had no cover texts or invariant sections, and (2) were thus incorporated prior to November 1, 2008.

The operator of an MMC Site may republish an MMC contained in the site under CC-BY-SA on the same site at any time before August 1, 2009, provided the MMC is eligible for relicensing.

ADDENDUM: How to use this License for your documents

To use this License in a document you have written, include a copy of the License in the document and put the following copyright and license notices just after the title page:

Copyright © YEAR YOUR NAME. Permission is granted to copy, distribute and/or modify this document under the terms of the GNU Free Documentation License, Version 1.3 or any later version published by the Free Software Foundation; with no Invariant Sections, no Front-Cover Texts, and no Back-Cover Texts. A copy of the license is included in the section entitled "GNU Free Documentation License".

If you have Invariant Sections, Front-Cover Texts and Back-Cover Texts, replace the "with … Texts." line with this:

with the Invariant Sections being LIST THEIR TITLES, with the Front-Cover Texts being LIST, and with the Back-Cover Texts being LIST.

If you have Invariant Sections without Cover Texts, or some other combination of the three, merge those two alternatives to suit the situation.

If your document contains nontrivial examples of program code, we recommend releasing these examples in parallel under your choice of free software license, such as the GNU General Public License, to permit their use in free software.

15   References

Alessi, Robert, "ekdosis: Using LuaLaTeX for Producing `TEI xml`-Compliant Critical Editions and Highlighting Parallel Writings," *Journal of Data Mining and Digital Humanities: Collecting, Preserving, and Disseminating Endangered Cultural Heritage for New Understandings through Multilingual Approaches* (Nov. 2020), jdmdh: 6536.

—— *The Arabluatex package* (version 1.20) [ArabTeX for LuaLaTeX] (Mar. 23, 2020), http://ctan.org/pkg/arabluatex.

—— *The Icite package* (version 1.3a) [Indices locorum citatorum] (Mar. 5, 2020), http://ctan.org/pkg/icite.

Bezos López, Javier, *The Titleps package* (version 2.13) [Page style control] (Oct. 16, 2019), https://ctan.org/pkg/titleps.

Bezos López, Javier and Braams, Johannes L., *The Babel package* (version 3.47) [Multilingual support for Plain TeX or LaTeX] (July 13, 2020), http://www.ctan.org/pkg/babel.

Caesar, *Gallic War*, ed. W. A. McDevitte and W. S. Bohn (Harper's New Classical Library; 1st edn., New York: Harper & Brothers, 1869).

Caesar, *Gallic War* (*Guerre des Gaules*), ed. L.-A. Constans (Collection des Universités de France; Paris: Les Belles Lettres, 1987) (originally pub. 1926).

Charette, François and Reutenauer, Arthur, *The Polyglossia package* (version 1.49) [An alternative to babel for XeLaTeX and LuaLaTeX] (Apr. 8, 2020), `http://www.ctan.org/pkg/polyglossia`.

Digital Latin Library, "Textual Criticism," `https://digitallatin.org/library-digital-latin-texts/textual-criticism`, accessed May 24, 2020.

Dunn, Brian, *The Keyfloat package: Provides a key/value interface for generating floats* (version 2.06) (June 29, 2021), `https://ctan.org/pkg/keyfloat`.

Homer, *The Odyssey*, ed. A. T. Murray, 2 vols. (Cambridge, MA. – London: Harvard University Press – William Heinemann, 1919).

Lagally, Klaus, *The Arabtex package* (version 4.00) [Macros and fonts for typesetting Arabic] (Mar. 11, 2004), `http://baobab.informatik.uni-stuttgart.de/ifi/bs/research/arab_e.html`.

Lück, Uwe and Böttcher, Stephan, *The Lineno package* (version 4.41) [Line numbers on paragraphs] (Nov. 2, 2005), `http://www.ctan.org/pkg/lineno`.

MacDonald Alden, Raymond (ed.), *The Sonnets of Shakespeare* [From the Quarto of 1609 with Variorum Readings and Commentary] (Boston & New York: The Riverside Press Cambridge, 1916).

Madsen, Lars and Wilson, Peter R., *The Memoir package* (version 3.7o) [Typeset fiction, non-fiction and mathematical books] (Mar. 23, 2021), `http://www.ctan.org/pkg/memoir`.

Mastronarde, Donald J. and Tarrant, Richard J., "Review: Guidelines for Encoding Critical Editions for the Library of Digital Latin Texts," Society for Classical Studies (Dec. 4, 2017), `https://classicalstudies.org/scs-blog/donald-j-mastronarde/review-guidelines-encoding-critical-editions-library-digital-latin`.

Nakashima, Hiroshi, *The Fnpos package* (version 1.0) [Control the position of footnotes on the page] (Sept. 3, 2018), `http://www.ctan.org/pkg/fnpos`.

—— *The Paracol package* (version 1.35) [Multiple columns with texts "in parallel"] (Dec. 31, 2018), `http://www.ctan.org/pkg/paracol`.

Reynolds, L. D. and Wilson, N. G., *Scribes and Scholars: A Guide to the Translation of Greek and Latin Literature* (3rd edn., Oxford: Clarendon Press, 1991).

Rozhenko, Alexander I., *The Extdash package* (version 1.3) [A range of dash commands for compound words] (June 24, 2018), `http://www.ctan.org/pkg/extdash`.

Sturm, Thomas F., *The Tcolorbox package: Coloured boxes, for LaTeX examples and theorems, etc* (version 4.51) (June 14, 2021), `https://ctan.org/pkg/tcolorbox`.

Van den Branden, Ron, Terras, Melissa, and Vanhoutte, Edward, "TEI by Example," `http://www.teibyexample.org`, accessed Aug. 4, 2020.

West, Martin L., *Textual Criticism and Editorial Technique* [Applicable to Greek and Latin Texts] (Stuttgart: B. G. Teubner, 1973).

Wilson, Peter R. and Robertson, Will, *The Verse package* (version 2.4b) [Aids for typesetting simple verse] (May 10, 2014), `http://www.ctan.org/pkg/verse`.

16 Sample: C. J. Caesar, *Gallic War*, VI, XIII.1

16.1 `.tex` Source File

```latex
\documentclass[12pt]{article}
\usepackage{fontspec}
\usepackage[latin.classic,french,english]{babel}
\babelfont{rm}{Old Standard}
\babelfont{sf}{NewComputerModernSans10}
\babelfont{tt}{NewComputerModernMono10}

\usepackage{nextpage}
\usepackage{xltabular}

\usepackage[teiexport=tidy]{ekdosis}
\DeclareApparatus{default}[
        delim=\hskip0.75em,
        ehook=.]

\FormatDiv{2}{}{.}

\SetAlignment{
  tcols=3,
  lcols=1,
  texts=latin[xml:lang="la"];
        english[xml:lang="en"];
        french[xml:lang="fr"],
  apparatus=latin,
  segmentation=auto}

\AtBeginEnvironment{latin}{\selectlanguage{latin}}
\AtBeginEnvironment{english}{\sloppy\selectlanguage{english}}
\AtBeginEnvironment{french}{\sloppy\selectlanguage{french}}

\DeclareWitness{A}{A}{\emph{Bongarsianus} 81}[
                msName=Bongarsianus,
                settlement=Amsterdam,
                idno=81,
                institution=University Library,
                origDate=s. IX--X]
\DeclareHand{A1}{A}{A\textsuperscript{1}}[\emph{Emendationes
                scribae ipsius}]
\DeclareWitness{M}{M}{\emph{Parisinus Lat.} 5056}[
                origDate={s. XII}]
\DeclareWitness{B}{B}{\emph{Parisinus Lat.} 5763}[
                origDate={s. IX--X}]
\DeclareWitness{R}{R}{\emph{Vaticanus Lat.} 3864}[
                origDate={s. X}]
\DeclareWitness{S}{S}{\emph{Laurentianus} R 33}[
                origDate={s. X}]
\DeclareWitness{L}{L}{\emph{Londinensis} Br. Mus. 10084}[
                origDate={s. XI}]
\DeclareWitness{N}{N}{\emph{Neapolitanus} IV, c. 11}[
                origDate={s. XII}]
```

```
51    \DeclareWitness{T}{T}{\emph{Parisinus Lat.} 5764}[
52                    origDate={s. XI}]
53    \DeclareWitness{f}{\emph{f}}{\emph{Vindobonensis} 95}[
54                    origDate={s. XII}]
55    \DeclareWitness{U}{U}{\emph{Vaticanus Lat.} 3324}[
56                    origDate={s. XI}]
57    \DeclareWitness{l}{\emph{l}}{\emph{Laurentianus} Riccard. 541}[
58                    origDate={s. XI--XII}]
59    \DeclareShorthand{a}{α}{A,M,B,R,S,L,N}
60    \DeclareShorthand{b}{β}{T,f,U,l}
61
62    \begin{document}
63
64    \begin{xltabular}[c]{0.75\linewidth}{lXl}
65      \caption*{\textbf{Conspectus siglorum}\label{tab:conspectus-siglorum}}\\
66      \multicolumn{3}{c}{\emph{Familia} \getsiglum{a}}\\
67      \SigLine{A}\\
68      & \getsiglum{A1} \emph{Emendationes scribae ipsius} & \\
69      \SigLine{M}\\
70      \SigLine{B}\\
71      \SigLine{R}\\
72      \SigLine{S}\\
73      \SigLine{L}\\
74      \SigLine{N}\\
75      \multicolumn{3}{c}{\emph{Familia} \getsiglum{b}}\\
76      \SigLine{T}\\
77      \SigLine{f}\\
78      \SigLine{U}\\
79      \SigLine{l}\\
80    \end{xltabular}
81
82    \cleartoevenpage
83
84    \begin{alignment}
85      \begin{latin}
86        \ekddiv{head=XIII, depth=2, n=6.13, type=section}
87        In omni Gallia eorum hominum qui \app{
88          \lem[wit=a]{aliquo}
89          \rdg[wit=b, alt=in al-]{in aliquo}}
90        sunt numero atque honore genera sunt duo. Nam plebes paene
91        seruorum habetur loco, quae \app{
92          \lem[wit={A,M}, alt={nihil audet (aut et \getsiglum{A1})
93            per se}]{nihil audet per se}
94          \rdg[wit=A1,nordg]{nihil aut et per se}
95          \rdg[wit={R,S,L,N}]{nihil habet per se}
96          \rdg[wit=b]{per se nihil audet}}, \app{
97          \lem[wit=a]{nullo}
98          \rdg[wit=b]{nulli}} adhibetur \app{
99          \lem{consilio}
100         \rdg[wit={T, U}, alt=conc-]{concilio}}.
101     \end{latin}
102     \begin{english}
103       \ekddiv{head=XIII, depth=2, n=6.13, type=section}
104       Throughout all Gaul there are two orders of those men who are of
105       any rank and dignity: for the commonality is held almost in the
```

```latex
106        condition of slaves, and dares to undertake nothing of itself,
107        and is admitted to no deliberation.
108      \end{english}
109      \begin{french}
110        \ekddiv{head=XIII, depth=2, n=6.13, type=section}
111        Partout en Gaule il y a deux classes d'hommes qui comptent et qui
112        sont considérés. Quant aux gens du peuple, ils ne sont guère
113        traités autrement que des esclaves, ne pouvant se permettre aucune
114        initiative, n'étant consultés sur rien.
115      \end{french}
116    \end{alignment}
117
118  \end{document}
```

16.2   TEI xml Output

```xml
1   <?xml version="1.0" encoding="utf-8"?>
2   <TEI xmlns="http://www.tei-c.org/ns/1.0">
3     <teiHeader>
4       <fileDesc>
5         <titleStmt>
6           <title>
7             <!-- Title -->
8           </title>
9           <respStmt>
10            <resp>
11              <!-- Edited by -->
12            </resp>
13            <name>
14              <!-- Name -->
15            </name>
16          </respStmt>
17        </titleStmt>
18        <publicationStmt>
19          <distributor>
20            <!-- Distributor name  -->
21          </distributor>
22        </publicationStmt>
23        <sourceDesc>
24          <listWit>
25            <witness xml:id="A">
26            <abbr type="siglum">A</abbr>
27            <emph>Bongarsianus</emph>81
28            <msDesc>
29              <msIdentifier>
30                <settlement>Amsterdam</settlement>
31                <institution>University Library</institution>
32                <idno>81</idno>
33                <msName>Bongarsianus</msName>
34              </msIdentifier>
35              <physDesc>
36                <handDesc hands="1">
37                  <handNote xml:id="A1">
```

```
38            <abbr type="siglum">A
39            <hi rend="sup">1</hi></abbr>
40            <p>
41              <emph>Emendationes scribae ipsius</emph>
42            </p>
43          </handNote>
44        </handDesc>
45      </physDesc>
46      <history>
47        <origin>
48          <origDate>s. IX--X</origDate>
49        </origin>
50      </history>
51    </msDesc></witness>
52    <witness xml:id="M">
53    <abbr type="siglum">M</abbr>
54    <emph>Parisinus Lat.</emph>5056
55    <msDesc>
56      <msIdentifier />
57      <history>
58        <origin>
59          <origDate>s. XII</origDate>
60        </origin>
61      </history>
62    </msDesc></witness>
63    <witness xml:id="B">
64    <abbr type="siglum">B</abbr>
65    <emph>Parisinus Lat.</emph>5763
66    <msDesc>
67      <msIdentifier />
68      <history>
69        <origin>
70          <origDate>s. IX--X</origDate>
71        </origin>
72      </history>
73    </msDesc></witness>
74    <witness xml:id="R">
75    <abbr type="siglum">R</abbr>
76    <emph>Vaticanus Lat.</emph>3864
77    <msDesc>
78      <msIdentifier />
79      <history>
80        <origin>
81          <origDate>s. X</origDate>
82        </origin>
83      </history>
84    </msDesc></witness>
85    <witness xml:id="S">
86    <abbr type="siglum">S</abbr>
87    <emph>Laurentianus</emph>R 33
88    <msDesc>
89      <msIdentifier />
90      <history>
91        <origin>
92          <origDate>s. X</origDate>
```

```
 93              </origin>
 94            </history>
 95          </msDesc></witness>
 96          <witness xml:id="L">
 97          <abbr type="siglum">L</abbr>
 98          <emph>Londinensis</emph>Br. Mus. 10084
 99          <msDesc>
100            <msIdentifier />
101            <history>
102              <origin>
103                <origDate>s. XI</origDate>
104              </origin>
105            </history>
106          </msDesc></witness>
107          <witness xml:id="N">
108          <abbr type="siglum">N</abbr>
109          <emph>Neapolitanus</emph>IV, c. 11
110          <msDesc>
111            <msIdentifier />
112            <history>
113              <origin>
114                <origDate>s. XII</origDate>
115              </origin>
116            </history>
117          </msDesc></witness>
118          <witness xml:id="T">
119          <abbr type="siglum">T</abbr>
120          <emph>Parisinus Lat.</emph>5764
121          <msDesc>
122            <msIdentifier />
123            <history>
124              <origin>
125                <origDate>s. XI</origDate>
126              </origin>
127            </history>
128          </msDesc></witness>
129          <witness xml:id="f">
130          <abbr type="siglum">
131            <emph>f</emph>
132          </abbr>
133          <emph>Vindobonensis</emph>95
134          <msDesc>
135            <msIdentifier />
136            <history>
137              <origin>
138                <origDate>s. XII</origDate>
139              </origin>
140            </history>
141          </msDesc></witness>
142          <witness xml:id="U">
143          <abbr type="siglum">U</abbr>
144          <emph>Vaticanus Lat.</emph>3324
145          <msDesc>
146            <msIdentifier />
147            <history>
```

```xml
148              <origin>
149                <origDate>s. XI</origDate>
150              </origin>
151            </history>
152          </msDesc></witness>
153          <witness xml:id="l">
154          <abbr type="siglum">
155            <emph>l</emph>
156          </abbr>
157          <emph>Laurentianus</emph>Riccard. 541
158          <msDesc>
159            <msIdentifier />
160            <history>
161              <origin>
162                <origDate>s. XI--XII</origDate>
163              </origin>
164            </history>
165          </msDesc></witness>
166        </listWit>
167      </sourceDesc>
168    </fileDesc>
169    <encodingDesc>
170      <variantEncoding method="parallel-segmentation"
171      location="internal" />
172    </encodingDesc>
173  </teiHeader>
174  <text>
175    <body>
176      <div xml:id="div-latin_1" xml:lang="la">
177        <div type="section" n="6.13">
178          <head>XIII</head>
179          <p>In omni Gallia eorum hominum qui
180          <app>
181            <lem wit="#A #M #B #R #S #L #N">aliquo</lem>
182            <rdg wit="#T #f #U #l">in aliquo</rdg>
183          </app>sunt numero atque honore genera sunt duo. Nam
184          plebes paene seruorum habetur loco, quae
185          <app>
186            <lem wit="#A #M">nihil audet per se</lem>
187            <rdg wit="#A1">nihil aut et per se</rdg>
188            <rdg wit="#R #S #L #N">nihil habet per se</rdg>
189            <rdg wit="#T #f #U #l">per se nihil audet</rdg>
190          </app>,
191          <app>
192            <lem wit="#A #M #B #R #S #L #N">nullo</lem>
193            <rdg wit="#T #f #U #l">nulli</rdg>
194          </app>adhibetur
195          <app>
196            <lem>consilio</lem>
197            <rdg wit="#T #U">concilio</rdg>
198          </app>.</p>
199        </div>
200      </div>
201      <div xml:id="div-english_1" xml:lang="en">
202        <div type="section" n="6.13">
```

```
203          <head>XIII</head>
204          <p>Throughout all Gaul there are two orders of those men
205          who are of any rank and dignity: for the commonality is
206          held almost in the condition of slaves, and dares to
207          undertake nothing of itself, and is admitted to no
208          deliberation.</p>
209        </div>
210      </div>
211      <div xml:id="div-french_1" xml:lang="fr">
212        <div type="section" n="6.13">
213          <head>XIII</head>
214          <p>Partout en Gaule il y a deux classes d'hommes qui
215          comptent et qui sont considérés. Quant aux gens du
216          peuple, ils ne sont guère traités autrement que des
217          esclaves, ne pouvant se permettre aucune initiative,
218          n'étant consultés sur rien.</p>
219        </div>
220      </div>
221    </body>
222  </text>
223 </TEI>
```

17 Arabic Sample File

`arabic-sample.tex:`—

```
% Instructions:
% 1. Compile this file three times.
%    – Open arabic-sample.pdf and arabic-sample-tei.xml and see the
%      result.
% 2. Compile arabic-sample_out.tex three times.
%    – Open arabic-sample_out.pdf and arabic-sample-out-tei.xml and
%      see the result.
%
\documentclass{article}

% The following three lines are only needed by the
% 'arabic-sample_out.tex' that arabluatex is instructed to produce:
\usepackage{babel}
\babelprovide[onchar=fonts]{arabic}
\babelfont[*arabic]{rm}{Amiri}

% instruct ekdosis to output TEI xml (arabic-sample-tei.xml):
\usepackage[teiexport=tidy]{ekdosis}

% instruct arabluatex to output sample-arabic_out.tex with Unicode
% Arabic strings in place of arabtex ASCII scheme:
\usepackage[fullvoc,export]{arabluatex}

\begin{document}

\begin{arabexport} % export arabtex strings to Unicode Arabic
  \begin{ekdosis}
```

```
  \begin{arab}
    'inna 'abI kAna mina
    \app{
      \lem{'l-muqAtilaTi}
      \rdg{'l-muqAtilIna}
    }
    wa-kAnat 'ummI min `u.zamA'i buyUti 'l-zamAzimaTi.
  \end{arab}
  \end{ekdosis}
\end{arabexport}
\end{document}
```

18   Implementation

ekdosis relies on Lua functions and tables. Read the `.lua` files that accompany ekdosis for more information.

```
1 \RequirePackage{iftex}
```

Of course, ekdosis requires LuaLaTeX. Issue an error if the document is processed with another engine.

```
2 \RequireLuaTeX
```

Set global options:—

```
 3 \RequirePackage{expkv-opt}
 4 \RequirePackage{expkv-def}
 5 \newif\if@pkg@float
 6 \newif\if@pkg@footins
 7 \newif\if@pkg@keyfloat
 8 \newif\if@pkg@fitapp
 9 \newif\if@pkg@ekddivs
10 \newif\if@parnotesroman
11 \newif\if@pkg@parnotes
12 \newif\iftei@export
13 \newif\if@pkg@poetry@verse
14 \ekvdefinekeys{ekdosis}{
15   choice layout = {float = {\@pkg@floattrue},
16     footins = {\@pkg@floatfalse\@pkg@footinstrue},
17     keyfloat = {\@pkg@floatfalse\@pkg@keyfloattrue},
18     fitapp = {\@pkg@floatfalse\@pkg@fitapptrue}},
19   initial layout = float,
20   unknown-choice layout = \PackageError{ekdosis}{unknown
21     layout=#1}{`layout' must be either `float' or `footins'.},
22   choice divs = {ekdosis = {\@pkg@ekddivstrue},
23     latex = {\@pkg@ekddivsfalse
24       \AtBeginDocument{\luadirect{ekdosis.setekddivsfalse()}}}},
25   initial divs = ekdosis,
26   unknown-choice divs = \PackageError{ekdosis}{unknown divs=#1}{`divs'
27     must be either `ekdosis' or `latex'.},
28   choice poetry = {verse = {\@pkg@poetry@versetrue}},
29   unknown-choice poetry = \PackageError{ekdosis}{unknown
30     poetry=#1}{`poetry' must be `verse' for now.},
31   choice parnotes = {false = {},
32     true = {\@pkg@parnotestrue},
33     roman = {\@pkg@parnotestrue\@parnotesromantrue}},
```

```
34    default parnotes = true,
35    unknown-choice parnotes = \PackageError{ekdosis}{unknown
36      parnotes=#1}{`parnotes' must be either `true', or `false' or
37      `roman'.},
38    choice teiexport = {false = {},
39      true = {\tei@exporttrue
40        \AtBeginDocument{\luadirect{ekdosis.openteistream()}}%
41        \AtEndDocument{\luadirect{ekdosis.closeteistream()}}},
42      tidy = {\tei@exporttrue
43        \AtBeginDocument{\luadirect{ekdosis.openteistream()}}%
44        \AtEndDocument{\luadirect{ekdosis.closeteistream("tidy")}}}},
45    default teiexport = true,
46    unknown-choice teiexport = \PackageError{ekdosis}{unknown
47      teiexport=#1}{`teiexport' must be either `true', `false' or
48      `tidy'.}
49 }
50 \ekvoProcessLocalOptions{ekdosis}
51 \newif\ifekd@memoir@loaded
52 \@ifclassloaded{memoir}{%
53    \ekd@memoir@loadedtrue\@pkg@poetry@versetrue}{}
```

Required Packages   In addition to iftex, expkv-opt and expkv-def, a list of the packages that are required by ekdosis follows:—

```
54 % \RequirePackage{iftex} % already loaded above
55 % \RequirePackage{expkv-opt} % already loaded above
56 % \RequirePackage{expkv-def} % already loaded above
57 \RequirePackage{luacode}
58 \RequirePackage{paracol}
59 \RequirePackage{etoolbox}
60 \RequirePackage{lineno}
61 \if@pkg@float
62    \RequirePackage{trivfloat}
63    \trivfloat{ekdapparatus}
64 \fi
65 \if@pkg@keyfloat
66    \RequirePackage{keyfloat}
67    \def\ekd@keyparopts#1{%
68      \def\ekd@insert@keyparapp{%
69        \keyparbox[!b]{#1}{\ekd@insert@apparatus}}}
70    \ekd@keyparopts{}
71 \fi
72 \if@pkg@fitapp
73    \RequirePackage{tcolorbox}
74    \tcbuselibrary{fitting,skins}
75 \fi
76 \RequirePackage{refcount}
77 \RequirePackage{zref-user}
78 \RequirePackage{zref-abspage}
79 \RequirePackage{ltxcmds}
80 \RequirePackage{pdftexcmds}
81 \RequirePackage{ifoddpage}
82 \if@pkg@poetry@verse
83    \RequirePackage{verse}
84 \fi
85 \if@pkg@parnotes
```

```
86    \RequirePackage{parnotes}
87 \fi
```

Lua   Here begins the real work: load `ekdosis.lua`:—

```
88 \luadirect{dofile(kpse.find_file("ekdosis.lua"))}

89 \AtEndDocument{
90    \luadirect{ekdosis.closestream()}
91 }
```

Setup

\ekdsetup   **\ekdsetup** is used to specify options that affect the general behavior of ekdosis. It is a preamble-only command.

```
92 \ekvdefinekeys{ekd@setup}{
93    bool showpagebreaks = \ifekd@showpb,
94    store spbmk = \ekd@spbmk,
95    initial spbmk = spb,
96    store hpbmk = \ekd@hpbmk,
97    initial hpbmk = hpb,
98 }
99 \NewDocumentCommand{\ekdsetup}{m}{\ekvset{ekd@setup}{#1}}
100 \@onlypreamble\ekdsetup
```

\SetHooks   **\SetHooks** is used to set hooks meant to be shared by all declared apparatuses, such as the font size, the format of numerals, &c. This command can be used in the preamble or at any point of the document.

```
101 \ekvdefinekeys{ekd@hooks}{
102    store appfontsize = \ekd@appfontsize,
103    store refnumstyle = \ekd@refnumstyle,
104    store postrefnum = \ekd@postrefnum,
105    code familysep = \luadirect{ekdosis.setfamilysep(\luastringN{#1})},
106    store lemmastyle = \ekd@lemmastyle,
107    store readingstyle = \ekd@readingstyle,
108    code keyparopts = \if@pkg@keyfloat\ekd@keyparopts{#1}\fi,
109    dimen appheight = \ekd@app@height,
110    initial appheight = .5\textheight,
111    choice fitalgorithm = {fontsize = \def\ekd@fit@algorithm{fontsize},
112       hybrid = \def\ekd@fit@algorithm{hybrid},
113       areasize = \def\ekd@fit@algorithm{areasize},
114       squeeze = \def\ekd@fit@algorithm{squeeze}},
115    initial fitalgorithm = fontsize,
116    unknown-choice fitalgorithm = \PackageError{ekdosis}{unknown
117       fitalgorithm=#1}{`fitalgorithm' must be either `fontsize',
118       `hybrid', `areasize' or `squeeze'.},
119    code initialrule = \def\ekd@initial@rule{#1\NLS},
120    default initialrule = \rule{0.4\columnwidth}{0.4pt},
121    noval noinitialrule = \undef\ekd@initial@rule,
122    initial appfontsize = \footnotesize,
123    initial refnumstyle = \bfseries,
124    initial postrefnum = ~,
125    initial lemmastyle = {},
126    initial readingstyle = {}
127 }
128 \NewDocumentCommand{\SetHooks}{m}{\ekvset{ekd@hooks}{#1}}
```

Build and process the list of witnesses and hands:—

```
129 \ekvdefinekeys{ekd@witness}{
130   store settlement = \settlement@value,
131   store institution = \institution@value,
132   store repository = \repository@value,
133   store collection = \collection@value,
134   store idno = \idno@value,
135   store msName = \msName@value,
136   store origDate = \origDate@value,
137   store locus = \locus@value
138 }
```

\DeclareWitness **\DeclareWitness** is a preamble-only command. It takes three mandatory arguments and one optional argument. It is meant to collect data related to witnesses to be used in the edition text. Data are stored in `Lua` tables and are used to encode the `<listWit>` part of the `TEI` header as well as the Conspectus Siglorum in the edition in print.

```
139 \NewDocumentCommand{\DeclareWitness}{m m m O{}}{%
140   \bgroup
141   \ekvset{ekd@witness}{#4}
142     \luadirect{ekdosis.newwitness(
143       \luastringN{#1},
144       \luastringN{#2},
145       \luastringN{#3},
146       \luastringO{\settlement@value},
147       \luastringO{\institution@value},
148       \luastringO{\repository@value},
149       \luastringO{\collection@value},
150       \luastringO{\idno@value},
151       \luastringO{\msName@value},
152       \luastringO{\origDate@value},
153       \luastringO{\locus@value})}
154     \egroup
155   }
156 \@onlypreamble\DeclareWitness
```

\DeclareHand As **\DeclareWitness**, **\DeclareHand** is a preamble-only command meant to collect data and store them in `Lua` tables. It takes three mandatory arguments and one optional argument. The second argument is used to connect the hand to a declared witness it is related to. Then the table in which this witness is recorded can be fed with new data.

```
157 \NewDocumentCommand{\DeclareHand}{m m m +O{}}{
158   \luadirect{ekdosis.newhand(\luastringN{#1},
159     \luastringN{#2},
160     \luastringN{#3},
161     \luastringN{#4})}
162 }
163 \@onlypreamble\DeclareHand
```

Build and process the list of scholars:—

```
164 \ekvdefinekeys{ekd@scholar}{
165   store rawname = \rawname@value,
166   store forename = \forename@value,
167   store surname = \surname@value,
168   store addname = \addname@value,
169   store note = \note@value
170 }
```

95

\DeclareScholar   **\DeclareScholar** is used to build a list of persons within the `<listPerson>` element. It takes two mandatory arguments to specify consecutively a unique identifier and the rendition to be used in the apparatus criticus in print, and one optional argument used to collect the name parts components and further items of information from `key-value` 'named' arguments.

```
171 \NewDocumentCommand{\DeclareScholar}{m m O{}}{%
172   \bgroup
173   \ekvset{ekd@scholar}{#3}
174     \luadirect{ekdosis.newscholar(
175       \luastringN{#1},
176       \luastringN{#2},
177       \luastringO{\rawname@value},
178       \luastringO{\forename@value},
179       \luastringO{\surname@value},
180       \luastringO{\addname@value},
181       \luastringO{\note@value})}
182     \egroup
183   }
184 \@onlypreamble\DeclareScholar
```

\DeclareSource   There is also a table in which are collected data related to sources to be used in the apparatus criticus. **\DeclareSource** is a preamble-only command and takes two mandatory arguments: a unique id and a shorthand (preferably a Bib(LA)TEX label) to be used in the apparatus criticus which can be extracted from a bibliographic database.

```
185 \NewDocumentCommand{\DeclareSource}{m m}{
186   \luadirect{ekdosis.newsource(\luastringN{#1},
187     \luastringN{#2})}
188 }
189 \@onlypreamble\DeclareSource
```

\DeclareShorthand   **\DeclareShorthand** is a preamble-only command that can be used to record manuscript families or any kind of shorthand to be used to refer to previously declared ids, for example the shorthand `codd` can be used to point to all declared witnesses. This command takes three mandatory arguments: a unique id, its rendition in print and a csv-list of previously declared ids.

```
190 \NewDocumentCommand{\DeclareShorthand}{m m m}{
191   \luadirect{ekdosis.newshorthand(\luastringN{#1},
192     \luastringN{#2},
193     \luastringN{#3})}
194 }
195 \@onlypreamble\DeclareShorthand
```

\getsiglum   **\getsiglum**{⟨*csv list*⟩} takes a comma-separated list of declared ids by means of **\DeclareWitness**, **\DeclareHand**, **\DeclareShorthand** or **\DeclareSource** and returns their respective renditions.

```
196 \NewDocumentCommand{\getsiglum}{m}{%
197   \luadirect{tex.sprint(ekdosis.getsiglum(\luastringN{#1}))}%
198 }
```

\SigLine   **\Sigline**{⟨*unique id*⟩} takes the unique id of any declared witness by means of **\DeclareWitness** as argument and returns a line ready to be inserted in a table set to print a Conspectus Siglorum. **\SigLine** returns three fields separated by the symbol **&** that is used in tables as follows: the siglum referring to the witness, the contents of the `description` field and the contents of the optional `origDate` field.

```
199 \NewDocumentCommand{\SigLine}{m}{%
200   \luadirect{tex.sprint(ekdosis.basic_cs(\luastringN{#1}))}
201 }
```

T_EX to TEI xml Here follow the `key-value` options to be used by `\SetTEIxmlExport` below:—

```
202 \ekvdefinekeys{tei@settings}{
203   choice autopar = {true = \luadirect{ekdosis.setteiautopar("yes")},
204     false = {\luadirect{ekdosis.setteiautopar("no")}}},
205   initial autopar = true,
206   unknown-choice autopar = \PackageError{ekdosis}{unknown
207     autopar=#1}{`autopar' must be either `true' or `false'.}
208 }
```

\SetTEIxmlExport   `\SetTEIxmlExport` collects the settings to be applied to `TEI xml` export. For now, there is only one option. This command can be used at any point of the document, except inside environments meant to receive an apparatus criticus.

```
209 \NewDocumentCommand{\SetTEIxmlExport}{m}{
210   \unless\ifekd@state\ekvset{tei@settings}{#1}\fi
211 }
```

The following three commands can be used to instruct **ekdosis** how to convert unknown or unusual (L^A)T_EX commands into `TEI xml` equivalents.

\TeXtoTEI   `\TeXtoTEI{⟨csname⟩}{⟨TEI element⟩}[⟨TEI attribute(s)⟩]` takes two mandatory arguments and one optional argument, namely: the control sequence name to be converted, the `TEI` element it is to be converted into and any additional `xml` attributes to be appended to the opening `TEI` element:—

```
212 \NewDocumentCommand{\TeXtoTEI}{m m O{}}{%
213   \luadirect{ekdosis.newcmdtotag(\luastringN{#1},
214     \luastringN{#2},
215     \luastringN{#3})}
216 }
```

\teidirect   `\teidirect[⟨xml attributes⟩]{⟨xml element⟩}{⟨code⟩}` does nothing in L^AT_EX. Its only use is to insert elements in the `TEI xml` output file.

```
217 \NewDocumentCommand{\teidirect}{O{}mm}{\ignorespaces}
```

\EnvtoTEI
\EnvtoTEI*   `\EnvtoTEI⟨*⟩{⟨env name⟩}{⟨TEI element⟩}[⟨TEI attribute(s)⟩]` instructs how to convert L^AT_EX environments into `TEI xml` equivalents. It takes two mandatory arguments and one optional argument, namely the name of the L^AT_EX environment to be converted, the `TEI` element it is to be converted into and any additional attributes to be appended to the `TEI` opening element. `\EnvtoTEI*` is restricted to `TEI` elements that must never appear within `<p>` elements, such as `<div>`, `<lg>` and the like.

```
218 \NewDocumentCommand{\EnvtoTEI}{s m m O{}}{%
219   \IfBooleanTF{#1}{%
220   \luadirect{ekdosis.newenvtotag(\luastringN{#2},
221     \luastringN{#3},
222     \luastringN{#4},
223     "yes")}
224   }{%
225   \luadirect{ekdosis.newenvtotag(\luastringN{#2},
226     \luastringN{#3},
```

```
227      \luastringN{#4})}
228    }
229 }
```

\TeXtoTEIPat Finally, the more flexible—and more delicate to handle—**\TeXtoTEIPat**{⟨*T$_E$X pattern*⟩}
{⟨**TEI** *pattern*⟩} uses pattern matching to instruct ekdosis how to convert (L*A*)T$_E$X commands
into **TEI** equivalents.

```
230 \NewDocumentCommand{\TeXtoTEIPat}{m m}{%
231    \luadirect{ekdosis.newpatttotag(\luastringN{#1}, \luastringN{#2})}
232 }
```

\SetTEIFilename **\SetTEIFilename**{⟨*basename*⟩} is a preamble-only command. It is used to set the base
name of the **TEI xml** output file, to which the suffix **.xml** is appended. By default, the base
name is **\jobname-tei**:—

```
233 \NewDocumentCommand{\SetTEIFileName}{m}{
234    \luadirect{ekdosis.setteifilename(\luastringN{#1})}
235 }
236 \@onlypreamble\SetTEIFileName
```

\AddxmlBibResource This is a preamble-only command. If a base name (either suffixed with **.xml** or not) for a **TEI**
xml-compliant bibliographical database file be provided with **\AddxmlBibResource**{⟨*basename*
or name.xml⟩}, ekdosis will use it and insert formatted data in the back matter section of
its own **TEI xml** output file, as **<biblStruct>** elements within a **<listBibl>** section.

```
237 \NewDocumentCommand{\AddxmlBibResource}{m}{
238    \luadirect{ekdosis.addxmlbibresource(\luastringN{#1})}
239 }
240 \@onlypreamble\AddxmlBibResource
```

\ekd@test@lang **\ekd@test@lang** is used internally by ekdosis. This command returns **\ekd@lang@pkgtrue**
if either babel or polyglossia be used so that **\languagename** can be inserted when and
where needed in the apparatus criticus.

```
241 \newif\ifekd@lang@pkg
242 \NewDocumentCommand{\ekd@test@lang}{}{%
243    \ltx@ifpackageloaded{babel}{\ekd@lang@pkgtrue}{}%
244    \ltx@ifpackageloaded{polyglossia}{\ekd@lang@pkgtrue}{}%
245 }
```

Multiple-layer apparatuses   ekdosis must know if an entry is to be processed in a single-
or multiple-layer context:—

```
246 \newif\ifekd@mapps
```

Now the key-value options can be defined:—

```
247 \ekvdefinekeys{ekd@newapp}{
248    choice direction = {LR = \def\direction@val{LR},
249                        RL = \def\direction@val{RL}},
250    unknown-choice direction = \PackageError{ekdosis}{unknown
251      direction=#1}{`direction' must be either `LR' or `RL'.},
252    store rule = \rule@val,
253    nmeta norule = {rule=none},
254    code delim = \def\delim@val{\unexpanded{#1}},
255    store sep = \sep@val,
256    store subsep = \subsep@val,
257    store bhook = \bhook@val,
258    store ehook = \ehook@val,
```

```
259    store maxentries = \limit@val,
260    store lang = \lang@val,
261    store notelang = \notelang@val,
262    initial direction = LR,
263    initial delim = {},
264    initial ehook = {\csname ekd@end@apparatus\endcsname}
265 }
```

\DeclareApparatus   \DeclareApparatus{⟨*apparatus name*⟩}[⟨*options*⟩] is a preamble-only command. As a
mandatory argument, it takes the name of the new layer of notes to be inserted in the
apparatus block. Then, the following seven key-value options can be used to lay out the
layer: direction=LR|RL, rule, delim (the delimiter between entries), sep (the separator
between lemma part and readings or notes), bhook (LaTeX code inserted as the layer begins),
ehook (LaTeX code inserted as the layer ends), maxentries (if set and maxentries >= 10,
the number of entries at which a \pagebreak is issued):—

```
266 \NewDocumentCommand{\DeclareApparatus}{m O{}}{
267    \newbool{subsq@unit@#1}
268    \booltrue{subsq@unit@#1}
269    \unless\ifekd@mapps\global\ekd@mappstrue\fi
270    \bgroup
271    \ekvset{ekd@newapp}{#2}
272    \luadirect{ekdosis.newapparatus(
273      \luastringN{#1},
274      \luastring{\direction@val},
275      \luastringO{\rule@val},
276      \luastringO{\delim@val},
277      \luastringO{\sep@val},
278      \luastringO{\subsep@val},
279      \luastringO{\bhook@val},
280      \luastringO{\ehook@val},
281      \luastringO{\limit@val},
282      \luastringO{\lang@val},
283      \luastringO{\notelang@val}
284      )}
285    \egroup
286 }
287 \@onlypreamble\DeclareApparatus
```

\addentries   If maxentries be set for a given layer of critical notes, \addentries[⟨*layer*⟩]{⟨*n*⟩}, where
⟨*n*⟩ is an integer, can be used to add ⟨*n*⟩ to—or remove it from if ⟨*n*⟩ be negative—the
number of accepted entries on the current page. \addentries operates on the default
layer of notes, but any other declared layer can be specified in the optional argument of the
command.

```
288 \NewDocumentCommand{\addentries}{O{\ekdan@type} m}{%
289    \luadirect{ekdosis.addto_bagunits(\luastringO{#1}, \luastringN{#2})}%
290    \ignorespaces
291 }
```

\ekdpb   \ekdpk[⟨*page no*⟩]{⟨*line no*⟩} is used to insert conditional page breaks by specifying that
the page break should occur only on a given line and optionally a given page. If the specified
conditions be met then this command triggers \pagebreak.

```
292 \newcounter{ekd@pb}
293 \globalcounter{ekd@pb}
294 \NewDocumentCommand{\ekdpb}{s o m}{%
```

```
295   \IfBooleanTF{#1}
296   {\ifekd@showpb\marginpar{\ekd@hpbmk}\fi
297     \pagebreak}
298   {%
299     \def\@tmpoarg{#2}%
300     \def\@tmpmarg{#3}%
301     \stepcounter{ekd@pb}%
302     \linelabel{ekdpb:\theekd@pb}%
303     \def\tmp@ln{%
304       \getrefnumber{ekdpb:\theekd@pb}}%
305     \def\tmp@pg{%
306       \getpagerefnumber{ekdpb:\theekd@pb}}%
307     \IfNoValueTF{#2}
308     {\ifnum
309       \pdf@strcmp{\@tmpmarg}{\tmp@ln} = 0
310       \ifekd@showpb\marginpar{\ekd@spbmk}\fi
311       \pagebreak
312       \else
313       \ifekd@showpb\marginpar{[\ekd@spbmk]}\fi
314       \fi}
315     {\ifnum
316       \pdf@strcmp{\@tmpoarg}{\tmp@pg} = 0
317       \ifnum
318       \pdf@strcmp{\@tmpmarg}{\tmp@ln} = 0
319       \ifekd@showpb\marginpar{\ekd@spbmk}\fi
320       \pagebreak
321       \else
322       \ifekd@showpb\marginpar{[\ekd@spbmk]}\fi
323       \fi
324       \fi
325     }%
326   }\ignorespaces
327 }
```

Apparatus-related settings and functions. Some booleans to check if an apparatus should be inserted and what is the current environment.

```
328 \newbool{do@app}
329 \newif\ifekd@state
330 \newif\ifekd@isinapp
331 \newif\ifekd@isinlem
332 \newif\ifekd@appinapp
```

The next boolean is shared with arabluatex. \LRnum is used internally to ensure that numerals referring to line spans are displayed in the right order.

```
333 \providebool{al@rlmode}
334 \@ifpackageloaded{arabluatex}{}{%
335   \def\setRL{\booltrue{al@rlmode}\pardir TRT\textdir TRT}
336   \def\setLR{\boolfalse{al@rlmode}\pardir TLT \textdir TLT}
337 }
338 \protected\def\LRnum#1{\bgroup\textdir TLT#1\egroup}
```

Set counter referring to line numbers and make it global.

```
339 \newcounter{ekd@lab}
340 \globalcounter{ekd@lab}
```

This command inserts words in the apparatus criticus without checking if both ekd@isinapp and ekd@state are set to true.

```
341 \NewDocumentCommand{\unconditional@appin}{o m}{%
342   \IfNoValueTF{#1}
343   {\luadirect{ekdosis.appin(\luastringO{#2})}}
344   {\luadirect{ekdosis.appin(\luastringO{#2}, \luastringO{#1})}}}%
345 }
```

\blfootnote **\blfootnote{⟨*footnote*⟩}** is used internally to insert the apparatus in the footnote block should the global optional argument `layout` be set to `footins`. Therefore, it is not documented.

```
346 \def\blfootnote{\gdef\@thefnmark{\relax}\@footnotetext}
347 % \def\blfootnote{\gdef\@thefnmark{}\@blfootnotetext}
348 \long\def\@blfootnotetext#1{\insert\footins{%
349     \reset@font\footnotesize
350     \interlinepenalty\interfootnotelinepenalty
351     \splittopskip\footnotesep
352     \splitmaxdepth \dp\strutbox \floatingpenalty \@MM
353     \hsize\columnwidth \@parboxrestore
354     \protected@edef\@currentlabel{%
355         \csname p@footnote\endcsname\@thefnmark
356     }%
357     \color@begingroup
358       \@makeblfntext{%
359         \rule\z@\footnotesep\ignorespaces#1\@finalstrut\strutbox}%
360     \color@endgroup}}%
361 \newcommand\@makeblfntext[1]{%
362     \parindent 1em%
363     \noindent
364     \hb@xt@0em{\hss\@makefnmark}#1}
```

Single-layer apparatus   The following commands are for general settings. All of them can be used in the preamble or at any point of the document. The keys to be used follow:—

```
365 \newif\ifrtl@app
366 \edef\ekdsep{] }
367 \edef\ekdsubsep{}
368 \ekvdefinekeys{default@app}{
369   choice direction = {LR = \rtl@appfalse,
370     RL = \rtl@apptrue},
371   unknown-choice direction = \PackageError{ekdosis}{unknown
372     direction=#1}{`direction' must be either `LR' or `RL'.},
373   code sep = \edef\ekdsep{#1},
374   code subsep = \edef\ekdsubsep{#1},
375   store bhook = \ekd@begin@apparatus,
376   initial bhook = {},
377   store ehook = \ekd@end@apparatus,
378   initial ehook = {},
379   store delim = \ekd@unit@delim,
380   initial delim = {},
381   store rule = \ekd@default@rule,
382   initial rule = \rule{0.4\columnwidth}{0.4pt},
383   noval norule = \def\ekd@default@rule{\mbox{}},
384   store lang = \ekd@singleapp@lang,
385   initial lang = \ltx@ifpackageloaded{babel}{\languagename}{%
386     \ltx@ifpackageloaded{polyglossia}{\languagename}{}},
387   store notelang = \ekd@singleapp@note@lang,
388   initial notelang = \ltx@ifpackageloaded{babel}{\languagename}{%
```

\SetApparatus   All settings can also be defined as `key-value` options within the argument of **\SetApparatus**:—

391 \NewDocumentCommand{\SetApparatus}{m}{
392   \ekvset{default@app}{#1}
393 }

\SetLTRapp   **\SetLTRapp** and **\SetRTLapp** are two argument-less commands to set the direction of
\SetRTLapp   single-layer apparatus criticus, either LTR or RTL:—

394 \NewDocumentCommand{\SetRTLapp}{}{\rtl@apptrue}
395 \NewDocumentCommand{\SetLTRapp}{}{\rtl@appfalse}

\SetSeparator   **\SetSeparator**{⟨*separator*⟩} allows to change the separator between lemma texts and
variant readings, which is by default a closing square bracket followed by a space (]␣):—

396 \NewDocumentCommand{\SetSeparator}{m}{\edef\ekdsep{#1}}

\SetSubseparator   **\SetSubseparator**{⟨*sub-separator*⟩} allows to change the "subseparator" between variant
readings. By default, no subseparator is set:—

397 \NewDocumentCommand{\SetSubseparator}{m}{\edef\ekdsubsep{#1}}

\SetBeginApparatus   **\SetBeginApparatus**{⟨*characters*⟩} can be used to append characters at the beginning of
the apparatus block. By default, nothing is appended:—

398 \NewDocumentCommand{\SetBeginApparatus}{m}{\edef\ekd@begin@apparatus{#1}}

\SetEndApparatus   **\SetEndApparatus**{⟨*characters*⟩} can be used to append characters at the end of the
apparatus block—such as a period, as it is customary in some editions. By default, nothing
is appended:—

399 \NewDocumentCommand{\SetEndApparatus}{m}{\edef\ekd@end@apparatus{#1}}

\SetUnitDelimiter   **\SetUnitDelimiter**{⟨*delimiter*⟩} can be used to set the delimiter between entries
in the apparatus criticus. By default, there is no delimiter except a simple space.
\SetUnitDelimiter can be used to insert a broad space (with **\hskip** for instance, as in
the OCT series) or the divider-sign (‖, as in the Budé series):—

400 \NewDocumentCommand{\SetUnitDelimiter}{m}{\def\ekd@unit@delim{#1}}

\SetApparatusLanguage   **\SetApparatusLang**{⟨*languagename*⟩} can be used when it is needed to apply in the
apparatus criticus a language different from the one that is selected in the edition text.

401 \NewDocumentCommand{\SetApparatusLanguage}{m}{%
402   \def\ekd@singleapp@lang{#1}}

\SetApparatusNoteLanguage   **\SetApparatusNoteLang**{⟨*languagename*⟩} can be used when it is needed to apply in
entries introduced by the **\note** command a language different from the one that is selected
in the edition text.

403 \NewDocumentCommand{\SetApparatusNoteLanguage}{m}{%
404   \def\ekd@singleapp@note@lang{#1}}

\footnoteruletrue   As ekdosis takes care of drawing a rule separating the main text from the apparatus
\footnoterulefalse   block as well as layers of notes from each other inside this block, it may not be desir-
able to have the standard LaTeX "footnoterule" printed on every page of the edition text.
\footnoterulefalse removes it while **\footnoteruletrue** leaves it untouched. The
latter is set by default.

405 \newif\iffootnoterule

```
406 \footnoteruletrue
407 \let\dflt@footnoterule\footnoterule
408 \let\dflt@pcol@footnoterule\pcol@footnoterule
409 \renewcommand\footnoterule{%
410   \iffootnoterule
411   \dflt@footnoterule%
412   \fi
413 }
414 \renewcommand\pcol@footnoterule{%
415   \iffootnoterule
416   \dflt@pcol@footnoterule%
417   \fi
418 }
```

\SetDefaultRule By default, ekdosis draws separating rules the definition of which is `\rule{0.4\columnwid th}{0.4pt}`. This can be changed in the preamble or at any point of the document with `\SetDefaultRule{⟨rule definition⟩}`. Leaving this argument empty as in `\SetDefaultRule{}` removes the rule.

```
419 \NewDocumentCommand{\SetDefaultRule}{m}{%
420   \def\@tempa{#1}
421   \ifx\@tempa\empty\def\ekd@default@rule{\mbox{}}%
422   \else%
423   \def\ekd@default@rule{#1}%
424   \fi}
```

\NLS \NLS was previously adapted from a snippet written by Heiko Oberdiek. It is used by ekdosis internally to prevent page breaks between separating rules and subsequent notes. Therefore, it is not documented.

```
425 \newcommand*{\NLS}{%
426   \nobreak\@normalcr\relax
427   % \par
428   % \nobreak
429   % \vspace{-\parskip}%
430   % \leavevmode
431   % \noindent
432   % \ignorespaces
433 }
```

This boolean is used to test if a given entry is to be preceded by a numeral referring to the line of the edition text.

```
434 \newif\ifsubsq@unit
435 \subsq@unittrue
```

\add@@apparatus inserts the apparatus block on a given page either in the footnote floating block or in a float of its own, depending on the value set in the `layout` global option. As some commands need to know whether they are called from inside the apparatus criticus, two conditionals are first defined.

```
436 \newif\ifekd@inside@app
437 \newif\ifekd@keepinapp
```

Then \ekd@fitapp is defined for `layout=fitapp`:—

```
438 \if@pkg@fitapp
439   \newtcboxfit{\ekd@fitapp}{%
440     blankest,
441     fit basedim = \f@size pt,
```

```
442     fit fontsize macros,
443     fit height from=0pt to \ekd@app@height,
444     fit algorithm = \ekd@fit@algorithm,
445     float=!b}
446 \fi
```

Finally two commands are used to actually insert the apparatus depending on the value set in the `layout` global option.

```
447 \long\def\ekd@insert@apparatus{%
448   \unless\ifekd@mapps
449   \ifrtl@app\pardir TRT\leavevmode\textdir TRT\else
450     \pardir TLT\leavevmode\textdir TLT\fi
451   \fi
452   \if@pkg@parnotes
453    \if@parnotesroman
454    \renewcommand*{\theparnotemark}{\roman{parnotemark}}\fi
455    \parnoteclear\fi
456   \ekd@inside@apptrue
457   \ekd@appfontsize
458   \ifekd@mapps
459     \ifdefined\ekd@initial@rule
460       \ekd@initial@rule
461     \fi
462   \fi
463   \apparatus\unless\ifekd@mapps\ekd@end@apparatus\fi
464   \ekd@inside@appfalse
465   \if@pkg@parnotes\parnotes\parnotereset\fi
466 }%
467 \def\add@@apparatus{%
468   \if@pkg@parnotes\parnotes\else\fi
469   \if@pkg@footins
470   \bgroup
471     \unless\ifekd@mapps
472       \ifrtl@app\pardir TRT\leavevmode\textdir TRT\else
473         \pardir TLT\leavevmode\textdir TLT\fi
474     \fi
475   \blfootnote{%
476     \if@pkg@parnotes
477     \if@parnotesroman
478     \renewcommand*{\theparnotemark}{\roman{parnotemark}}\else\fi
479     \parnoteclear\else\fi
480     \ekd@inside@apptrue
481     \ekd@appfontsize
482     \ifekd@mapps
483       \ifdefined\ekd@initial@rule
484         \ekd@initial@rule
485       \fi
486     \fi
487     \apparatus\unless\ifekd@mapps\ekd@end@apparatus\fi
488     \ekd@inside@appfalse
489     \if@pkg@parnotes\parnotes\parnotereset\else\fi
490   }%
491   \egroup
492   \fi
493   \if@pkg@float
494   \begin{ekdapparatus}[!b]%
```

104

```
495        \ekd@insert@apparatus
496    \end{ekdapparatus}%
497    \fi
498    \if@pkg@keyfloat
499        \ekd@insert@keyparapp
500    \fi
501    \if@pkg@fitapp
502        \ekd@fitapp{\ekd@insert@apparatus}%
503    \fi
504 }
```

Before inserting any new entry, **\add@apparatus** calls **\test@apparatus** to decide whether a new apparatus block must be created on a given page.

```
505 \def\add@apparatus{%
506    \test@apparatus%
507    \ifbool{do@app}{\subsq@unitfalse\add@@apparatus}{}%
508 }
```

\append@app inserts a bare (sub)entry in the apparatus...

```
509 \NewDocumentCommand{\append@app}{o +m}{%
510    \ifekd@isinapp%
511        \ifekd@state%
512        \IfNoValueTF{#1}%
513            {\luadirect{ekdosis.appin(\luastringO{#2})}}%
514            {\luadirect{ekdosis.appin(\luastringO{#2}, \luastringO{#1})}}%
515        \fi%
516    \fi}
```

while **\append@ln@app** inserts a (sub)entry possibly preceded by a line number.

```
517 \NewDocumentCommand{\append@ln@app}{o +m}{%
518    \IfNoValueTF{#1}
519    {\luadirect{tex.sprint(ekdosis.mdvappend(\luastringO{#2}))}}
520    {\luadirect{tex.sprint(ekdosis.mdvappend(\luastringO{#2},
521        \luastringO{#1}))}}}
```

Lineation Settings

\outerlinenumbers   ekdosis does not use the "pagewise" numbering mode that is provided by lineno. Therefore,
\innerlinenumbers   **\outerlinenumbers** and **\innerlinenumbers** are defined in addition to **\rightlinenum bers** and **\leftlinenumbers**.

```
522 \def\outerlinenumbers{%
523    \def\makeLineNumberRunning{%
524        \checkoddpage
525        \ifoddpage
526        \linenumberfont\hskip\linenumbersep\hskip\textwidth
527        \hbox to\linenumberwidth{\hss\LineNumber}\hss
528        \else
529        \hss\linenumberfont\LineNumber\hskip\linenumbersep
530        \fi
531    }%
532 }
533 \def\innerlinenumbers{%
534    \def\makeLineNumberRunning{%
535        \checkoddpage
536        \ifoddpage
537        \hss\linenumberfont\LineNumber\hskip\linenumbersep
```

```
538    \else
539    \linenumberfont\hskip\linenumbersep\hskip\textwidth
540    \hbox to\linenumberwidth{\hss\LineNumber}\hss
541    \fi
542  }%
543 }
```

The keys to be used for lineation settings follow. A conditional is defined beforehand so that ekdosis may know whether the numbering should start afresh at the top of each page.

```
544 \newif\ifekd@pagelineation
545 \newif\ifekd@pagevlineation
546 \NewDocumentCommand{\ekdatbegshihook}{}{%
547   \ifekd@pagelineation\resetlinenumber\fi
548 }
549 \AddToHook{shipout/before}{\ekdatbegshihook}
550 \newif\ifekd@elidednumbers
551 \ekvdefinekeys{ekd@lineation}{
552   choice lineation = {page = \ekd@pagelineationtrue,
553     document = \ekd@pagelineationfalse,
554     none = \ekd@pagelineationtrue
555           \renewcommand\thelinenumber{}},
556   unknown-choice lineation = \PackageError{ekdosis}{unknown
557     lineation=#1}{`lineation' must be either `page' or `document'.},
558   choice vlineation = {page = \ekd@pagevlineationtrue,
559     document = \ekd@pagevlineationfalse},
560   unknown-choice vlineation = \PackageError{ekdosis}{unknown
561     vlineation=#1}{`vlineation' must be either `page' or `document'.},
562   code modulonum = \chardef\c@linenumbermodulo#1\relax,
563   noval modulo = \modulolinenumbers,
564   code vmodulo = \ifekd@memoir@loaded\linenumberfrequency{#1}
565                 \else\if@pkg@poetry@verse\poemlines{#1}\fi\fi,
566   initial vmodulo = 1,
567   default vmodulo = 5,
568   bool vnumbrokenlines = \ifnum@brokenline,
569   bool continuousvnum = \if@continuous@vnum,
570   choice numbers = {elided = \ekd@elidednumberstrue,
571     full = \ekd@elidednumbersfalse},
572   unknown-choice numbers = \PackageError{ekdosis}{unknown
573     numbers=#1}{`numbers' must be either `elided' or `full'.},
574   initial numbers = elided,
575   choice margin = {right = \rightlinenumbers,
576     left = \leftlinenumbers,
577     inner = \innerlinenumbers,
578     outer = \outerlinenumbers},
579   unknown-choice margin = \PackageError{ekdosis}{unknown
580     margin=#1}{`margin' must be either `left', `right', \MessageBreak
581     `inner' or `outer'},
582   choice vmargin = {
583     right = \if@pkg@poetry@verse\verselinenumbersright\fi,
584     left = \if@pkg@poetry@verse\verselinenumbersleft\fi},
585   unknown-choice vmargin = \PackageError{ekdosis}{unknown
586     vmargin=#1}{`margin' must be either `left' ot `right'}
587 }
```

\SetLineation Then `\SetLineation{⟨options⟩}` can be used in the preamble or at any point of the document to set lineation preferences. Its argument processes the `key-value` options that are defined just above.

```
588 \NewDocumentCommand{\SetLineation}{m}{
589   \ekvset{ekd@lineation}{#1}
590 }
```

\vmodulolinenumbers

```
591 \NewDocumentCommand{\vmodulolinenumbers}{O{5}}{%
592   \ifekd@memoir@loaded
593     \linenumberfrequency{#1}%
594   \else
595     \if@pkg@poetry@verse
596       \poemlines{#1}%
597     \fi
598   \fi
599   \ignorespaces
600 }
```

Use `\normalfont` for line numbers:—

```
601 \renewcommand\linenumberfont{\normalfont\footnotesize}
```

\SetDefaultApparatus By default, **ekdosis** defines one layer of critical notes which is called `default`. This name can be changed at any point of the document with `\SetDefaultApparatus{⟨name⟩}`.

```
602 \ekvdefinekeys{appnote}{
603   store type = \ekdan@type,
604   initial type = default
605 }
606 \NewDocumentCommand{\SetDefaultApparatus}{m}{%
607   \ekvset{appnote}{type=#1}}
```

\app `\app[type=⟨type⟩]{⟨apparatus entries⟩}` takes one mandatory argument and accepts one optional argument. `type=` refers to the layer the note must go into and ⟨apparatus entries⟩ contains command used to insert the entries, either `\lem`, `\rdg` or `\note⟨*⟩`:—

```
608 \NewDocumentCommand{\app}{O{} > { \TrimSpaces } +m}{%
609   \leavevmode
610   \begingroup
611   \ekvset{appnote}{#1}%
612   \ifekd@isinapp\ekd@appinapptrue\fi
613   \ekd@isinapptrue
614   \stepcounter{ekd@lab}%
615   \zlabel{ekd:\theekd@lab}%
616   \luadirect{ekdosis.storeabspg(
617     \luastring{\zref@extract{ekd:\theekd@lab}{abspage}})}%
618   \ifekd@state\add@apparatus\fi
619   \luadirect{tex.sprint(ekdosis.removesp(\luastringN{#2}))}%
620   \ekd@isinappfalse
621   \ekd@appinappfalse
622   \endgroup}
```

\ekdpage Instead of absolute page numbers, **ekdosis** now marks the entries of the apparatus with its own page numbering scheme. `\ekdpage` can be used at any point of the document to retrieve and print the current number.

```
623 \NewDocumentCommand{\ekdpage}{}{%
```

```
624    \luadirect{tex.sprint(ekdosis.getekdabspg())}%
625 }
```

`\current@ref@arg` is used outside `\app` by `\note`. It takes two mandatory arguments: the beginning line label and the ending line label—which are manually inserted—and returns the formatted reference to be inserted in the apparatus criticus.

```
626 \def\current@ref@arg#1#2{{%\textdir TLT%
627     \unexpanded\expandafter{\ekd@refnumstyle}%
628     \ifnum%
629     \pdf@strcmp{\getpagerefnumber{#1}}{\getpagerefnumber{#2}}
630     =
631     0
632     \ifnum%
633     \pdf@strcmp{\getrefnumber{#1}}{\getrefnumber{#2}}
634     =
635     0
636     %
637     \ifekd@mapps%
638     \ifbool{subsq@unit@\ekdan@type}{%
639       \ifnum%
640       \pdf@strcmp{\getrefnumber{#1}}{%
641         \getrefnumber{\luadirect{tex.sprint(ekdosis.getprevnotelab())}}}}
642       =
643       0
644       \else
645       \LRnum{\getrefnumber{#1}}\unexpanded\expandafter{\ekd@postrefnum}% issue the no
646       \fi%
647     }%
648     {\LRnum{\getrefnumber{#1}}\unexpanded\expandafter{\ekd@postrefnum}}% issue the no
649     \else
650     \ifsubsq@unit%
651     %
652     \ifnum%
653     \pdf@strcmp{\getrefnumber{#1}}{%
654       \getrefnumber{\luadirect{tex.sprint(ekdosis.getprevnotelab())}}}}
655     =
656     0
657     \else
658     \LRnum{\getrefnumber{#1}}\unexpanded\expandafter{\ekd@postrefnum}% issue the no
659     \fi
660     %
661     \else
662     \LRnum{\getrefnumber{#1}}\unexpanded\expandafter{\ekd@postrefnum}% issue the no
663     \fi
664     \fi
665     %
666     \else
667     \ifekd@elidednumbers
668     \luadirect{tex.sprint(ekdosis.numrange(\luastring{\getrefnumber{#1}},
669       \luastring{\getrefnumber{#2}}))}%
670         \unexpanded\expandafter{\ekd@postrefnum}% issue the nos
671     \else
672     \LRnum{\getrefnumber{#1}}--%
673     \LRnum{\getrefnumber{#2}}\unexpanded\expandafter{\ekd@postrefnum}% issue the nos
674     \fi
```

```latex
675       \fi%
676     \else
677     \ifboolexpr{bool {ekd@pagelineation} or bool {ekd@pagevlineation}}
678       {\LRnum{\getrefnumber{#1}}--%
679       \LRnum{\getpagerefnumber{#2}}.%
680       \LRnum{\getrefnumber{#2}}\unexpanded\expandafter{\ekd@postrefnum}}% issue pg and ln nos
681       {\LRnum{\getrefnumber{#1}}--%
682       \LRnum{\getrefnumber{#2}}\unexpanded\expandafter{\ekd@postrefnum}}% issue the nos
683     \fi%
684     \ifekdn@forcenum
685       \LRnum{\getrefnumber{#1}}\unexpanded\expandafter{\ekd@postrefnum}% force the no
686     \fi
687   }%
688 }
```

`\current@ref` is pretty much the same as `\current@reg@arg`, but takes no argument.
It is used by commands such as `\lem` when references to page and line numbers can be
returned by Lua.

```latex
689 \def\current@ref{{%\textdir TLT%
690     \unexpanded\expandafter{\ekd@refnumstyle}%
691     \ifnum%
692     \pdf@strcmp{%
693       \getpagerefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
694       {\getpagerefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}
695     =
696     0
697     \ifnum%
698     \pdf@strcmp{%
699       \getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
700       {\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}
701     =
702     0
703     %
704     \ifekd@mapps%
705     \ifbool{subsq@unit@\ekdan@type}{%
706       \ifnum%
707       \pdf@strcmp{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
708       {\getrefnumber{\luadirect{tex.sprint(ekdosis.getprevlnlab())}-b}}
709       =
710       0
711     %%%begin
712     \ifnum%
713     \pdf@strcmp{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}%
714     {\getrefnumber{\luadirect{tex.sprint(ekdosis.getprevlnlab())}-e}}
715     =
716     0
717     \ifekd@appinapp
718     \ifnum%
719     \pdf@strcmp{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
720     {\getrefnumber{\luadirect{tex.sprint(ekdosis.getprevprevlnlab())}-b}}
721     =
722     0
723     \else
724     \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
725       \unexpanded\expandafter{\ekd@postrefnum}% issue the no
726     \fi
```

```
727    \fi
728    \else
729    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
730      \unexpanded\expandafter{\ekd@postrefnum}% issue the no
731    \fi
732    %%% end
733      \else
734      \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
735        \unexpanded\expandafter{\ekd@postrefnum}% issue the no
736      \fi%
737    }{\LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
738      \unexpanded\expandafter{\ekd@postrefnum}}% issue the no
739    \else
740    \ifsubsq@unit%
741    %
742    \ifnum%
743    \pdf@strcmp{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
744    {\getrefnumber{\luadirect{tex.sprint(ekdosis.getprevlnlab())}-b}}
745    =
746    0
747    %%%begin
748    \ifnum%
749    \pdf@strcmp{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}%
750    {\getrefnumber{\luadirect{tex.sprint(ekdosis.getprevlnlab())}-e}}
751    =
752    0
753    \ifekd@appinapp
754    \ifnum%
755    \pdf@strcmp{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
756    {\getrefnumber{\luadirect{tex.sprint(ekdosis.getprevprevlnlab())}-b}}
757    =
758    0
759    \else
760    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
761      \unexpanded\expandafter{\ekd@postrefnum}% issue the no
762    \fi
763    \fi
764    \else
765    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
766      \unexpanded\expandafter{\ekd@postrefnum}% issue the no
767    \fi
768    %%% end
769    \else
770    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
771      \unexpanded\expandafter{\ekd@postrefnum}% issue the no
772    \fi
773    %
774    \else
775    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
776      \unexpanded\expandafter{\ekd@postrefnum}% issue the no
777    \fi
778    \fi
779    %
780    \else
781    \ifekd@elidednumbers
```

```
782    \luadirect{tex.sprint(ekdosis.numrange(
783      \luastring{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}},
784      \luastring{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}))}%
785        \unexpanded\expandafter{\ekd@postrefnum}% issue the nos
786    \else
787    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}--%
788    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}%
789        \unexpanded\expandafter{\ekd@postrefnum}% issue the nos
790    \fi
791    \fi%
792    \else
793    \ifboolexpr{bool {ekd@pagelineation} or bool {ekd@pagevlineation}}
794      {\LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}--%
795      \LRnum{\getpagerefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}.%
796      \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}%
797        \unexpanded\expandafter{\ekd@postrefnum}}% issue pg and ln nos
798      {\LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}--%
799      \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-e}}%
800        \unexpanded\expandafter{\ekd@postrefnum}}% issue the nos
801    \fi%
802    \ifekdl@forcenum
803    \LRnum{\getrefnumber{\luadirect{tex.sprint(ekdosis.getlnlab())}-b}}%
804      \unexpanded\expandafter{\ekd@postrefnum}% force the no
805    \fi
806  }%
807 }
```

Define keys to be used by the optional arguments of `\lem` and `\rdg`:—

```
808 \newif\ifekdl@forcenum
809 \newif\ifekdl@nonum
810 \ekvdefinekeys{lem}{
811   code wit = \def\ekdlr@wit{#1},
812   code source = \def\ekdlr@source{#1},
813   code resp = \def\ekdlr@resp{#1},
814   code alt  = \def\ekdlr@alt{#1},
815   code pre = \def\ekdlr@pre{#1},
816   code post = \def\ekdlr@post{#1},
817   code prewit = \def\ekdlr@prewit{#1},
818   code postwit = \def\ekdlr@postwit{#1},
819   store type = \ekdlr@type,
820   store sep = \ekdl@sep,
821   noval nonum = \ekdl@nonumtrue,
822   noval num = \ekdl@forcenumtrue,
823   bool nolem = \ifekdl@nolem,
824   bool nosep = \ifekdl@nosep,
825   initial sep = \ekdsep
826 }
827 \ekvdefinekeys{rdg}{
828   code wit = \def\ekdlr@wit{#1},
829   code source = \def\ekdlr@source{#1},
830   code resp = \def\ekdlr@resp{#1},
831   code alt  = \def\ekdlr@alt{#1},
832   code pre = \def\ekdlr@pre{#1},
833   code post = \def\ekdlr@post{#1},
834   code prewit = \def\ekdlr@prewit{#1},
835   code postwit = \def\ekdlr@postwit{#1},
```

```
836    store subsep = \ekdr@subsep,
837    initial subsep = \ekdsubsep,
838    bool nosubsep = \ifekdr@nosubsep,
839    store type = \ekdlr@type,
840    bool nordg = \ifekdr@nordg
841 }
```

\rdgGrp **\rdgGrp**[⟨*option*⟩]{⟨*lemma and/or readings*⟩} may be used to group readings so as to indicate subvariation in apparatus entries. This command is expected inside **\app{}**, and takes as argument readings to be grouped introduced by means of **\lem** and/or **\rdg** commands. It further accepts **type** as an optional key-value argument to describe the type of grouping.

```
842 \NewDocumentCommand{\rdgGrp}{O{} > {\TrimSpaces } m}{%
843    \luadirect{tex.sprint(ekdosis.removesp(\luastringN{#2}))}%
844 }
```

\app@lang **\app@lang** is used internally by **\lem** and **\rdg** to set the language for apparatus entries.
\app@note@lang **\note** uses **\@note@lang**.

```
845 \def\app@lang{%
846    \ifekd@mapps
847    \luadirect{tex.sprint(ekdosis.getapplang(\luastring{\ekdan@type}))}%
848    \else
849    \ekd@singleapp@lang
850    \fi
851 }
852 \def\app@note@lang{%
853    \ifekd@mapps
854    \luadirect{tex.sprint(ekdosis.getappnotelang(\luastring{\ekdan@type}))}%
855    \else
856    \ekd@singleapp@note@lang
857    \fi
858 }
```

\lem **\lem**[⟨*options*⟩]{⟨*lemma text*⟩} inserts ⟨*lemma text*⟩ both in the edition text and in the apparatus criticus by default, preceded by the reference to the line number or a space if it is the same number as the one of the previous entry. This command accepts the optional key-value arguments just defined above.

```
859 \NewDocumentCommand{\lem}{O{} m}{%
860    \ekd@isinlemtrue%
861    \luadirect{ekdosis.dolnlab(\luastringN{#2})}%
862    \null
863    \bgroup%
864    \ekdl@forcenumfalse
865    \ekdl@nonumfalse
866    \ekvset{lem}{#1}%
867    \ekd@test@lang
868    \ifekd@mapps%
869       \ifnum%
870       \luadirect{tex.sprint(ekdosis.get_bagunits(\luastringO{\ekdan@type}))}
871       = 1
872       \boolfalse{subsq@unit@\ekdan@type}%
873       \fi%
874       \luadirect{ekdosis.increment_bagunits(\luastringO{\ekdan@type})}%
875       \def\ekd@munit@delim{%
876          \luadirect{tex.sprint(ekdosis.getappdelim(\luastringO{\ekdan@type}))}}%
```

```
877      \luadirect{tex.sprint(ekdosis.limit_bagunits(\luastringO{\ekdan@type}))}%
878    \fi%
879    \ifekdl@nolem\edef\lem@app{%
880      % \hskip .75em
881      \ifekd@mapps
882      \ifbool{subsq@unit@\ekdan@type}%
883      {\ekd@munit@delim}{}%
884      \else%
885      \ifsubsq@unit\unexpanded\expandafter{\ekd@unit@delim}\fi%
886      \fi%
887      \unless\ifekdl@nonum\current@ref\fi}%\hskip .25em}%
888    \else%
889    \ifbool{al@rlmode}{%
890      \edef\lem@app{%
891        % \hskip .75em
892        \ifekd@mapps
893        \ifbool{subsq@unit@\ekdan@type}%
894        {\ekd@munit@delim}{}%
895        \else%
896        \ifsubsq@unit\unexpanded\expandafter{\ekd@unit@delim}\fi%
897        \fi%
898        \unless\ifekdl@nonum\current@ref\fi%\hskip .25em
899        \ifdefined\ekdlr@alt%
900          \ifdefined\ekdlr@post%
901            \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
902            {\textdir TRT\unexpanded\expandafter{\ekd@lemmastyle}%
903              \unexpanded\expandafter{\ekdlr@alt}}%
904          \ifdefined\ekdlr@pre%
905            \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
906        \else
907          \ifdefined\ekdlr@post%
908            \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
909            {\textdir TRT\unexpanded\expandafter{\ekd@lemmastyle}%
910              \unexpanded{#2}}%
911          \ifdefined\ekdlr@pre%
912            \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
913        \fi
914        \ifdefined\ekdlr@postwit%
915          \space\unexpanded\expandafter{\ekdlr@postwit}\else\fi
916        \ifdefined\ekdlr@resp\space\getsiglum{\ekdlr@resp}\else\fi
917        \ifdefined\ekdlr@source\space\getsiglum{\ekdlr@source}\else\fi
918        \ifdefined\ekdlr@wit\space\getsiglum{\ekdlr@wit}\else\fi
919        \ifdefined\ekdlr@prewit%
920          \space\unexpanded\expandafter{\ekdlr@prewit}\space\else\fi
921        \ifekdl@nosep\else\unexpanded\expandafter{\ekdl@sep}\fi
922      }%
923    }%
924    {%
925      \edef\lem@app{%
926        % \hskip .75em
927        \ifekd@mapps
928        \ifbool{subsq@unit@\ekdan@type}%
929        {\ekd@munit@delim}{}%
930        \else%
931        \ifsubsq@unit\unexpanded\expandafter{\ekd@unit@delim}\fi%
```

```
932        \fi%
933        \unless\ifekdl@nonum\current@ref\fi%\hskip .25em
934        \ifdefined\ekdlr@alt%
935          \ifdefined\ekdlr@pre%
936            \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
937          \ifbool{ekd@lang@pkg}%
938          {{\unexpanded\expandafter{\ekd@lemmastyle}%
939              \noexpand\selectlanguage{\app@lang}%
940              \unexpanded\expandafter{\ekdlr@alt}}}%
941          {\unexpanded\expandafter{\ekd@lemmastyle}%
942            \unexpanded\expandafter{\ekdlr@alt}}%
943          \ifdefined\ekdlr@post%
944            \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
945        \else
946          \ifdefined\ekdlr@pre%
947            \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
948          \ifbool{ekd@lang@pkg}%
949          {{\unexpanded\expandafter{\ekd@lemmastyle}%
950              \noexpand\selectlanguage{\app@lang}%
951              \unexpanded{#2}}}{%
952            {\unexpanded\expandafter{\ekd@lemmastyle}\unexpanded{#2}}}%
953          \ifdefined\ekdlr@post%
954            \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
955        \fi
956        \ifdefined\ekdlr@prewit%
957          \space\unexpanded\expandafter{\ekdlr@prewit}\space\else\fi
958        \ifdefined\ekdlr@wit\space\getsiglum{\ekdlr@wit}\else\fi
959        \ifdefined\ekdlr@source\space\getsiglum{\ekdlr@source}\else\fi
960        \ifdefined\ekdlr@resp\space\getsiglum{\ekdlr@resp}\else\fi
961        \ifdefined\ekdlr@postwit%
962          \space\unexpanded\expandafter{\ekdlr@postwit}\else\fi
963        \ifekdl@nosep\else\unexpanded\expandafter{\ekdl@sep}\fi
964      }%
965    }%
966    \fi%
967    \ifekd@mapps%
968    \append@ln@app[\ekdan@type]{\lem@app}%
969    \else%
970    \append@ln@app{\lem@app}%
971    \fi%
972    \egroup%
973    \ekd@isinlemfalse%
974    \subsq@unittrue%
975  }
```

\rdg   \rdg[⟨*options*⟩]{⟨*variant reading*⟩} inserts ⟨*variant reading*⟩ in the second part of the en-
        try, after the lemma text and the separator, in the apparatus criticus. This command accepts
        the optional key-value arguments defined above. This command sets \ifekd@subsq@rdg
        to true, which instructs ekdosis that "subseparators" may be used for subsequent entries.

```
976  \newif\ifekd@subsq@rdg
977  \NewDocumentCommand{\rdg}{O{} m}{%
978    \bgroup%
979    \ekvset{rdg}{#1}%
980    \ekd@test@lang
981    % \ifekdr@nordg\append@app{}\else% do we need \append@app{} here? If
```

```
982  %                                      % so, keep in mind \ifekd@mapps,
983  %                                      like so:
984  \ifekdr@nordg%
985     \ifekd@mapps%
986        \append@app[\ekdan@type]{}%
987     \else%
988     \append@app{}%
989     \fi%
990  \else%
991  \ifbool{al@rlmode}{%
992     \edef\rdg@app{%
993        \ifekd@subsq@rdg
994           \unless\ifekdr@nosubsep\unexpanded\expandafter{\ekdr@subsep}\fi
995        \fi
996        \ifdefined\ekdlr@alt%
997           \ifdefined\ekdlr@post%
998              \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
999              {\textdir TRT\unexpanded\expandafter{\ekd@readingstyle}%
1000                 \unexpanded\expandafter{\ekdlr@alt}}%
1001           \ifdefined\ekdlr@pre%
1002              \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
1003        \else
1004           \ifdefined\ekdlr@post%
1005              \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
1006              {\textdir TRT\unexpanded\expandafter{\ekd@readingstyle}%
1007                 \unexpanded{#2}}%
1008           \ifdefined\ekdlr@pre%
1009              \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
1010        \fi
1011        \ifdefined\ekdlr@postwit%
1012           \space\unexpanded\expandafter{\ekdlr@postwit}\else\fi
1013        \ifdefined\ekdlr@resp\space\getsiglum{\ekdlr@resp}\else\fi
1014        \ifdefined\ekdlr@source\space\getsiglum{\ekdlr@source}\else\fi
1015        \ifdefined\ekdlr@wit\space\getsiglum{\ekdlr@wit}\else\fi
1016        \ifdefined\ekdlr@prewit%
1017           \space\unexpanded\expandafter{\ekdlr@prewit}\space\else\fi
1018     }%
1019  }%
1020  {%
1021     \edef\rdg@app{%
1022        \ifekd@subsq@rdg
1023           \unless\ifekdr@nosubsep\unexpanded\expandafter{\ekdr@subsep}\fi
1024        \fi
1025        \ifdefined\ekdlr@alt%
1026           \ifdefined\ekdlr@pre%
1027              \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
1028           \ifbool{ekd@lang@pkg}%
1029           {{\unexpanded\expandafter{\ekd@readingstyle}%
1030              \noexpand\selectlanguage{\app@lang}%
1031              \unexpanded\expandafter{\ekdlr@alt}}}%
1032           {\unexpanded\expandafter{\ekd@readingstyle}%
1033              \unexpanded\expandafter{\ekdlr@alt}}%
1034           \ifdefined\ekdlr@post%
1035              \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
1036        \else
```

```
1037        \ifdefined\ekdlr@pre%
1038          \space\unexpanded\expandafter{\ekdlr@pre}\space\else\fi
1039          \ifbool{ekd@lang@pkg}%
1040          {{\unexpanded\expandafter{\ekd@readingstyle}%
1041              \noexpand\selectlanguage{\app@lang}\unexpanded{#2}}}{%
1042            {\unexpanded\expandafter{\ekd@readingstyle}\unexpanded{#2}}}%
1043          \ifdefined\ekdlr@post%
1044            \space\unexpanded\expandafter{\ekdlr@post}\space\else\fi
1045        \fi
1046        \ifdefined\ekdlr@prewit%
1047          \space\unexpanded\expandafter{\ekdlr@prewit}\space\else\fi
1048        \ifdefined\ekdlr@wit\space\getsiglum{\ekdlr@wit}\else\fi
1049        \ifdefined\ekdlr@source\space\getsiglum{\ekdlr@source}\else\fi
1050        \ifdefined\ekdlr@resp\space\getsiglum{\ekdlr@resp}\else\fi
1051        \ifdefined\ekdlr@postwit%
1052            \space\unexpanded\expandafter{\ekdlr@postwit}\else\fi
1053    }%
1054  }%
1055  \ifekd@mapps
1056      \append@app[\ekdan@type]{\rdg@app}%
1057  \else
1058  \append@app{\rdg@app}%
1059  \fi
1060  \fi
1061  \egroup
1062  \ekd@subsq@rdgtrue
1063 }
```

Define keys to be used by the optional argument of `\note` when this command is found outside `\app`:—

```
1064 \newif\ifekdn@forcenum
1065 \ekvdefinekeys{note}{
1066   store type = \ekdan@type,
1067   store lem = \ekdn@lem,
1068   code labelb = \def\ekdn@labelb{#1},
1069   code labele = \def\ekdn@labele{#1},
1070   store sep = \ekdn@sep,
1071   bool nosep = \ifekdn@nosep,
1072   initial type = default,
1073   initial sep = \ekdsep,
1074   bool nonum = \ifekdn@nonum,
1075   noval num = \ekdn@forcenumtrue
1076 }
```

`\note@noapp` is used internally when a `\note` command is found outside `\app`. This command is mostly used to insert short comments or references to texts quoted or cited in the edition text to go into additional layers of the apparatus criticus, e.g. the *apparatus testium*. It accepts the optional key-value arguments just defined above. It must be noted that `labelb` must be specified; otherwise ekdosis will issue an error message.

```
1077 \NewDocumentCommand{\note@noapp}{O{} +m}{%
1078   \leavevmode
1079   \bgroup%
1080   \ekvset{note}{#1}%
1081   \ekd@test@lang
1082   \stepcounter{ekd@lab}%
1083   \zlabel{ekd:\theekd@lab}%
```

```
1084    \luadirect{ekdosis.storeabspg(
1085      \luastring{\zref@extract{ekd:\theekd@lab}{abspage}})}%
1086    \ifekd@state\add@apparatus\fi%
1087    \ifekd@mapps%
1088      \ifnum%
1089        \luadirect{tex.sprint(ekdosis.get_bagunits(\luastringO{\ekdan@type}))}
1090        = 1
1091        \boolfalse{subsq@unit@\ekdan@type}%
1092      \fi%
1093    \luadirect{ekdosis.increment_bagunits(\luastringO{\ekdan@type})}%
1094      \def\ekd@munit@delim{%
1095        \luadirect{tex.sprint(ekdosis.getappdelim(\luastringO{\ekdan@type}))}}%
1096      \luadirect{tex.sprint(ekdosis.limit_bagunits(\luastringO{\ekdan@type}))}%
1097    \fi%
1098    \ifdefined\ekdn@labelb%
1099      \luadirect{tex.sprint(ekdosis.setnotelab(\luastringO{\ekdn@labelb}))}%
1100      \ifdefined\ekdn@labele\else\def\ekdn@labele{\ekdn@labelb}\fi%
1101    \else\PackageError{ekdosis}{missing labelb}{`labelb' must be
1102      set.}\fi%
1103    \ifbool{al@rlmode}%
1104    {\edef\note@contents{%
1105        % \hskip .75em
1106        \ifekd@mapps
1107          \ifbool{subsq@unit@\ekdan@type}%
1108          {\ekd@munit@delim}{}%
1109        \else%
1110          \ifsubsq@unit\unexpanded\expandafter{\ekd@unit@delim}\fi%
1111        \fi%
1112        \unless\ifekdn@nonum\current@ref@arg{\ekdn@labelb}{\ekdn@labele}\fi%\hskip .25em
1113        \ifdefined\ekdn@lem%
1114        {\textdir TRT\unexpanded\expandafter{\ekd@lemmastyle}%
1115          \unexpanded\expandafter{\ekdn@lem}}%
1116          \unless\ifekdn@nosep
1117          \unexpanded\expandafter{\ekdn@sep}\fi
1118          \else\fi%
1119            {\textdir TRT\unexpanded{#2}}}}%
1120    {\edef\note@contents{%
1121        % \hskip .75em
1122        \ifekd@mapps
1123          \ifbool{subsq@unit@\ekdan@type}%
1124          {\ekd@munit@delim}{}%
1125        \else%
1126          \ifsubsq@unit\unexpanded\expandafter{\ekd@unit@delim}\fi%
1127        \fi%
1128        \unless\ifekdn@nonum\current@ref@arg{\ekdn@labelb}{\ekdn@labele}\fi%\hskip .25em
1129        \ifdefined\ekdn@lem
1130          \ifbool{ekd@lang@pkg}%
1131          {{\unexpanded\expandafter{\ekd@lemmastyle}%
1132              \noexpand\selectlanguage{\app@lang}%
1133                \unexpanded\expandafter{\ekdn@lem}}}%
1134            {\unexpanded\expandafter{\ekd@lemmastyle}%
1135              \unexpanded\expandafter{\ekdn@lem}}%
1136            \unless\ifekdn@nosep
1137            \unexpanded\expandafter{\ekdn@sep}\fi
1138            \else\fi%
```

```
1139            \ifbool{ekd@lang@pkg}%
1140              {{\noexpand\selectlanguage{\app@note@lang}\unexpanded{#2}}}{%
1141                {\unexpanded{#2}}}}}%
1142      \ifekd@mapps%
1143      \unconditional@appin[\ekdan@type]{\note@contents}%
1144      \else%
1145      \unconditional@appin{\note@contents}%
1146      \fi%
1147        \luadirect{ekdosis.setprevnotelab(\luastringO{\ekdn@labelb})}%
1148      \egroup
1149      \subsq@unittrue
1150      \ignorespaces
1151 }
```

Define keys to be used by the optional argument of `\note` when this command is found inside `\app`:—

```
1152 \ekvdefinekeys{ekd@note}{
1153   store pre = \pre@value,
1154   store post = \post@value,
1155   nmeta sep = {post=\ekdsep},
1156   nmeta subsep = {pre=\ekdsubsep}
1157 }
```

The following three commands, `\note@app`, `\ekd@note` and `\ekd@note@star` are used internally when a `\note` command is found inside `\app`. These commands are used to insert short comments after the lemma text or after any variant reading in the apparatus criticus. `\note@app` and subsequently `\ekd@note` and `\ekd@note@star` accept the optional key-value arguments just defined above.

```
1158 \NewDocumentCommand{\ekd@note}{O{} m}{%
1159   \bgroup%
1160   \ekvset{ekd@note}{#1}%
1161   \edef\note@contents{%
1162     \ekvifdefinedNoVal{ekd@note}{pre}{}{%
1163       \unexpanded\expandafter{\pre@value}}%
1164     {\unexpanded{#2}}%
1165     \ekvifdefinedNoVal{ekd@note}{post}{}{%
1166       \unexpanded\expandafter{\post@value}}%
1167   }%
1168   \ifekd@mapps%
1169   \append@app[\ekdan@type]{\note@contents}%
1170   \else%
1171   \append@app{\note@contents}%
1172   \fi%
1173   \egroup%
1174 }
1175 \NewDocumentCommand{\ekd@note@star}{O{} m}{%
1176   \bgroup
1177   \ekvset{ekd@note}{#1}%
1178   \edef\note@contents{%
1179     \ekvifdefinedNoVal{ekd@note}{pre}{}{%
1180       \unexpanded\expandafter{\pre@value}}%
1181     \if@pkg@parnotes
1182       \unskip\noexpand\parnote{\unexpanded{#2}}%
1183     \else
1184       \unskip\noexpand\footnote{\unexpanded{#2}}%
1185     \fi
```

```
1186     \ekvifdefinedNoVal{ekd@note}{post}{}{%
1187        \unexpanded\expandafter{\post@value}}%
1188    }%
1189    \ifekd@mapps
1190        \append@app[\ekdan@type]{\note@contents}%
1191    \else
1192        \append@app{\note@contents}%
1193    \fi
1194    \egroup
1195 }
1196 \NewDocumentCommand{\note@app}{s O{} +m}{%
1197    \ifbool{al@rlmode}{%
1198        \IfBooleanTF{#1}{\ekd@note@star[#2]{%
1199                {\textdir TRT#3}}}
1200        {\ekd@note[#2]{{\textdir TRT#3}}}%
1201    }{%
1202        \IfBooleanTF{#1}{\ekd@note@star[#2]{#3}}
1203        {\ekd@note[#2]{#3}}%
1204    }%
1205 }
```

\note   Finally, `\note` is a simple command designed to check whether `\note` itself is called inside or outside `\app`. Then, unless it is found inside `\lem`, it calls `\note@app` in the former case and `\note@noapp` in the latter case:—

```
1206 \NewDocumentCommand{\note}{s O{} +m}{%
1207    \ifekd@state%
1208        \ifekd@isinapp%
1209            \ifekd@isinlem%
1210                \note@noapp[#2]{#3}%
1211            \else%
1212                \IfBooleanTF{#1}{\note@app*[#2]{#3}}{\note@app[#2]{#3}}%
1213            \fi%
1214        \else%
1215            \note@noapp[#2]{#3}%
1216        \fi%
1217    \fi%
1218 }
```

Emendations and Conjectures   Here follows the `key-value` options to be used by `\SetCritSymbols` below:—

```
1219 \ekvdefinekeys{ekd@corr}{
1220    store suppbegin = \suppb@value,
1221    store suppend = \suppe@value,
1222    store delbegin = \delb@value,
1223    store delend = \dele@value,
1224    store sicbegin = \sicb@value,
1225    store sicend = \sice@value,
1226    store gapmark = \gapm@value,
1227    initial suppbegin = \ifbool{al@rlmode}{>}{<},
1228    initial suppend = \ifbool{al@rlmode}{<}{>},
1229    initial delbegin = \ifbool{al@rlmode}{\}}{\{},
1230    initial delend = \ifbool{al@rlmode}{\{}{\}},
1231    initial sicbegin = \dag,
1232    initial sicend = \dag,
1233    initial gapmark = ***,
```

```
1234   bool keepinapp = \ifekd@keepinapp
1235 }
```

\supplied \supplied{⟨*text*⟩} takes as mandatory argument the text added or supplied by conjecture.

```
1236 \NewDocumentCommand{\supplied}{m}{%
1237   \ifekd@inside@app
1238     \ifekd@keepinapp
1239       \suppb@value #1\suppe@value
1240     \else
1241       #1%
1242     \fi
1243   \else
1244     \suppb@value #1\suppe@value
1245   \fi
1246 }
```

\surplus \surplus{⟨*text*⟩} takes as mandatory argument the text considered by the editor to be inauthentic, but nevertheless retained between braces in the edition text as it is transmitted by all witnesses.

```
1247 \NewDocumentCommand{\surplus}{m}{%
1248   \ifekd@inside@app
1249     \ifekd@keepinapp
1250       \delb@value #1\dele@value
1251     \else
1252       #1%
1253     \fi
1254   \else
1255     \delb@value #1\dele@value
1256   \fi
1257 }
```

\sic \sic{⟨*text*⟩} takes as mandatory argument the text deemed by the editor to be readable but not understandable. \sic insert ⟨*text*⟩ between cruces while \sic* prints only one crux before ⟨*text*⟩.

```
1258 \NewDocumentCommand{\sic}{s m}{%
1259   \ifekd@inside@app
1260     \ifekd@keepinapp
1261       \IfBooleanTF{#1}
1262         {\sicb@value #2}
1263         {\sicb@value #2\sice@value}%
1264     \else
1265       #2%
1266     \fi
1267   \else
1268     \IfBooleanTF{#1}
1269       {\sicb@value #2}
1270       {\sicb@value #2\sice@value}%
1271   \fi
1272 }
```

\gap \gap{⟨*options*⟩} indicates that some amount of text has fallen away from the entire tradition. It takes as mandatory argument a comma-separated list of options that can be used to further specify the reason for omission, the unit of measurement, the quantity and extent.

```
1273 \NewDocumentCommand{\gap}{m}{%
1274   \gapm@value
```

```
1275 }
```

\SetCritSymbols{⟨*csv list of options*⟩} is used to change the symbols that ekdosis uses by default for representing emendations, lacunae, omissions, gaps and editorial deletions.

```
1276 \NewDocumentCommand{\SetCritSymbols}{m}{
1277   \ekvset{ekd@corr}{#1}
1278 }
```

\apparatus is used internally by ekdosis to print the apparatus at the bottom of pages. Therefore, it is not documented, but this may change in the future for it will be possible to have apparatuses printed at other places.

```
1279 \NewDocumentCommand{\apparatus}{}{%
1280   \luadirect{tex.sprint(ekdosis.appout())}}
```

The following two commands call Lua functions to check whether an apparatus should be printed on a given page and to store the current column id.

```
1281 \NewDocumentCommand{\test@apparatus}{}{%
1282   \luadirect{tex.sprint(ekdosis.testapparatus())}}
1283 \NewDocumentCommand{\ekd@storecol}{}{%
1284   \luadirect{ekdosis.storecurcol(\luastring{\thecolumn})}%
1285 }
```

Start and stop ekdosis:

```
1286 \NewDocumentCommand{\EkdosisOn}{}{%
1287   \ekd@statetrue}
1288 \NewDocumentCommand{\EkdosisOff}{}{%
1289   \ekd@statefalse%
1290 }
```

Neutralize unwanted commands provided by lineno within the ekdosis environment:—

```
1291 \def\ekd@setlineno{%
1292   \let\setpagewiselinenumbers\relax%
1293   \let\pagewiselinenumbers\relax%
1294   \let\endpagewiselinenumbers\relax%
1295   \let\runningpagewiselinenumbers\relax%
1296   \let\realpagewiselinenumbers\relax%
1297 }
```

Finally comes the ekdosis environment meant to receive the edition text equipped with an apparatus criticus. This environment collects its contents and delivers it to Lua functions if a TEI xml output file be desired.

```
1298 \NewDocumentEnvironment{ekdosis}{+b}{%
1299   \ekd@setlineno%
1300   \runninglinenumbers
1301     \EkdosisOn#1}{%
1302     \EkdosisOff
1303   \endrunninglinenumbers%
1304   \iftei@export
1305   \luadirect{ekdosis.exporttei(\luastringN{\par #1\par })}\fi}
```

Alignment What follows is to arrange texts in parallel columns either on single pages or on facing pages.

Define keys to be used by the alignment environment:—

```
1306 \ekvdefinekeys{ekd@align}{
1307   store tcols = \tcols@num,
```

```
1308    store lcols = \lcols@num,
1309    store texts = \texts@value,
1310    store apparatus = \apparatus@value,
1311    bool paired = \ifekd@paired,
1312    choice lineation = {page = \ekd@pagelineationtrue,
1313                        document = \ekd@pagelineationfalse},
1314    unknown-choice lineation = \PackageError{ekdosis}{unknown
1315      lineation=#1}{`lineation' must be either `page' or `document'.},
1316    choice segmentation = {auto = \def\segmentation@val{auto},
1317                           noauto = \def\segmentation@val{noauto}},
1318    unknown-choice segmentation = \PackageError{ekdosis}{unknown
1319      segmentation=#1}{`segmentation' must be either `auto' or
1320      `noauto'.},
1321    bool flush = \ifekd@flushapp,
1322    initial tcols = 2,
1323    initial lcols = 1,
1324    initial texts = edition;translation,
1325    initial apparatus = edition,
1326    default segmentation = auto
1327 }
```

\SetAlignment \SetAlignment{⟨*settings*⟩} can be used either in the preamble or at any point of the document to set or modify the keys-value settings just defined above.

```
1328 \NewDocumentCommand{\SetAlignment}{m}{
1329   \ekvset{ekd@align}{#1}
1330 }
```

Patch paracol to insert a hook in \pcol@nextpage. This hook is used to reset line numbers on new pages.

```
1331 \patchcmd{\pcol@nextpage}{%
1332   \endgroup}{%
1333   \ifekd@pagelineation\resetlinenumber\fi
1334   \endgroup}{}{}
```

\EkdosisColStart and \EkdosisColStop initialize columns meant to receive edition texts. These commands are used internally by ekdosis.

```
1335 \NewDocumentCommand{\EkdosisColStart}{}{%
1336   \ekd@setlineno%
1337   \runninglinenumbers
1338   \ekd@storecol%
1339   \stepcounter{ekd@lab}%
1340   \zlabel{ekd:\theekd@lab}%
1341   \luadirect{%
1342     ekdosis.storeabspg(\luastring{\zref@extract{ekd:\theekd@lab}{abspage}},
1343     "pg_i")}%
1344   \ifekd@pagelineation
1345     \luadirect{tex.sprint(ekdosis.checkresetlineno())}
1346   \fi
1347 }
1348 \NewDocumentCommand{\EkdosisColStop}{}{%
1349   \stepcounter{ekd@lab}%
1350   \zlabel{ekd:\theekd@lab}%
1351   \luadirect{%
1352     ekdosis.storeabspg(\luastring{\zref@extract{ekd:\theekd@lab}{abspage}},
1353     "pg_ii")}%
1354   \endrunninglinenumbers%
```

```
1355 }
```

alignment `\begin{alignment}[⟨options⟩]...\end{alignment}` can be used as it is provided to type-
set a standard critical edition text on the left-hand pages accompanied with a translation on
the right-hand pages. To that effect, it provides by default two new environments, `edition`
and `translation`, to be used to typeset both texts. (Either whole texts or texts entered
by paragraphs alternately.) The optional argument of `alignment` accepts the exact same
key-value options as `\SetAlignment` described above. One may contrast these options
with those accepted by `\SetAlignment` as "local settings".

```
1356 \NewDocumentEnvironment{alignment}{O{}}
1357 {%
1358   \ekvset{ekd@align}{#1}%
1359   \luadirect{ekdosis.mkenvdata(
1360     \luastring{\texts@value},
1361     "texts"
1362     )}
1363   \ifekd@flushapp
1364     \luadirect{ekdosis.newalignment("set")}
1365   \fi
1366   \luadirect{ekdosis.mkenvdata(
1367     \luastring{\apparatus@value}, "apparatus"
1368     )}
1369   \setrunninglinenumbers
1370   \luadirect{tex.sprint(ekdosis.mkenv())}
1371   \ifekd@paired
1372   \begin{paracol}[\lcols@num]{\tcols@num}
1373   \else
1374   \begin{paracol}[\lcols@num]*{\tcols@num}
1375   \fi
1376   }
1377   {\end{paracol}
1378   \iftei@export\luadirect{ekdosis.export_coldata_totei()}\fi
1379   \ifekd@flushapp
1380     \luadirect{ekdosis.newalignment("reset")}
1381   \fi
1382   \luadirect{ekdosis.flushenvdata()}
1383   \luadirect{ekdosis.flushcolnums()}
1384   }
```

Headers and Footers   ekdosis provides a mechanism of its own for headers and footers as
follows. Most of it is handled by Lua functions.

\ekd@storemark   `\ekd@storemark` is used internally by the `mark` optional argument of `\ekddiv` described
below to store marks to be printed at specific places in headers or footers.

```
1385 \NewDocumentCommand{\ekd@storemark}{m}{%
1386   \stepcounter{ekd@lab}%
1387   \label{ekd:\theekd@lab}%
1388   \luadirect{ekdosis.storehfmark(
1389     \luastring{\getpagerefnumber{ekd:\theekd@lab}},
1390     \luastringN{#1})}%
1391 }
```

\endmark   By default, `\ekdmark` described below prints the first mark that is emitted on a given page
and ignores the mark corresponding to any portion of text that may be printed between the

top of the page and the point where the first mark is called. `\endmark` is an argument-less command that can be used just at the end of that portion of text to instruct **ekdosis** to print the last-emitted mark of the preceding page instead of the first-emitted mark of the current page.

```
1392 \NewDocumentCommand{\endmark}{}{%
1393   \stepcounter{ekd@lab}%
1394   \label{ekd:\theekd@lab}%
1395   \luadirect{ekdosis.storehfmark(
1396     \luastring{\getpagerefnumber{ekd:\theekd@lab}},
1397     "", "endmk")}%
1398   \ifdefined\xspace\xspace\fi
1399 }
```

\edkmark   `\ekdmark` is an argument-less command called in commands used to make headers and footers where the marks stored by means of the `mark` optional argument of `\ekddiv` are to be printed.

```
1400 \NewDocumentCommand{\ekdmark}{}{%
1401   \luadirect{tex.sprint(ekdosis.gethfmark(\luastring{\thepage}))}%
1402 }
```

\ekdprintmark   `\ekdprintmark{⟨selector⟩}{⟨signpost⟩}` The signposts printed in headers and footers must be passed as second argument of `\ekdprintmark` so that **ekdosis** can remove them on pages where printing them is not desirable. ⟨selector⟩ refers to three symbolic letters where the first can be either `H` or `F`—for header or footer—, the second `E` or `O`—for odd or even—and the third `L`, `C` or `R`—for left, center or right:—

```
1403 \ekvdefinekeys{ekd@marks}{
1404   choice mark = {HEL = \def\ekd@mk{HEL},
1405     HEC = \def\ekd@mk{HEC},
1406     HER = \def\ekd@mk{HER},
1407     HOL = \def\ekd@mk{HOL},
1408     HOC = \def\ekd@mk{HOC},
1409     HOR = \def\ekd@mk{HOR},
1410     FEL = \def\ekd@mk{FEL},
1411     FEC = \def\ekd@mk{FEC},
1412     FEL = \def\ekd@mk{FER},
1413     FOL = \def\ekd@mk{FOL},
1414     FOC = \def\ekd@mk{FOC},
1415     FOL = \def\ekd@mk{FOR}},
1416   unknown-choice mark = \PackageError{ekdosis}{unknown mark=#1}{`mark'
1417     must be either `HEL', `HEC', `HER', `HOL', `HOC', `HOR', `FEL',
1418     \MessageBreak `FEC', `FER', `FOL', `FOC' or `FOR'.}
1419 }
1420 \NewDocumentCommand{\ekdprintmark}{m m}{%
1421   \bgroup
1422   \ekvset{ekd@marks}{mark = #1}%
1423   \luadirect{tex.sprint(ekdosis.printmark(\luastringN{#2},
1424     \luastringO{\ekd@mk}))}%
1425   \egroup
1426 }
```

\ekdnofhmarks   Once the signposts are marked with `\ekdprintmark`, `\ekdnohfmarks` has the same effect as the LaTeX standard command `\thispagestyle{empty}`.

```
1427 \NewDocumentCommand{\ekdnohfmark}{}{%
1428   \luadirect{ekdosis.nohfmark()}%
1429 }
```

\ekdresethfmarks \ekdresethfmarks can be used in rare cases when it is needed to reset headers and footers to their original, viz. printable state.

```
1430 \NewDocumentCommand{\ekdresethfmarks}{}{%
1431   \luadirect{ekdosis.resethfmark()}%
1432 }
```

Divisions of the Body ekdosis can convert \book, \part, \chapter, \section, \subsection and \subsubsection into corresponding TEI 'numbered' <div$_n$> elements, where $1 \le n \le 6$.

\MkBodyDivs \MkBodyDivs is used to let ekdosis know which sectional commands are actually being used in an edition text. This command takes six mandatory arguments. For example, if \section and \subsection are the only sectional commands being used, \MkBodyDivs{section}{subsection}{}{}{}{} will have \section and \subsection converted into <div1> and <div2> respectively.

```
1433 \NewDocumentCommand{\MkBodyDivs}{mmmmmm}{
1434   \luadirect{ekdosis.mkdivdepths(
1435     \luastringN{#1},
1436     \luastringN{#2},
1437     \luastringN{#3},
1438     \luastringN{#4},
1439     \luastringN{#5},
1440     \luastringN{#6}
1441     )
1442   }
1443 }
```

Divisions specific to ekdosis. Define keys to be used by \ekddiv:—

```
1444 \ekvdefinekeys{ekd@div}{
1445   code type = \def\type@value{#1},
1446   code n = \def\n@value{#1},
1447   code head = \def\head@value{#1},
1448   code barehead = \def\barehead@value{#1},
1449   store depth = \depth@value,
1450   code mark = \ekd@storemark{#1},
1451   choice toc = {book = \def\toc@value{book},
1452                 part = \def\toc@value{part},
1453                 chapter = \def\toc@value{chapter},
1454                 section = \def\toc@value{section},
1455                 subsection = \def\toc@value{subsection},
1456                 subsubsection = \def\toc@value{subsubsection},
1457                 paragraph = \def\toc@value{paragraph},
1458                 subparagraph = \def\toc@value{subparagraph}},
1459   unknown-choice toc = \PackageError{ekdosis}{unknown toc=#1}{`toc'
1460     must be either `book', `part', `chapter', `section', `subsection',
1461     \MessageBreak `subsubsection', `paragraph' or `subparagraph'.},
1462   initial depth = 1
1463 }
```

\FormatDiv \FormatDiv{⟨n⟩}{⟨code before⟩}{⟨code after⟩} is used to lay out the heading of the title. It takes three mandatory arguments: n, namely the number referring to the particular depth of the division, and then some LaTeX formatting commands to go before and after the heading itself:—

```
1464 \NewDocumentCommand{\FormatDiv}{m m m}{
```

```
1465    \luadirect{ekdosis.fmtdiv(\luastring{#1},
1466        \luastringN{#2},
1467        \luastringN{#3})}
1468 }
```

\ekd@getfmtdiv gets the formatting commands that have been stored by **\FormatDiv**.

```
1469 \NewDocumentCommand{\ekd@getfmtdiv}{m m}{%
1470    \luadirect{tex.sprint(ekdosis.getfmtdiv(\luastringO{#1},
1471        \luastringN{#2}))}%
1472 }
```

\ekddiv   **\ekddiv{**⟨*key-value arguments*⟩**}** is the standard command provided by ekdosis to meet the requirements of classical and literary texts the divisions of which depend on many different received traditions. It takes one mandatory argument in which the key-value arguments defined above are accepted, and converts the divisions into TEI 'un-numbered' **<div>** elements.

```
1473 \NewDocumentCommand{\ekddiv}{m}{
1474    \begingroup
1475    \ekvset{ekd@div}{#1}%
1476    \ifdefined\head@value
1477      \bgroup
1478        \ekd@getfmtdiv{\depth@value}{b}%
1479        \head@value
1480        \ekd@getfmtdiv{\depth@value}{e}%
1481      \egroup
1482      \ifdefined\toc@value
1483        \ltx@ifpackageloaded{hyperref}{\phantomsection}{}%
1484          \ifdefined\barehead@value
1485            \addcontentsline{toc}{\toc@value}{\barehead@value}%
1486          \else
1487            \addcontentsline{toc}{\toc@value}{\head@value}%
1488          \fi
1489      \fi
1490    \fi
1491    \endgroup
1492 }
```

Poetry Settings

ekdverse   ekdverse provides an implementation of poetry lines. It is set to use either the lineno or the verse package depending on the value that is passed to the global option poetry.

\test@vpnum   **\test@vpnum** is used internally when ekdosis needs to know whether two subsequent lines are printed on the same page or not.

```
1493 \newif\ifekd@test@vpnum
1494 \newcounter{ekd@vpnum}
1495 \globalcounter{ekd@vpnum}
1496 \NewDocumentCommand{\test@vpnum}{}{%
1497    \ifekd@test@vpnum
1498      \edef\@tempa{\theekd@vpnum}%
1499      \stepcounter{ekd@vpnum}%
1500      \label{vpnum:\theekd@vpnum}%
1501      \ifnum
1502        \pdf@strcmp{\getpagerefnumber{vpnum:\@tempa}}%
1503          {\getpagerefnumber{vpnum:\theekd@vpnum}}
```

```
1504            = 0
1505         \else
1506            \resetvlinenumber
1507      \fi
1508   \else
1509   \label{vpnum:\theekd@vpnum}%
1510   \global\ekd@test@vpnumtrue
1511   \fi
1512 }
```

\\+ **\\+** comes in addition to the verse commands that are provided by the verse package. **\\+** causes a linebreak within a verse line. In contrast to **\\>**, the subsequent line is not indented and complies to any already defined indent pattern. **\@vscentercr** must be redefined accordingly.

```
1513 \ifboolexpr{bool {@pkg@poetry@verse} or bool {ekd@memoir@loaded}}
1514 {\newcommand{\@vsifplus}[1]{\@ifnextchar +{\@firstoftwo{#1}}}
1515   \renewcommand{\@vscentercr}{%
1516     \ifhmode \unskip\else \@nolnerr\fi
1517     \@vsifgt{\ifnum@brokenline\@vstypelinenum\fi\verselinebreak}{%
1518       \@vsifplus{\ifnum@brokenline\@vstypelinenum\fi\stepcounter{vslineno}%
1519         \par\@ifstar{\nobreak\@vsxcentercr}{%
1520           \@vsifbang{\@ifnextchar[ {\@vsicentercr}{}}{\@vsxcentercr}%
1521         }%
1522       }{%
1523         \@vstypelinenum
1524         \incr@vsline%
1525         \par\@ifstar{\nobreak\@vsxcentercr}{%
1526           \@vsifbang{\@ifnextchar[ {\@vsicentercr}{}}{\@vsxcentercr}%
1527         }%
1528       }%
1529     }%
1530   }
1531 }{}
```

A small patch is applied to the verse package, then **ekdverse** is defined:—

```
1532 \if@pkg@poetry@verse
1533 \patchcmd{\start@vsline}{%
1534   \ifaltindent}{%
1535   \ifekd@pagevlineation\test@vpnum\fi
1536   \ifaltindent}{}{}
1537 \ekvdefinekeys{ekd@verse}{
1538   dimen width = \vwidth@val,
1539   initial width = \linewidth,
1540   code type = \def\type@value{#1},
1541 }
1542 \ifekd@memoir@loaded
1543   \def\vlvnumfont{\normalfont\footnotesize}
1544   \def\verselinenumfont#1{\def\vlvnumfont{#1}}
1545 \else
1546   \verselinenumfont{\normalfont\footnotesize}
1547 \fi
1548 \setcounter{poemline}{1}
1549 \NewDocumentEnvironment{ekdverse}{!O{}}{%
1550   \ekvset{ekd@verse}{#1}%
1551   \if@continuous@vnum\setverselinenums{\thelinenumber}{0}\fi
```

127

```
1552    \nolinenumbers
1553    \let\linelabel\label
1554    \ifekd@memoir@loaded
1555      \refstepcounter{verse}%
1556    \else
1557      \stepcounter{verse@envctr}%
1558    \fi
1559    \addtocounter{poemline}{-1}\refstepcounter{poemline}%
1560    \setcounter{vslineno}{1}%
1561    \let\\=\@vscentercr
1562    \list{}{\itemsep \z@
1563            \itemindent  -\vindent%
1564            \listparindent\itemindent
1565            \parsep       \stanzaskip
1566            \setlength{\itemsep}{0pt}%
1567            \setlength{\topsep}{0pt}%
1568            \setlength{\partopsep}{0pt}%
1569            \ifdim\vwidth@val < \linewidth
1570              \rightmargin        \z@
1571              \setlength{\leftmargin}{\linewidth}%
1572              \addtolength{\leftmargin}{-\vwidth@val}%
1573              \addtolength{\leftmargin}{-0.5\leftmargin}%
1574            \else
1575              \rightmargin        \leftmargin
1576            \fi
1577            \addtolength{\leftmargin}{\vindent}}%
1578    \item[]\ifekd@pagevlineation\test@vpnum\fi%
1579 }
1580 {\endlist
1581    \if@continuous@vnum\resetlinenumber[\thepoemline]\fi}
```

Finally, this is the standard **verse** environment:—

```
1582 \else
1583 \newlength{\ekdverseindentlength}
1584 \setlength{\ekdverseindentlength}{\parindent}
1585 \NewDocumentEnvironment{ekdverse}{!O{\ekdverseindentlength}}{
1586   \begin{list}{}{%
1587       \setlength{\leftmargin}{#1}
1588       \setlength{\itemsep}{0pt}
1589       \setlength{\topsep}{0pt}
1590       \setlength{\partopsep}{0pt}
1591     }
1592   \item[]
1593   }{\end{list}}
1594 \fi
```

`\resetvlinenumber` This command is the equivalent of `\resetlinenumber` for lines of poetry. It takes an integer as optional argument, which is **1** by default.

```
1595 \NewDocumentCommand{\resetvlinenumber}{O{1}}{%
1596   \if@pkg@poetry@verse
1597   \setverselinenums{#1}{0}%
1598   \fi
1599 }
```

ekdstanza   **ekdstanza** is needed when lines are grouped into stanzas, which can be further named by means of the **type** optional argument:—

```
1600 \ekvdefinekeys{ekd@stanza}{
1601   code type = \def\type@value{#1}
1602 }
1603 \NewDocumentEnvironment{ekdstanza}{!O{}}{%
1604   \leavevmode\unskip
1605   \ekvset{ekd@stanza}{#1}%
1606   \ignorespaces
1607 }{}
```

ekdpar   When **autopar** is set to **false** by means of **\SetTEIxmlExport**, ekdpar—or any other environment set to be inserted within **<p>** elements—must be used so that **ekdosis** can be informed of paragraph boundaries.

```
1608 \NewDocumentEnvironment{ekdpar}{}{\par}{\par}
```

Configuration File   Finally, if a configuration file named **\jobname-ekd.cfg** can be found, this file is read and its contents loaded into the document preamble. This provides a convenient way to gather all the settings related to the critical edition in a separate file.

```
1609 \IfFileExists{\jobname-ekd.cfg}{\input{\jobname-ekd.cfg}}{}
```

19   Change History

20 Index

Numbers written in italic refer to the page where the corresponding entry is described; numbers underlined refer to the code line of the definition; numbers in roman refer to the code lines where the entry is used.

136